## ROOM FINISH SCHEDULE - THIRD LEVEL: MEDICAL OFFICES

| ROOM NO. | ROOM NAME | MATERIAL FLOOR | MATERIAL BASE | WALL NORTH | WALL EAST | WALL SOUTH | WALL WEST | CEILING MAT'L | CEILING HEIGHT | NO. | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | ELEVATOR | RT | * | * | * | * | * | * | * | 1 | *BY ELEVATOR COMPANY |
| 2 | ELEVATOR | RT | * | * | * | * | * | * | * | 2 | *BY ELEVATOR COMPANY |
| A | STAIR | RT | RS | PT | PT | PT | PT | | | A | RUBBER TREADS& RISERS |
| B | STAIR | RT | RS | PT | PT | PT | PT | | | B | RUBBER TREADS& RISERS |
| 3001 | VESTIBULE | WOM | PCT | PT | ALUM | PT/ALUM | PT | GWB-PT | 9'-0" | 3001 | |
| 3002 | LOBBY | PCT 1 &2 | WD | WDP/PT | WDP/PT | WDP/PT | WDP/PT | ACT/GWB-PT | 10'-0" | 3002 | |
| 3003 | W.C. STORAGE | CPT | RS | WP/PT | WP/PT | | WP/PT | GWB-PT | 8'-0" | 3003 | WALL PROTECTION BELOW CABINET |
| 3004 | W.C. STORAGE | CPT | RS | WP/PT | WP/PT | | WP/PT | GWB-PT | 8'-0" | 3004 | WALL PROTECTION BELOW CABINET |
| 3005 | LOBBY | PCT 1 &2 | WD | WDP/PT | WDP/PT | | WDP/PT | ACT/GWB-PT | 9'-0" | 3005 | |
| 3006 | STORAGE | VCT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3006 | |
| 3007 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3007 | |
| 3008 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3008 | |
| 3009 | BLOOD DRAW | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3009 | |
| 3009A | TEL/DATA | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3009A | |
| 3010 | BLOOD DRAW | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3010 | |
| 3011 | BLOOD DRAW | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3011 | |
| 3011A | STORAGE | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3011A | |
| 3012 | LAB LOBBY | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3012 | |
| 3013 | LAB CHECK-IN | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3013 | |
| 3014 | LAB PROCESS | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3014 | |
| 3014A | STORAGE | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3014A | |
| 3015 | PROTIME ROOM | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3015 | |
| 3016 | STORAGE | CONC | | | | | | EXP | | 3016 | |
| 3017 | WAITING | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 8'-8" | 3017 | |
| 3018 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3018 | |
| 3019 | CORRIDOR | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3019 | |
| 3020 | SOILED HOLDING | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3020 | |
| 3021 | EXAM/NURSE TRIAGE | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3021 | |
| 3022 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3022 | |
| 3023 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3023 | |
| 3024 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3024 | |
| 3025 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3025 | |
| 3026 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3026 | |
| 3027 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3027 | |
| 3028 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3028 | |
| 3029 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3029 | |
| 3030 | TEL/DATA | VCT | RS | PT | PT | PT | PT | EXP | | 3030 | |
| 3031 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3031 | |
| 3032 | CORRIDOR | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3032 | |
| 3033 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3033 | |
| 3034 | NURSE WORK | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3034 | |
| 3035 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3035 | |
| 3036 | ELECTRICAL | VCT | RS | PT | PT | PT | PT | EXP | | 3036 | |
| 3037 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3037 | |
| 3038 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3038 | |
| 3038A | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8-8" | 3038A | |
| 3039 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3039 | |
| 3040 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3040 | |
| 3041 | SHARED OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3041 | |
| 3042 | COFFEE ALCOVE | PCT-3 | PCT | PT | PT | PT | PT | ACT | 9'-0" | 3042 | |
| 3043 | ALCOVE | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 9'-0" | 3043 | |
| 3044 | CORRIDOR | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 8'-6" | 3044 | |
| 3045 | INPATIENT CONF/INFUSION | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3045 | |
| 3045A | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3045A | |
| 3046 | MNTL HEALTH CONSULT | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3046 | |
| 3047 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3047 | |
| 3048 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3048 | |
| 3049 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3049 | |
| 3051 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3051 | |
| 3052 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3052 | |
| 3053 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3053 | |
| 3053A | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3053A | |
| 3055 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3055 | |
| 3056 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-6" | 3056 | |
| 3057 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3057 | |
| 3058 | NURSE WORKROOM | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3058 | |
| 3058A | NURSE WORKROOM | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3058A | |
| 3059 | EXAM/NURSE TRIAGE | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3059 | |
| 3061 | CORRIDOR | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 8'-6" | 3061 | |
| 3062 | ALCOVE | CPT | RS | PT/WP | PT/WP | | PT/WP | GWB-PT | 8'-0" | 3062 | |
| 3063 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3063 | |
| 3064 | WAITING | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | GWB-PT | VARIES* | 3064 | |
| 3065 | ALCOVE | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 9'-0" | 3065 | |
| 3066 | CORRIDOR | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 8'-6" | 3066 | |
| 3067 | PROCEDURE ROOM | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3067 | |
| 3068 | EXAM/NURSE TRIAGE | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3068 | |
| 3069 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3069 | |
| 3071 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3071 | |
| 3073 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3073 | |
| 3074 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3074 | |
| 3075 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3075 | |
| 3076 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3076 | |
| 3078 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8-6" | 3078 | |
| 3079 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3079 | |
| 3081 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3081 | |
| 3082 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3082 | |
| 3083 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3083 | |
| 3084 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3084 | |
| 3085 | CORRIDOR | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 8'-6" | 3085 | |
| 3086 | SOILED HOLDING ROOM | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3086 | |
| 3087 | HOUSEKEEPING | SV-2 | ICB | FRP/PT-SG | FRP/PT-SG | FRP/PT-SG | FRP/PT-SG | ACT | 8'-8" | 3087 | |
| 3087A | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3087A | |
| 3088 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3088 | |
| 3089 | CORRIDOR | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 9'-0" | 3089 | |
| 3091 | ALCOVE | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 9'-0" | 3091 | |
| 3092 | CORRIDOR | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 8'-6" | 3092 | |
| 3093 | EQUIPMENT STORAGE/SUPPLY | VCT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3093 | |
| 3094 | HOUSE KEEPING | SV-2 | ICB | FRP/PT-SG | FRP/PT-SG | FRP/PT-SG | FRP/PT-SG | ACT | 8'-8" | 3094 | |
| 3095 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3095 | |
| 3096 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3096 | |
| 3097 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3097 | |
| 3099 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3099 | |
| 3101 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3101 | |
| 3102 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3102 | |
| 3103 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3103 | |
| 3105 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 9'-0" | 3105 | |
| 3106 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3106 | |
| 3107 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3107 | |
| 3108 | NURSE WORKROOM | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3108 | |
| 3108A | NURSE WORKROOM | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3108A | |
| 3109 | EXAM/NURSE TRIAGE | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3109 | |
| 3111 | CORRIDOR | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 8'-6" | 3111 | |
| 3112 | ALCOVE | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 8'-6" | 3112 | |
| 3113 | PROCEDURE ROOM | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3113 | |
| 3114 | WAITING | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | GWB-PT | VARIES | 3114 | |
| 3115 | ALCOVE | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 9'-0" | 3115 | |
| 3116 | CORRIDOR | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 8'-6" | 3116 | |
| 3117 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3117 | |
| 3118 | EXAM/NURSE TRIAGE | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3118 | |
| 3119 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3119 | |
| 3121 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3121 | |
| 3123 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3123 | |
| 3124 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3124 | |
| 3125 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3125 | |
| 3126 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3126 | |
| 3128 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3128 | |
| 3129 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3129 | |
| 3131 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3131 | |
| 3132 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3132 | |
| 3133 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3133 | |
| 3134 | STORAGE | VCT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3134 | |
| 3135 | CORRIDOR | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 8'-6" | 3135 | |
| 3136 | STORAGE | VCT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3136 | |
| 3137 | FLEX | VCT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3137 | |
| 3138 | WAITING | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | GWB-PT | VARIES | 3138 | |
| 3139 | ALCOVE | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 9'-0" | 3139 | |
| 3141 | CORRIDOR | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 8'-6" | 3141 | |
| 3142 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3142 | |
| 3143 | CORRIDOR | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 8'-6" | 3143 | |
| 3144 | ULTRASOUND | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3144 | |
| 3145 | RADIOLOGY/ULTRASOUND READING | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3145 | |
| 3146 | DEXA | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3146 | |
| 3148 | ALCOVE | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3148 | |
| 3149 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3149 | |
| 3150 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3150 | |
| 3151 | BREAK ROOM | VCT-P | RS | PT | PT | PT | PT | ACT | 9'-0" | 3151 | |
| 3152 | STAFF WOMEN | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3152 | |
| 3153 | STAFF MEN | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3153 | |
| 3154 | STAFF SHOWER | CT1 | CT | CT-2/CT-3 | CT-2/CT-3 | | CT-2/CT-3 | GWB-PT | 8'-6" | 3154 | |
| 3155 | CORRIDOR | CPT | RS | PT | PT | PT | PT | GWB-PT | 8'-0" | 3155 | |
| ACT | ACCOUSTICAL CEILING TILE | | | | | | | | | | |
| CP | CARPET | | | | | | | | | | |
| CPT | CARPET TILE | | | | | | | | | | |
| CR | CHAIR RAIL | | | | | | | | | | |
| EPT | EPOXY PAINT | | | | | | | | | | |

## ROOM FINISH SCHEDULE - THIRD LEVEL: MEDICAL OFFICES CONTINUED

| ROOM NO. | ROOM NAME | MATERIAL FLOOR | MATERIAL BASE | WALL NORTH | WALL EAST | WALL SOUTH | WALL WEST | CEILING MAT'L | CEILING HEIGHT | NO. | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 3156 | TECHNICIAN WORK AREA | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3156 | |
| 3157 | STAFF SHOWER | CT1 | CT | | CT-2/CT-3 | CT-2/CT-3 | CT-2/CT-3 | GWB-PT | 8'-6" | 3157 | |
| 3158 | XRAY | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | GWB-PT | 8'-6" | 3158 | |
| 3159 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3159 | |
| 3161 | WAITING | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3161 | |
| 3162 | XRAY DRESSING | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3162 | |
| 3163 | XRAY DRESSING | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3163 | |
| 3164 | XRAY | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | GWB-PT | 8'-6" | 3164 | |
| 3165 | MAMMOGRAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3165 | |
| 3166 | MAMMOGRAM GOWNED WAITING | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3166 | |
| 3167 | MAMMOGRAM DRESSING | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3167 | |
| 3168 | MAMMOGRAM DRESSING | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3168 | |
| 3169 | CORRIDOR | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 8'-6" | 3169 | |
| 3169A | ALCOVE | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | GWB-PT | 8'-0" | 3169A | |
| 3169B | ALCOVE | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | GWB-PT | 8'-0" | 3169B | |
| 3169C | ALCOVE | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | GWB-PT | 8'-0" | 3169C | |
| 3171 | REGISTRATION | CPT | RS | PT | PT | PT | PT | ACT | 9'-0" | 3171 | |
| 3172 | ALCOVE | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 9'-0" | 3172 | |
| 3173 | WORK AREA | CPT | RS | PT | PT | PT | PT | ACT | 9'-0" | 3173 | |
| 3174 | ALCOVE | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 9'-0" | 3174 | |
| 3176 | ALCOVE | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 9'-0" | 3176 | |
| 3178 | CORRIDOR | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 8'-6" | 3178 | |
| 3179 | REGISTRATION | CPT | RS | PT | PT | PT | PT | ACT | 9'-0" | 3179 | |
| 3181 | EXAM/NURSE TRIAGE | VP | RE | PT | PT | PT | PT | ACT | 9'-0" | 3181 | |
| 3182 | NURSE WORKROOM | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3182 | |
| 3183 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3183 | |
| 3184 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3184 | |
| 3185 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3185 | |
| 3186 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3186 | |
| 3187 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3187 | |
| 3188 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3188 | |
| 3191 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3191 | |
| 3192 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3192 | |
| 3193 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3193 | |
| 3194 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3194 | |
| 3195 | STORAGE | VCT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3195 | |
| 3196 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3196 | |
| 3197 | CORRIDOR | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 8'-6" | 3197 | |
| 3198 | EQUIPMENT STORAGE SUPPLY | VCT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3198 | |
| 3199 | WAITING | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | GWB-PT | VARIES | 3199 | |
| 3201 | ALCOVE | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 9'-0" | 3201 | |
| 3202 | CORRIDOR | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 9'-0" | 3202 | |
| 3203 | SOILED UTILITY | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3203 | |
| 3204 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3204 | |
| 3205 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3205 | |
| 3206 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3206 | |
| 3207 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3207 | |
| 3209 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3209 | |
| 3211 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3211 | |
| 3212 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3212 | |
| 3213 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3213 | |
| 3215 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3215 | |
| 3216 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3216 | |
| 3217 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3217 | |
| 3218 | NURSE WORKROOM | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3218 | |
| 3218A | NURSE WORKROOM | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3218A | |
| 3219 | EXAM/NURSE TRIAGE | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3219 | |
| 3221 | CORRIDOR | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 8'-6" | 3221 | |
| 3222 | SUPPLY | VCT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3222 | |
| 3223 | PROCEDURE ROOM | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3223 | |
| 3224 | WAITING | CPT | RS | PT/WP | PT | PT | PT | GWB-PT | VARIES | 3224 | |
| 3225 | ALCOVE | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 9'-0" | 3225 | |
| 3226 | CORRIDOR | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 8'-6" | 3226 | |
| 3227 | EXAM/NURSE TRIAGE | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3227 | |
| 3228 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3228 | |
| 3229 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3229 | |
| 3232 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3232 | |
| 3233 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3233 | |
| 3234 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3234 | |
| 3235 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3235 | |
| 3237 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3237 | |
| 3238 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3238 | |
| 3239 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3239 | |
| 3240 | OFFICE | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3240 | |
| 3241 | STORAGE | VCT | RS | PT | PT | PT | PT | ACT | 8-8" | 3241 | |
| 3242 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3242 | |
| 3243 | CORRIDOR | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 8'-6" | 3243 | |
| 3244 | PROCEDURE ROOM | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3244 | |
| 3245 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3245 | |
| 3246 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3246 | |
| 3247 | CORRIDOR | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 9'-0" | 3247 | |
| 3248 | ALCOVE | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 9'-0" | 3248 | |
| 3249 | CORRIDOR | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 8'-6" | 3249 | |
| 3251 | HOUSE KEEPING | SV-2 | ICB | FRP/PT-SG | FRP/PT-SG | FRP/PT-SG | FRP/PT-SG | ACT | 8'-8" | 3251 | |
| 3252 | STRESS/ECHO ROOM | SV-1/SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3252 | |
| 3253 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3253 | |
| 3254 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3254 | |
| 3255 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3255 | |
| 3256 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3256 | |
| 3257 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3257 | |
| 3259 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3259 | |
| 3261 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3261 | |
| 3262 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8-8" | 3262 | |
| 3263 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3263 | |
| 3265 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3265 | |
| 3266 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3266 | |
| 3267 | NURSE WORKROOM | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3267 | |
| 3267A | NURSE WORKROOM | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3267A | |
| 3268 | EXAM/NURSE TRIAGE | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3268 | |
| 3269 | CORRIDOR | CPT | RS | PT/WP | PT | PT/WP | PT | ACT | 8'-6" | 3269 | |
| 3271 | ECHO | SV-2 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3271 | |
| 3272 | WAITING | CPT | RS | PT/WP | PT | PT | PT | GWB-PT | VARIES | 3272 | |
| 3273 | ALCOVE | CPT | RS | PT/WP | PT/WP | PT/WP | PT/WP | ACT | 9'-0" | 3273 | |
| 3274 | CORRIDOR | CPT | RS | PT/WP | PT/WP | | PT/WP | ACT | 8'-6" | 3274 | |
| 3274A | ALCOVE | CPT | RS | PT/WP | | PT/WP | PT/WP | GWB-PT | 8'-0" | 3274A | |
| 3275 | ECHO READ | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3275 | |
| 3276 | HEALTH ED OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3276 | |
| 3277 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3277 | |
| 3278 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3278 | |
| 3279 | STORAGE | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3279 | |
| 3282 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3282 | |
| 3283 | TEAM ROOM | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3283 | |
| 3284 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3284 | |
| 3285 | NURSE STATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-6" | 3285 | |
| 3286 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3286 | |
| 3287 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3287 | |
| 3288 | EXAM | SV-1 | RS | PT | PT | PT | PT | ACT | 8'-8" | 3288 | |
| 3289 | MNTL HEALTH CONSULTANT | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3289 | |
| 3291 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3291 | |
| 3292 | INPATIENT CONF/INFUSION | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3292 | |
| 3293 | COFFEE ALCOVE | PCT-3 | PCT | PT | PT | PT | PT | ACT | 9'-0" | 3293 | |
| 3294 | VESTIBULE | WOM | RS | PT | PT | PT | PT | ACT | 8'-8" | 3294 | |
| 3295 | WAITING | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3295 | |
| 3296 | PATIENT SERVICES MANAGER | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3296 | |
| 3297 | PRACTICE DIRECTOR OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3297 | |
| 3298 | OPEN OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3298 | |
| 3299 | COATS | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3299 | |
| 3301 | TOILET | SV-2 | ICB | PT-SG | PT-SG | PT-SG | PT-SG | ACT | 8'-8" | 3301 | |
| 3302 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3302 | |
| 3303 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3303 | |
| 3305 | CORRIDOR | CP | RS | | PT | PT | PT | ACT | 8'-8" | 3305 | |
| 3307 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3307 | |
| 3308 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3308 | |
| 3309 | OFFICE | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3309 | |
| 3311 | CONF ROOM A | CP | RS | PT | PT | PT | PT | ACT | 9'-0" | 3311 | |
| 3312 | CONF ROOM B | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3312 | |
| 3313 | CONF ROOM C | CP | RS | PT | PT | PT | PT | ACT | 8'-8" | 3313 | |
| 3314 | ELECTRICAL | VCT | RS | PT | PT | PT | PT | EXP-PT | | 3314 | |
| 3315 | IT SET-UP | VCT | RS | PT | PT | PT | PT | EXP-PT | | 3315 | |
| 3316 | IT/PHONE | VCT | RS | PT | PT | PT | PT | EXP-PT | | 3316 | |
| 3317 | STORAGE | CONC | | PT | PT | PT | PT | ACT | 8'-8" | 3317 | |
| 3318 | PHARMACY | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3318 | *SOFFITS=8'-0" ACT=9'-0" |
| 3319 | PHARMACY MANAGER | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3319 | |
| 3321 | DRUG CONSULTATION | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3321 | |
| 3322 | PHARMACY WAITING | CPT | RS | PT | PT | PT | PT | ACT | 8'-8" | 3322 | |
| | FINISH ABBREVIATIONS | | | | | | | | | | |
| ACT | ACCOUSTICAL CEILING TILE | | | | | | | | | | |
| CK | CORK | | | | | | | | | | |
| CP | CARPET | | | | | | | | | | |
| CPT | CARPET TILE | | | | | | | | | | |

## ROOM FINISH SCHEDULE - FIRST LEVEL: PARKING

| ROOM NO. | ROOM NAME | MATERIAL FLOOR | MATERIAL BASE | WALL NORTH | WALL EAST | WALL SOUTH | WALL WEST | CEILING MAT'L | CEILING HEIGHT | NO. | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | ELEVATOR | RT | * | * | * | * | * | * | * | 1 | *BY ELEVATOR COMPANY |
| 2 | ELEVATOR | RT | * | * | * | * | * | * | * | 2 | *BY ELEVATOR COMPANY |
| A | STAIR | RT | RS | PT | PT | PT | PT | | | A | RUBBER TREADS& RISERS |
| B | STAIR | RT | RS | PT | PT | PT | PT | | | B | RUBBER TREADS& RISERS |
| 1001 | PARKING | BIT | | EXP | EXP | EXP | EXP | EXP | | 1001 | |
| 1002 | ELEVATOR MACHINE | SC | | PT | PT | PT | PT | EXP | | 1002 | |
| 1003 | HOUSEKEEPING | SC | | EPT | EPT | EPT | EPT | EXP | | 1003 | |
| 1004 | ELEVATOR LOBBY | RT | RS | PT | PT | PT/ALUM | PT | ACT | 9'-0" | 1004 | |
| 1005 | WATER ENTRY | SC | | PT | PT | PT | PT | EXP | | 1005 | |

## ROOM FINISH SCHEDULE - SECOND LEVEL: PARKING

| ROOM NO. | ROOM NAME | MATERIAL FLOOR | MATERIAL BASE | WALL NORTH | WALL EAST | WALL SOUTH | WALL WEST | CEILING MAT'L | CEILING HEIGHT | NO. | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | ELEVATOR | RT | * | * | * | * | * | * | * | 1 | *BY ELEVATOR COMPANY |
| 2 | ELEVATOR | RT | * | * | * | * | * | * | * | 2 | *BY ELEVATOR COMPANY |
| A | STAIR | RT | RS | PT | PT | PT | PT | | | A | RUBBER TREADS& RISERS |
| B | STAIR | RT | RS | PT | PT | PT | PT | | | B | RUBBER TREADS& RISERS |
| 2001 | PARKING | CONC | | EPT | EPT | EPT | EPT | GWB/EPT | VARIES | 2001 | |
| 2002 | ELECTRICAL | SC | | PT | PT | PT | PT | EXP-PT | | 2002 | |
| 2003 | TELE/DATA | SC | | PT | PT | PT | PT | EXP-PT | | 2003 | |
| 2004 | ELEVATOR LOBBY | RT | RS | PT | PT | PT | PT | GWB | 7'-8" | 2004 | |
| 2005 | STORAGE | SC | | PT | PT | PT/ALUM | PT | EXP-PT | | 2005 | |

## ROOM FINISH SCHEDULE - FOURTH LEVEL: PENTHOUSE

| ROOM NO. | ROOM NAME | MATERIAL FLOOR | MATERIAL BASE | WALL NORTH | WALL EAST | WALL SOUTH | WALL WEST | CEILING MAT'L | CEILING HEIGHT | NO. | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| A | STAIR | RS | RS | PT | PT | PT | PT | | | A | |
| 4001 | MECHANICAL | SC | | PT | PT | PT | PT | EXP-PT | | 4001 | |

## FINISH LEGEND:

ACOUSTICAL CEILING TILE
ACT 24X24-INCH TILE, COLOR: WHITE.

CARPET (BROADLOOM)
CP 12-FOOT ROLL, COLOR: TBD.

CARPET (TILE)
CPT 24X24-INCH TILE, COLOR: TBD.

CERAMIC TILE
CT-1 (FLOOR TILE-FIELD) 2X2-INCH UNGLAZED MOSAIC TILE, COLOR: TBD.
CT-2 (WALL TILE-FIELD) 6X6-INCH MATTE WALL TILE, COLOR: TBD.

GLASS TILE
GT (WALL TILE-ACCENT) 3X6-INCH TILE, COLOR: TBD.

CORNER GUARD
CG-1 COLOR: TBD.
CG-2 END WALL GUARD, COLOR:TBD.

DECORATIVE ARCHITECTURAL GLASS
DAG PATTERN & COLOR: TBD.

PAINT
PT-1 (FIELD) TBD.
PT-2 (DOOR & WINDOW TRIM, ACCENT) TBD.
PT-3 (ACCENT) TBD.
PT-4 (ACCENT) TBD.
PT-5 (ACCENT) TBD.

PLASTIC LAMINATE
PLAM-1 (HORIZONTAL SURFACES) TBD.
PLAM-2 (VERTICAL SURFACES) TBD.

PORCELAIN CERAMIC TILE
PCT-1 12X12-INCH TILE, COLOR: TBD.
PCT-2 12X24-INCH TILE, COLOR: TBD.
PCT-3 12X12-INCH TILE, COLOR: TBD.

RESILIENT BASE
RS 4-INCH STANDARD RUBBER COVE BASE, COLOR: TBD.

RESILIENT TILE
RT-1 (STAIR TREADS) RUBBER SHEET
RT-2 RUBBER TILE

SHEET VINYL
SV-1 (FIELD-DIRECTIONAL FLOORING, RE: AF103), COLOR: TBD.
SV-2 (FIELD, ACCENT, BASE) COLOR: TBD.

SOLID SURFACE
SS COLOR: TBD.

VINYL COMPOSITION TILE
VCT-1 (FIELD) COLOR: TBD.
VCT-2 (ACCENT) COLOR: TBD.
VCT-3 (ACCENT) COLOR: TBD.

WALK-OFF MAT
WOM 18 TO 24-INCH TILE, COLOR: TBD.

WALL PROTECTION
WP COLOR: TBD.

## GENERAL NOTES:

1. SEE GI001 FOR PROJECT GENERAL NOTES.

## FINISH NOTES:

1. SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION REGARDING FINISH MATERIALS AND MANUFACTURERS.
2. REFER TO PARTITION LEGEND FOR TYPE OF GWB COMPOSITION REQUIRED. "ABUSE RESISTANT", "MOISTURE RESISTANT" OR OTHER (TYPICAL).
3. REFER TO INTERIOR ELEVATIONS FOR MORE INFORMATION ON MATERIAL LOCATIONS AND PATTERNS.
4. REFER TO AF103 FOR MORE INFORMATION ON MATERIAL LOCATIONS AND PATTERNS.

## FINISH ABBREVIATIONS:

| | |
|---|---|
| ACT | ACOUSTICAL CEILING TILE |
| CG | CORNER GUARD |
| CP | CARPET (BROADLOOM) |
| CPT | CARPET (TILE) |
| CT | CERAMIC TILE |
| DAG | DECORATIVE ARCHITECTURAL GLASS |
| EPT | EPOXY PAINT |
| EXP | EXPOSED STRUCTURE |
| GT | GLASS TILE |
| GWB | GYPSUM WALLBOARD |
| ICB | INTEGRAL COVE BASE |
| PT | PAINTED |
| PCT | PORCELAIN CERAMIC TILE |
| RS | RESILIANT BASE |
| RT | RESILIANT TILE |
| SC | SEALED CONCRETE |
| SS | SOLID SURFACE |
| SV | SHEET VINYL |
| VCT | VINYL COMPOSITION TILE |
| VCT-P | VINYL COMPOSITION TILE- PATTERN W/ THREE COLORS |
| VP | VINYL PLANK |
| WD | WOOD |
| WDP | WOOD PANELING |
| WOM | WALK-OFF MAT |
| WP | WALL PROTECTION |

| REV. | DESCRIPTION | DATE |
|---|---|---|
| | | |

ISSUED FOR G.M.P. & PERMITTING
4-3-09

CURRENT ISSUE STATUS:

PROJECT NORTH

MAG NORTH

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING

144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

MARTIN'S POINT HEALTH CARE
MEDICAL OFFICE BUILDING
PORTLAND, MAINE

ROOM FINISH SCHEDULES

| | | | |
|---|---|---|---|
| SHEET TITLE: | | | |
| SCALE: | AS NOTED | DATE: | |
| PROJECT MANAGER: | SLB | GRAPHIC SCALE: | 0" 1" |
| JOB CAP/DRAWN: | TCM/TCM | | |
| A/E OF RECORD: | SLB | SHEET No. | AE601 |
| SMRT CAD FILE: | AE611-08139 | | |
| PROJECT No. | 08139 | | |

©COPYRIGHT 2008 SMRT INC.

PROGRESS PRINT