DOOR SCHEDULE - THIRD LEVEL: MEDICAL OFFICES

DOOR NO.	DOOR W x H	DOOR MAT'L	DOOR ELEV	GLAZE	FRAME MAT'L	FRAME ELEV	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	HDW GRP	FIRE RTG	DOOR NO.	REMARKS
3001	(2) 3'-2" x 7'-0"	ALUM	FG	TEMP/INSUL	ALUM					2		3001	
3002A	(2) 3'-4" x 7'-0"	ALUM	FG	TEMP	ALUM					3		3002A	
3002B	3'-0" x 7'-0"	WD	NG	WIRE	HM					6	90 MIN	3002B	
3006	3'-0" x 7'-0"	WD	F		HM					7		3006	
3007	3'-0" x 7'-0"	WD	F		HM					8		3007	
3008	3'-0" x 7'-0"	WD	F		HM					8		3008	
3009A	3'-0" x 7'-0"	WD	F		HM					7		3009A	
3011A	3'-0" x 7'-0"	WD	F		HM					9		3011A	
3011B	3'-0" x 7'-0"	WD	F		HM					7		3011B	
3012	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3012	
3014	3'-0" x 7'-0"	WD	HG	TEMP	HM					10		3014	
3014A	3'-0" x 7'-0"	WD	F		HM					7		3014B	
3015	3'-0" x 7'-0"	WD	NG	TEMP	HM					7		3015	
3016	3'-0" x 7'-0"	WD	F		HM					12	45 MIN	3016	
3017	3'-0" x 7'-0"	WD	HG	TEMP	HM					8		3017	
3017A	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3017A	
3017B	NO DOOR	N/A	N/A		HM					N/A		3017B	FRAMED OPENING
3018	(2) 2'-6" x 7'-0"	WD	F		HM					11		3018	
3020	3'-0" x 7'-0"	WD	F		HM					12	45 MIN	3020	
3021	3'-0" x 7'-0"	WD	F		HM					9		3021	
3022	3'-8" x 7'-0"	WD	F		HM					9		3022	
3023	(2) 2'-6" x 7'-0"	WD	F		HM					11		3023	
3024	(2) 2'-6" x 7'-0"	WD	F		HM					11		3024	
3025	3'-0" x 7'-0"	WD	F		HM					9		3025	
3026	3'-0" x 7'-0"	WD	F		HM					9		3026	
3027	3'-0" x 7'-0"	WD	F		HM					9		3027	
3028	3'-0" x 7'-0"	WD	F		HM					9		3028	
3029	(2) 2'-6" x 7'-0"	WD	F		HM					11		3029	
3030	(2) 2'-6" x 7'-0"	WD	F		HM					11		3030	
3031	3'-0" x 7'-0"	WD	F		HM					9		3031	
3033	3'-0" x 7'-0"	WD	F		HM					9		3033	
3034	3'-0" x 7'-0"	WD	F		HM					9		3034	
3035	3'-0" x 7'-0"	WD	F		HM					8		3035	
3036	3'-0" x 7'-0"	WD	F		HM					12		3036	
3037	(2) 2'-6" x 7'-0"	WD	F		HM					11		3037	
3038	3'-0" x 7'-0"	WD	HG	TEMP	HM					10		3038	
3038A	(2) 2'-6" x 7'-0"	WD	F		HM					11		3038A	
3039	3'-0" x 7'-0"	WD	F		HM					7		3039	
3040	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3040	
3041	3'-0" x 7'-0"	WD	F		HM					7		3041	
3044	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3044	
3045	3'-0" x 7'-0"	WD	F		HM					7		3045	
3045A	3'-0" x 7'-0"	WD	F		HM					8		3045A	
3046	3'-0" x 7'-0"	WD	F		HM					7		3046	
3047	3'-0" x 7'-0"	WD	F		HM					9		3047	
3048	3'-0" x 7'-0"	WD	F		HM					9		3048	
3049	3'-0" x 7'-0"	WD	F		HM					9		3049	
3052	3'-0" x 7'-0"	WD	F		HM					7		3052	
3053	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3053	
3053A	3'-0" x 7'-0"	WD	F		HM					7		3053A	
3055	(2) 2'-6" x 7'-0"	WD	F		HM					11		3055	
3056	3'-0" x 7'-0"	WD	F		HM					9		3056	
3057	3'-0" x 7'-0"	WD	F		HM					9		3057	
3058	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3058	
3058A	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3058A	
3059	3'-0" x 7'-0"	WD	F		HM					9		3059	
3063	3'-0" x 7'-0"	WD	F		HM					8		3063	
3066	3'-0" x 7'-0"	WD	HG	TEMP	HM					10		3066	
3067	3'-0" x 7'-0"	WD	F		HM					9		3067	
3068	3'-8" x 7'-0"	WD	F		HM					9		3068	
3069	3'-0" x 7'-0"	WD	F		HM					9		3069	
3071	3'-0" x 7'-0"	WD	F		HM					9		3071	
3074	3'-0" x 7'-0"	WD	F		HM					7		3074	
3075	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3075	
3076	3'-0" x 7'-0"	WD	F		HM					7		3076	
3078	(2) 2'-6" x 7'-0"	WD	F		HM					11		3078	
3079	3'-0" x 7'-0"	WD	F		HM					9		3079	
3081	3'-0" x 7'-0"	WD	F		HM					9		3081	
3082	3'-0" x 7'-0"	WD	F		HM					9		3082	
3083	3'-0" x 7'-0"	WD	F		HM					8		3083	
3084	(1)3'-0" x 7'-0" (1)1'-6" x 7'-0"	WD	F		HM					14		3084	
3086	3'-0" x 7'-0"	WD	F		HM					12	45 MIN	3086	
3087	3'-0" x 7'-0"	WD	F		HM					7		3087	
3087a	3'-0" x 7'-0"	WD	F		HM					8		3087a	
3088	3'-0" x 7'-0"	WD	F		HM					8		3088	
3092	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3092	
3093	3'-0" x 7'-0"	WD	F		HM					12	45 MIN	3093	
3094	3'-0" x 7'-0"	WD	F		HM					7		3094	
3095	3'-8" x 7'-0"	WD	F		HM					9		3095	
3096	3'-0" x 7'-0"	WD	F		HM					9		3096	
3097	3'-0" x 7'-0"	WD	F		HM					9		3097	
3101	3'-0" x 7'-0"	WD	F		HM					7		3101	
3102	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3102	
3103	3'-0" x 7'-0"	WD	F		HM					7		3103	
3105	(2) 2'-6" x 7'-0"	WD	F		HM					11		3105	
3106	3'-0" x 7'-0"	WD	F		HM					9		3106	
3107	3'-0" x 7'-0"	WD	F		HM					9		3107	
3108	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3108	
3108A	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3108A	
3109	3'-0" x 7'-0"	WD	F		HM					9		3109	
3113	3'-0" x 7'-0"	WD	F		HM					9		3113	
3116	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3116	
3117	3'-0" x 7'-0"	WD	F		HM					8		3117	
3118	3'-0" x 7'-0"	WD	F		HM					9		3118	
3119	3'-0" x 7'-0"	WD	F		HM					9		3119	
3121	3'-0" x 7'-0"	WD	F		HM					9		3121	
3124	3'-0" x 7'-0"	WD	F		HM					7		3124	
3125	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3125	
3126	3'-0" x 7'-0"	WD	F		HM					7		3126	
3128	(2) 2'-6" x 7'-0"	WD	F		HM					11		3128	
3129	3'-0" x 7'-0"	WD	F		HM					9		3129	
3131	3'-0" x 7'-0"	WD	F		HM					9		3131	
3132	3'-8" x 7'-0"	WD	F		HM					9		3132	
3133	3'-0" x 7'-0"	WD	F		HM					8		3133	
3134	3'-0" x 7'-0"	WD	F		HM					7		3134	
3136	3'-0" x 7'-0"	WD	F		HM					12		3136	
3137	3'-0" x 7'-0"	WD	F		HM					7		3137	
3141	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3141	
3142	3'-0" x 7'-0"	WD	F		HM					8		3142	
3143a	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3143a	
3143b	3'-0" x 7'-0"	WD	HG	TEMP	HM					10		3143b	
3144	3'-0" x 7'-0"	WD	F		HM					9		3144	
3145	3'-0" x 7'-0"	WD	F		HM					9		3145	
3146	3'-0" x 7'-0"	WD	F		HM					9		3146	
3149	3'-0" x 7'-0"	WD	F		HM					7		3149	
3150	3'-0" x 7'-0"	WD	F		HM					7		3150	
3151	3'-0" x 7'-0"	WD	HG	TEMP	HM					15		3151	
3152	3'-0" x 7'-0"	WD	F		HM					8		3152	
3153	3'-0" x 7'-0"	WD	F		HM					8		3153	
3154	3'-0" x 7'-0"	WD	F		HM					8		3154	
3155	3'-0" x 7'-0"	WD	NG	WIRE	HM					16	90 MIN	3155	
3157	3'-0" x 7'-0"	WD	F		HM					8		3157	
3158	4'-0" x 7'-0"	WD	LEAD		HM					17		3158	INTERLOCK DOOR W/ X-RAY
3159	3'-0" x 7'-0"	WD	F		HM					8		3159	
3161	4'-0" x 7'-0"	WD	NG	TEMP	HM					10		3161	
3162	3'-0" x 7'-0"	WD	F		HM					8		3162	
3163	3'-0" x 7'-0"	WD	F		HM					8		3163	
3164	4'-0" x 7'-0"	WD	LEAD		HM					17		3164	INTERLOCK DOOR W/ X-RAY
3165A	3'-8" x 7'-0"	WD	F		HM					9		3165A	
3165B	3'-0" x 7'-0"	WD	F		HM					9		3165B	
3166	3'-8" x 7'-0"	WD	HG	TEMP	HM					15		3166	
3167	3'-0" x 7'-0"	WD	F		HM					8		3167	
3168	3'-0" x 7'-0"	WD	F		HM					8		3168	
3173a	3'-0" x 7'-0"	WD	HG	TEMP	HM					10		3173a	
3173b	3'-0" x 7'-0"	WD	HG	TEMP	HM					10		3173b	
3178	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3178	
3181	3'-0" x 7'-0"	WD	F		HM					9		3181	
3182	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3182	
3183	3'-0" x 7'-0"	WD	F		HM					9		3183	
3184	3'-0" x 7'-0"	WD	F		HM					9		3184	
3186	3'-0" x 7'-0"	WD	F		HM					7		3186	
3187	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3187	
3188	3'-0" x 7'-0"	WD	F		HM					7		3188	
3191	(2) 2'-6" x 7'-0"	WD	F		HM					11		3191	
3192	3'-0" x 7'-0"	WD	F		HM					9		3192	
3193	3'-0" x 7'-0"	WD	F		HM					9		3193	
3194	3'-8" x 7'-0"	WD	F		HM					9		3194	
3195	3'-0" x 7'-0"	WD	F		HM					7		3195	
3196	(1)3'-0" x 7'-0" (1)1'-6" x 7'-0"	WD	F		HM					14		3196	
3198	3'-0" x 7'-0"	WD	F		HM					12	45 MIN?	3198	

DOOR SCHEDULE - THIRD LEVEL: MEDICAL OFFICES

DOOR NO.	DOOR W x H	DOOR MAT'L	DOOR ELEV	GLAZE	FRAME MAT'L	FRAME ELEV	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	HDW GRP	FIRE RTG	DOOR NO.	REMARKS
3205	3'-0" x 7'-0"	WD	F		HM					9		3205	
3206	3'-0" x 7'-0"	WD	F		HM					9		3206	
3207	3'-8" x 7'-0"	WD	F		HM					9		3207	
3209	3'-0" x 7'-0"	WD	F		HM					7		3209	
3211	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3211	
3212	3'-0" x 7'-0"	WD	F		HM					7		3212	
3215	(2) 2'-6" x 7'-0"	WD	F		HM					11		3215	
3216	3'-0" x 7'-0"	WD	F		HM					9		3216	
3217	3'-0" x 7'-0"	WD	F		HM					9		3217	
3218	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3218	
3218A	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3218A	
3219	3'-0" x 7'-0"	WD	F		HM					9		3219	
3222	3'-0" x 7'-0"	WD	F		HM					7		3222	
3223	3'-0" x 7'-0"	WD	F		HM					7		3223	
3226	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3226	
3227	3'-0" x 7'-0"	WD	F		HM					9		3227	
3228	3'-0" x 7'-0"	WD	F		HM					9		3228	
3229	3'-0" x 7'-0"	WD	F		HM					9		3229	
3232	3'-0" x 7'-0"	WD	F		HM					7		3232	
3233	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3233	
3234	3'-0" x 7'-0"	WD	F		HM					7		3234	
3237	3'-0" x 7'-0"	WD	F		HM					9		3237	
3238	3'-0" x 7'-0"	WD	F		HM					9		3238	
3239	3'-8" x 7'-0"	WD	F		HM					9		3239	
3240	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3240	
3241	3'-0" x 7'-0"	WD	F		HM					7		3241	
3242	3'-0" x 7'-0"	WD	F		HM					8		3242	
3244A	3'-0" x 7'-0"	WD	F		HM					7		3244A	
3244B	3'-0" x 7'-0"	WD	F		POCKET					18		3244B	
3245	3'-0" x 7'-0"	WD	F		HM					8		3245	
3246	3'-0" x 7'-0"	WD	F		HM					8		3246	
3249	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3249	
3251	3'-0" x 7'-0"	WD	F		HM					7		3251	
3252	3'-0" x 7'-0"	WD	F		HM					7		3252	
3253	3'-0" x 7'-0"	WD	F		HM					8		3253	
3254	3'-0" x 7'-0"	WD	F		HM					9		3254	
3255	3'-0" x 7'-0"	WD	F		HM					9		3255	
3256	3'-8" x 7'-0"	WD	F		HM					9		3256	
3257	(2) 2'-6" x 7'-0"	WD	F		HM					11		3257	
3259	3'-0" x 7'-0"	WD	F		HM					7		3259	
3261	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3261	
3262	3'-0" x 7'-0"	WD	F		HM					7		3262	
3265	3'-0" x 7'-0"	WD	F		HM					9		3265	
3266	3'-0" x 7'-0"	WD	F		HM					9		3266	
3267	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3267	
3267A	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3267A	
3271	3'-0" x 7'-0"	WD	F		HM					7		3271	
3274	3'-8" x 7'-0"	WD	HG	TEMP	HM					10		3274	
3275A	3'-0" x 7'-0"	WD	F		HM					7		3275A	
3275B	3'-0" x 7'-0"	WD	F		POCKET					18		3275B	
3276	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3276	
3277	3'-0" x 7'-0"	WD	F		HM					9		3277	
3278	3'-0" x 7'-0"	WD	F		HM					9		3278	
3279	(2) 2'-6" x 7'-0"	WD	F		HM					11		3279	
3282	3'-0" x 7'-0"	WD	F		HM					7		3282	
3283	3'-8" x 7'-0"	WD	HG	TEMP	HM					13		3283	
3284	3'-0" x 7'-0"	WD	F		HM					7		3284	
3286	3'-0" x 7'-0"	WD	F		HM					9		3286	
3287	3'-0" x 7'-0"	WD	F		HM					9		3287	
3288	3'-0" x 7'-0"	WD	F		HM					9		3288	
3289	3'-0" x 7'-0"	WD	F		HM					7		3289	
3291	3'-0" x 7'-0"	WD	F		HM					8		3291	
3292	3'-0" x 7'-0"	WD	F		HM					7		3292	
3293	3'-0" x 7'-0"	WD	HG	TEMP	HM					15		3293	
3294	3'-0" x 7'-0"	ALUM	FG	TEMP/INSUL	ALUM					1		3294	
3295	3'-0" x 7'-0"	WD	HG	TEMP	HM					10		3295	
3296	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3296	
3297	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3297	
3299	(2) 2'-3" x 7'-0"	WD	F		HM					19		3299	
3301	3'-0" x 7'-0"	WD	F		HM					8		3301	
3302	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3302	
3303	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3303	
3305	3'-0" x 7'-0"	WD	HG	TEMP	HM					10		3305	
3307	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3307	
3308	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3308	
3309	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3309	
3311	3'-0" x 7'-0"	WD	NG	TEMP	HM					9		3311	
3312	3'-0" x 7'-0"	WD	NG	TEMP	HM					7		3312	
3313	3'-0" x 7'-0"	WD	NG	TEMP	HM					7		3313	
3314	3'-0" x 7'-0"	WD	F		HM					12	45 MIN	3314	
3315	3'-0" x 7'-0"	WD	F		HM					20		3315	
3316	3'-0" x 7'-0"	WD	F		HM					7		3316	
3317	3'-0" x 7'-0"	WD	F		HM					12	45 MIN	3317	
3318	3'-0" x 7'-0"	WD	NG	TEMP	HM					21		3318	
3319	3'-0" x 7'-0"	WD	HG	TEMP	HM					7		3319	
3320	9'-6" x 8'-0"	ALUM	OH		ALUM					22		3320	

DOOR SCHEDULE - FIRST LEVEL: PARKING

DOOR NO.	DOOR W x H	DOOR MAT'L	DOOR ELEV	GLAZE	FRAME MAT'L	FRAME ELEV	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	HDW GRP	FIRE RTG	DOOR NO.	REMARKS
1001a	3'-0" x 7'-0"	HM	NG	WIRE/INSUL	HM					4	90 MIN	1001a	
1001b	3'-0" x 7'-0"	HM	NG	WIRE/INSUL	HM					4	90 MIN	1001b	
1001c	3'-0" x 7'-0"	HM	NG	TEMP/INSUL	HM					4		1001c	
1002	3'-0" x 7'-0"	HM	F		HM					5	45 MIN	1002	
1003	3'-0" x 7'-0"	HM	F		HM					5	45 MIN	1003	
1004	3'-8" x 7'-0"	ALUM	FG	TEMP/INSUL	ALUM					1		1004	
1005	3'-0" x 7'-0"	HM	F		HM					5	45 MIN	1005	

DOOR SCHEDULE - SECOND LEVEL: PARKING

DOOR NO.	DOOR W x H	DOOR MAT'L	DOOR ELEV	GLAZE	FRAME MAT'L	FRAME ELEV	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	HDW GRP	FIRE RTG	DOOR NO.	REMARKS
2001a	3'-0" x 7'-0"	HM	NG	WIRE/INSUL	HM					4	90 MIN	2001a	
2001b	3'-0" x 7'-0"	HM	NG	WIRE/INSUL	HM					4	90 MIN	2001b	
2002a	3'-0" x 7'-0"	HM	F		HM					5	45 MIN	2002a	
2002b	3'-0" x 7'-0"	HM	F		HM					5	45 MIN	2002b	
2003	3'-0" x 7'-0"	HM	F		HM					5		2003	
2004	3'-8" x 7'-0"	ALUM	FG	TEMP/INSUL	ALUM					1		2004	
2005	3'-0" x 7'-0"	HM	F		HM					5		2005	

DOOR SCHEDULE - FOURTH LEVEL: PENTHOUSE

DOOR NO.	DOOR W x H	DOOR MAT'L	DOOR ELEV	GLAZE	FRAME MAT'L	FRAME ELEV	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	HDW GRP	FIRE RTG	DOOR NO.	REMARKS
4001a	3'-0" x 7'-0"	HM	F		HM					23	90 MIN	4001a	
4001b	(PR) 3'-0" x 7'-0"	HM	F		HM	H3	M11/AE634	F11/AE634	A11/AE634	24		4001b	EXTERIOR INSULATED

GENERAL NOTES:

1. SEE G001 FOR PROJECT GENERAL NOTES.

DOOR SCHEDULE NOTES:

1. ALL DOORS SHALL BE 3/4" UNDERCUT (TYPICAL) EXCEPT WHEN THERE IS A BOTTOM FRAME, SILL THRESHOLD, WHERE RATED (1/2" UNDERCUT @ RATED LOCATIONS), OR SPECIFICALLY NOTED OTHERWISE.
2. ALL DOORS WITH BOTTOM FRAMES OR SILL THRESHOLDS SHALL HAVE MANUFACTURERS RECOMMENDED STANDARD UNDERCUT.
3. SEE SPECIFICATIONS FOR HARDWARE SET DESCRIPTIONS.

DOOR ABBREVIATIONS

ALUM	ALUMINUM
HM	HOLLOW METAL
WD	WOOD

REV.	DESCRIPTION	DATE

ISSUED FOR G.M.P. & PERMITTING
4-3-09

CURRENT ISSUE STATUS:

PROJECT NORTH

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING

144 Fore Street,P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

MARTIN'S POINT HEALTH CARE
MEDICAL OFFICE BUILDING
PORTLAND, MAINE

DOOR SCHEDULE

SHEET TITLE:

SCALE:	AS NOTED	DATE:	
PROJECT MANAGER:	SLB	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:	TCM/TCM		
A/E OF RECORD:	SLB	SHEET No.	
SMRT CAD FILE:	AE611-08139		AE611
PROJECT No.	08139		

©COPYRIGHT 2009 SMRT ME

PROGRESS PRINT