



D1 FIRST LEVEL FLOOR PLAN

1/8" = 1'-0"

<p>144 First Street, P.O. Box 618 Portland, Maine 04101 Tel: (207) 772-2846 Fax: (207) 772-2847 www.smartinc.com</p>		<p>ARCHITECTURE ENGINEERING PLANNING INTERIOR DESIGN COMMISSIONING</p>							
<p><b>SMART</b></p>		<p>MARTIN'S POINT HEALTH CARE MEDICAL OFFICE BUILDING PORTLAND, MAINE</p>							
<p>PROJECT NUMBER: 02132 DATE: 02/23</p>		<p>AS NOTED SUB: 02132 TOWERS: 01 DATE: 02/23</p>							
<p>ISSUED FOR G.M.P. &amp; PERMITTING 4-3-09</p>		<p>FIRST LEVEL: PARKING GARAGE FIRE PROTECTION PLAN</p>							
<p>REVISIONS</p> <table border="1"> <thead> <tr> <th>NO.</th> <th>DESCRIPTION</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	DESCRIPTION	DATE				<p>SHEET TITLE: FIRE PROTECTION PLAN</p>	
NO.	DESCRIPTION	DATE							
<p>KEYED NOTES:</p> <ul style="list-style-type: none"> <li>① FIRE DEPARTMENT VALVE. TURN FDN 1/16 AWAY FROM WALL TO ALLOW GREATER ACCESS TO THREADS TO FIRE DEPARTMENT.</li> <li>② 4" STICK TYPE FIRE DEPARTMENT CONNECTION FOR MANUAL DRY PIPE SPRINKLER SYSTEM. PROVIDE CHECK VALVE BETWEEN FPC AND STANDPIPE.</li> </ul>		<p>NOTES:</p> <ul style="list-style-type: none"> <li>1. SEE GRID FOR PROJECT GENERAL NOTES.</li> <li>2. SEE SHEET FP001 FOR FIRE PROTECTION LEGEND AND ABBREVIATIONS.</li> <li>3. DRY SYSTEM LOW-POINT DRAINS TO BE INSTALLED IN HEATED SPACE.</li> <li>4. SPRINKLER HEAD LOCATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING COMPLETE SPRINKLER COVERAGE THROUGHOUT THE FLOOR PER REQUIREMENTS OF NFPA 13. 13000 SERIES SPECIFICATIONS AND PER AUTHORITIES HAVING JURISDICTION. COORDINATE SPRINKLER HEAD LOCATIONS WITHIN THE CEILING WITH THE ARCHITECTURAL REFLECTED CEILING PLAN.</li> <li>5. SPRINKLER HEAD TYPES: REFER TO 13000 SERIES SPECIFICATIONS FOR SPRINKLER HEAD TYPES FOR EACH SPECIFIC LOCATION.</li> <li>6. PROVIDE SWING JOINT OR ENGINEER APPROVED FLEXIBLE CONNECTOR WHERE PIPES PASS EXPANSION JOINT.</li> </ul>							
<p>CURRENT ISSUE STATUS:</p> <p>PROJECT NUMBER: 02132 SHEET NO.: FP101</p>		<p>PROJECT TITLE: FIRE PROTECTION PLAN</p>							