DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
RECEPTS LEVEL ONE PARKING	0.9			1	20	20	2	0.2			LIGHTING CONTROL PANEL LC1
RECEPTS RMS 1003-1005		0.8		3	20	20	4		1.0		SITE LTG & RECEPTS
RECEPTS LEVEL ONE PARKING			0.8	5	20	20	6			0.8	SITE LTG & RECEPTS
RECEPTS LEVEL ONE PARKING	0.8			7	20	20	8	0.9			SITE LTG & RECEPTS
RECEPTS LEVEL TWO PARKING		0.8		9	20	20	10		0.9		SITE LTG & RECEPTS
RECEPTS RMS 2001, 2004, 2005			0.6	11	20	20	12			0.8	SITE LTG & RECEPTS
RECEPTS LEVEL TWO PARKING	0.8			13	20	20	14	0.9			SITE LTG & RECEPTS
RECEPTS LEVEL TWO PARKING		0.9		15	20	20	16		0.9		SITE LTG & RECEPTS
GROUND FLOOR UH-1, CUH-1, 2, 3			0.8	17	20	20	18			1.2	TEL/DATA 2003 UPS RECEPT
RECEPTS TEL/DATA 2003	0.8			19	20		20	1.2			
RECEPTS TEL/DATA 2003		0.4		21	20	30	22		1.2		TEL/DATA 2003 UPS RECEPT
ELEVATOR PIT RECEPTS			0.4	23	20		24			1.2	
ELEVATOR CAB LTG	0.5			25	20	20	26	1.0			GENERATOR JACKET HTR
ELEVATOR CAB LTG		0.5		27	20		28		1.0		
ELEVATOR MACH RM RECEPT			0.4	29	20	20	30			1.0	GENERATOR BATTERY CHARGER
SUMP PUMP WP-1	1.2			31	20	20	32	1.1			STAIR A & B RECEPTS
ELEC RM RECEPTS		0.4		33	20		34				
SPARE				35	20		36				
SPARE				37	20		38				
SPARE				39	20		40				
SPARE				41	20		42				
SUB-TOTAL	5.0	3.8	3.0		NEUTRAL BUS / GROUND BUS			4.2	5.0	5.0	SUB-TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE 225 AMP BUS — TOTAL kVA A 9.2 — PANEL NO. PG1
MAIN BREAKER: 150 AMP TRIP — TOTAL kVA B 8.8
MOUNTING: SURFACE — TOTAL kVA C 8.8 — LOCATION ELECTRICAL 2002
SC RATING: 10,000 AIC — TOTAL kVA 26.0
NOTES:

DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
RECEPTS EXAM 3129	1.1			1	20	20	2	0.6			RECEPTS ULTRA SOUND
RECEPTS EXAM 3131		1.1		3	20	20	4		0.8		RECEPTS ULTRA SOUND
RECEPTS EXAM 3132			1.1	5	20	20	6			1.0	DEXA EQUIPMENT RECEPT
RECEPTS RMS 3116, 3133, 3134, 3142, 3105, 3128	1.3			7	20	20	8	0.8			DEXA RM RECEPTS
RECEPTS RMS 3143, 3148		1.3		9	20	20	10		0.6		RAD READING B145 RECEPT
FLOOR RECEPTS NURSE 3123			0.8	11	20	20	12			0.6	RAD READING B145 RECEPT
RECEPTS RM 3102	0.9			13	20	20	14	0.9			RECEPTS RMS 3166-3168
RECEPTS RM 3103, 3124		1.1		15	20	20	16		0.9		RECEPTS MAMMO 3165
RECEPTS RM 3125			0.9	17	20	20	18			0.9	RECEPTS RMS 3159, 3161-3163
RECEPTS RM 3126, 3149	1.1			19	20	20	20	0.8			RECEPTS X-RAY 3158
RECEPTS RM 3150		0.8		21	20	20	22		0.8		RECEPTS X-RAY 3164
COUNTER RECEPT BREAK RM			1.0	23	20	20	24			0.9	RECEPTS TECH WORK 3156
COUNTER RECEPT BREAK RM	1.0			25	20	20	26	0.9			RECEPTS TECH WORK 3156
COUNTER RECEPT BREAK RM		1.0		27	20	20	28		0.9		RECEPTS TECH WORK 3156
BREAK RM RECEPTS			1.1	29	20	20	30			0.9	RECEPTS TECH WORK 3156
VENDING MACHINE BREAK RM	1.0			31	20	20	32	1.0			TECH WORK PRINTER RECEPT
VENDING MACHINE BREAK RM		1.0		33	20	35	34		1.4		MAMMO EQUIPMENT
RECEPTS RMS 3152-3155, 3157			0.9	35	20		36			1.4	
X-RAY 120V FEED	1.0			37	20	20	38				SPARE
REFRIG RECEPT BREAK RM		1.0		39	20	20	40				SPARE
REFRIG RECEPT BREAK RM			1.0	41	20	20	42				SPARE
SUB-TOTAL	7.4	7.3	6.8		NEUTRAL BUS / GROUND BUS			5.0	5.4	5.7	SUB-TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE 400 AMP BUS — TOTAL kVA A 12.4 — PANEL NO. PP2C
MAIN LUGS ONLY 400 AMP LUGS — TOTAL kVA B 12.7
MOUNTING: SURFACE — TOTAL kVA C 12.5 — LOCATION ELEC 3036
SC RATING: 10,000 AIC — TOTAL kVA 37.6
NOTES: 1. PROVIDE W/ FEED THRU LUGS.

DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
REPECPTS EXAM 3219	1.1			1	20	20	2	0.9			RECEPTS RMS 3195, 3196, 3204, CORR
REPECPTS EXAM 3217		1.1		3	20	20	4		1.1		RECEPTS CORR/ NURSE STATION
REPECPTS EXAM 3216			1.1	5	20	20	6			1.1	RECEPTS NURSE WORK 3182
REPECPTS EXAM 3205	1.1			7	20	20	8	0.8			FLOOR RECEPTS NURSE 3213
REPECPTS EXAM 3206		1.1		9	20	20	10		0.8		FLOOR RECEPTS NURSE 3185
REPECPTS EXAM 3207			1.1	11	20	20	12			0.9	RECEPTS RMS 3211, 3212
REPECPTS EXAM 3192	1.1			13	20	20	14	1.1			RECEPTS RMS 3209, 3211
REPECPTS EXAM 3193		1.1		15	20	20	16		0.9		RECEPTS RMS 3187, 3188
REPECPTS EXAM 3194			1.1	17	20	20	18			1.1	RECEPTS RMS 32186, 3187
REPECPTS EXAM 3181	1.1			19	20	20	20	0.6			GASEOUS FIRE PROTECTION 3011A, 3030, 3316
REPECPTS EXAM 3183		1.1		21	20	20	22		1.1		DOOR HOLD OPEN DEVICES
REPECPTS EXAM 3184			1.1	23	20	20	24			0.4	NURSE CALL HEAD END EQUIPMENT
SPARE				25	20	20	26				SPARE
SPARE				27	20	20	28				SPARE
SPARE				29	20	20	30				SPARE
SPARE				31	20	20	32				SPARE
SPARE				33	20	20	34				SPARE
SPARE				35	20	20	36				SPARE
SPARE				37	20	20	38				SPARE
SPARE				39	20	20	40				SPARE
SPARE				41	20	20	42				SPARE
SUB-TOTAL	4.4	4.4	4.4		NEUTRAL BUS / GROUND BUS			3.4	3.9	3.5	SUB-TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE 400 AMP BUS — TOTAL kVA A 7.8 — PANEL NO. PP2F
MAIN LUGS ONLY 400 AMP LUGS — TOTAL kVA B 8.3
MOUNTING: FURFACE — TOTAL kVA C 7.9 — LOCATION ELEC 3314
SC RATING: 10,000 AIC — TOTAL kVA 24.0
NOTES: 1. PROVIDE W/ FEED THRU LUGS.

DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
RECEPTS EXAM/ NURSE TRIAGE 3021	1.1			1	20	20	2	0.9			RECEPTS COFFEE ALCOVE 3042
RECEPTS EXAM 3026		1.1		3	20	20	4		0.4		RECEPTS COFFEE ALCOVE 3042
RECEPTS EXAM 3027			1.1	5	20	20	6			0.6	RECEPTS COFFEE ALCOVE 3042
RECEPTS EXAM 3033	1.1			7	20	20	8	0.9			RECEPTS TEL.DATA 3030
RECEPTS EXAM 3022		1.1		9	20	20	10		0.4		RECEPTS TEL.DATA 3030
RECEPTS EXAM 3025			1.1	11	20	20	12			0.8	RECEPTS INPATIENT CONF. 3045
RECEPTS EXAM 3028	1.1			13	20	20	14	1.3			RECEPTS RMS 3044, 3045A, 3061, 3063
RECEPTS EXAM 3031		1.1		15	20	20	16		1.1		RECEPTS PROCEDURE 3067
RECEPTS RMS 3016, 3019, 3020			1.3	17	20	20	18			1.1	RECEPTS RMS 3085, 3086, 3092, 3093
RECEPTS RMS 3032, 3035, 3037, 3038	1.3			19	20	20	20	0.9			RECEPTS RMS 3087-3089
RECEPTS OFFICE 3039, 3038		0.9		21	20	20	22		1.1		RECEPTS WAITING 3017
RECEPTS TEAM ROOM 3040			0.9	23	20	20	24			0.9	RECEPTS WAITING 3114
RECEPTS SHARED OFFICE 3041, 3038	0.9			25	20	20	26	0.8			RECEPTS PROTIME RM 3015
RECEPTS NURSE WORK 3034		0.9		27	20	20	28		1.3		RECEPTS WAITING 3138
FLOOR RECEPTS 3038			0.8	29	20	20	30			0.8	RECEPTS RMS 3136
RECEPTS PROCEDURE 3113	1.1			31	20	20	32	0.9			RECEPTS RMS 3111, 3116, 3117, 3135
RECEPTS RMS 3137, 3141		0.9		33	20	20	34		1.0		PROCEDURE 3067 EXAM LIGHTS
RECEPTS WAITING 3064			1.1	35	20	20	36			1.0	PROCEDURE 3113 EXAM LIGHTS
TEL/DATA 3030 UPS RECEPT	1.2			37	20	20	38	1.2			TEL/DATA 3030 UPS RECEPT
		1.2		39			40		1.2		
SPARE				41	20	20	42				SPARE
SUB-TOTAL	7.8	7.2	6.3		NEUTRAL BUS / GROUND BUS			6.4	6.5	5.2	SUB-TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE 400 AMP BUS — TOTAL kVA A 14.2 — PANEL NO. PP2A
MAIN BREAKER 400 AMP TRIP — TOTAL kVA B 13.7
MOUNTING: SURFACE — TOTAL kVA C 11.5 — LOCATION ELEC 3036
SC RATING: 10,000 AIC — TOTAL kVA 39.4
NOTES: 1. PROVIDE W/ FEED THRU LUGS.

DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
RECEPTS REGISTRATION 3171	0.8			1	20	20	2	0.8			RECEPTS RM 3007, 3007A, 3012
RECEPTS REGISTRATION 3171		0.9		3	20	20	4		0.4		RECEPT BLOOD DRAW 3011
RECEPTS WORK AREA 3173			0.8	5	20	20	6			0.8	RECEPTS LAB CHECK-IN 3013
RECEPTS WORK AREA 3173	0.8			7	20	20	8	0.6			RECEPTS LAB CHECK-IN 3013
RECEPTS WORK AREA 3173		0.8		9	20	20	10		1.0		LAB HEM ANALYZER RECEPT
RECEPTS WORK AREA 3173			0.4	11	20	20	12			0.8	LAB BENCH RECEPTS
COPY RECEPT WORK AREA 3173	1.0			13	20	20	14	1.0			LAB COAG ANALYZER RECEPT
RECEPTS LOBBY/EXTERIOR		1.3		15	20	20	16		0.8		LAB BENCH RECEPTS
RECEPTS LOBBY DESK			0.8	17	20	20	18			0.8	LAB RECEPTS
RECEPTS TEL/DATA 3011A	0.4			19	20	20	20	1.0			LAB LG REFRIDGERATOR
RECEPTS TEL/DATA 3011A		0.4		21	20	20	22		0.4		LAB BENCH RECEPTS
RECEPT BLOOD DRAW 3009, 3010			0.8	23	20	20	24			0.4	LAB BENCH RECEPTS
LAB BENCH RECEPT	1.0			25	20	20	26	0.6			CABINET UNIT HEATER CUH-6
LAB BENCH RECEPT		1.0		27	20	20	28		0.4		CANOPY HEAT TRACE (2)
LAB BENCH RECEPT			1.0	29	20	20	30			1.0	MOTORIZED DOOR OPENERS
ELEC RM RECEPTS	0.4			31	20	20	32				SPARE
SPARE				33	20	20	34				SPARE
SPARE				35	20	20	36				SPARE
SPARE				37	20	20	38				SPARE
SPARE				39	20	20	40				SPARE
SPARE				41	20	20	42				SPARE
SUB-TOTAL	4.5	4.4	3.8		NEUTRAL BUS / GROUND BUS			4.0	3.0	3.8	SUB-TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE 400 AMP BUS — TOTAL kVA A 8.5 — PANEL NO. PP2D
MAIN LUGS ONLY 400 AMP LUGS — TOTAL kVA B 7.4
MOUNTING: SURFACE — TOTAL kVA C 7.6 — LOCATION ELEC 3036
SC RATING: 10,000 AIC — TOTAL kVA 23.5
NOTES: 1. PROVIDE W/ FEED THRU LUGS
2. PROVIDE GFGI PROTECTED CIRCUIT BREAKER

DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
RECEPTS RMS 3297, 3298	0.9			1	20	20	2	0.8			RECEPTS RMS 3292
RECEPTS RMS 3296, 3298		0.8		3	20	20	4		0.9		RECEPTS RMS 3249, 3269, 3274, 3291
RECEPTS OPEN OFFICE 3298			0.8	5	20	20	6			1.1	RECEPTS WAITING 3272
RECEPTS OFFICE 3307	0.8			7	20	20	8	0.9			RECEPTS RMS 3245-3248, 3251
RECEPTS OFFICE 3308		0.8		9	20	20	10		0.8		RECEPTS CONF B 3312
RECEPTS OFFICE 3309			0.8	11	20	20	12			0.8	RECEPTS CONF C 3313
RECEPTS RMS 3294, 3295, 3301	0.9			13	20	20	14	0.8			RECEPTS ECHO RM
RECEPTS OPEN OFFICE 3306		0.8		15	20	20	16		1.0		TREADMILL RECEPTS ECHO
COUNTER RECEPTS RM 3298			1.0	17	20	20	18			0.9	RECEPTS ECHO RM
COUNTER RECEPTS RM 3298	1.0			19	20	20	20	0.9			RECEPTS PROCEDURE 3244
RECEPTS OFFICE 3302		0.8		21	20	20	22		0.9		RECEPTS PROCEDURE 3244
RECEPTS OFFICE 3303			0.8	23	20	20	24			0.6	RECEPTS PROCEDURE 3244
RECEPTS COFFEE ALCOVE 3293	0.6			25	20	20	26	0.2			CANOPY DRAIN HEAT TRACE (2)
COUNTER RECEPTS 3293		1.0		27	20	20	28		0.2		CABINET UNIT HTR CUH-5
COUNTER RECEPTS 3293			1.0	29	20	20	30			1.0	PROCEDURE 3223 EXAM LIGHTS
RECEPTS CONF A 3311	0.6			31	20	20	32	0.9			ELEC RM RECEPTS
RECEPTS CONF A 3311		0.6		33	20	20	34		0.5		REFRIG. RECEPT RM 3298
RECEPTS STORAGE 3317			0.8	35	20	20	36			0.6	RECEPTS A/V CONF A 3311
SPARE				37	20	20	38				SPARE
SPARE				39	20	20	40				SPARE
SPARE				41	20	20	42				SPARE
SUB-TOTAL	4.8	4.8	5.2		NEUTRAL BUS / GROUND BUS			4.0	4.3	5.0	SUB-TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE 400 AMP BUS — TOTAL kVA A 8.8 — PANEL NO. PP2G
MAIN LUGS ONLY 400 AMP LUGS — TOTAL kVA B 9.1
MOUNTING: SURFACE — TOTAL kVA C 10.2 — LOCATION ELEC 3314
SC RATING: 10,000 AIC — TOTAL kVA 28.1
NOTES: 1. PROVIDE W/ FEED THRU LUGS
2. PROVIDE GFGI PROTECTED CIRCUIT BREAKER

DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
RECEPTS EXAM 3047	1.1			1	20	20	2	0.8			RECEPTS MENTAL HLTH 3046
RECEPTS EXAM 3048		1.1		3	20	20	4		0.9		RECEPTS NURSE WORK 2058
RECEPTS EXAM 3049			1.1	5	20	20	6			0.9	RECEPTS NURSE WORK 2058A
RECEPTS EXAM/ NURSE TRIAGE 3059	1.1			7	20	20	8	0.9			RECEPTS RMS 3044, 3051
RECEPTS EXAM 3057		1.1		9	20	20	10		0.9		RECEPTS RMS 3052, 3053
RECEPTS EXAM 3056			1.1	11	20	20	12			0.8	RECEPTS RMS 3053, 3053A
RECEPTS EXAM/ NURSE TRIAGE 3068	1.1			13	20	20	14	0.9			RECEPTS RMS 3053A, 3074
RECEPTS EXAM 3069		1.1		15	20	20	16		0.9		RECEPTS RMS 3075
RECEPTS EXAM 3071			1.1	17	20	20	18			1.1	RECEPTS RMS 3076, 3101
RECEPTS EXAM 3082	1.1			19	20	20	20	0.8			FLOOR RECEPTS NURSE ST 3073
RECEPTS EXAM 3081		1.1		21	20	20	22		0.8		FLOOR RECEPTS NURSE ST 3051
RECEPTS EXAM 3079			1.1	23	20	20	24			0.8	FLOOR RECEPTS NURSE ST 3099
RECEPTS EXAM 3095	1.1			25	20	20	26	1.3			RECEPTS RMS 3066, 3092, 3083, 3084
RECEPTS EXAM 3096		1.1		27	20	20	28		1.1		RECEPTS NURSE WORK 3108
RECEPTS EXAM 3097			1.1	29	20	20	30			1.1	RECEPTS NURSE WORK 3108A
RECEPTS EXAM/ NURSE TRIAGE 3109	1.1			31	20	20	32	0.8			RECEPTS RMS 3055, 3073, 3078
RECEPTS EXAM 3107		1.1		33	20	20	34		0.6		FREEZE PROTECT PUMP HWP-6
RECEPTS EXAM 3106			1.1	35	20	20	36			1.0	REFRIGERATOR NURSE WORK 3034, 3039
RECEPTS EXAM/ NURSE TRIAGE 3118	1.1			37	20	20	38				SPARE
RECEPTS EXAM 3119		1.1		39	20	20	40				SPARE
RECEPTS EXAM 3121			1.1	41	20	20	42				SPARE
SUB-TOTAL	7.7	7.7	7.7		NEUTRAL BUS / GROUND BUS			5.7	5.4	5.9	SUB-TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE 400 AMP BUS — TOTAL kVA A 13.4 — PANEL NO. PP2B
MAIN LUGS ONLY 400 AMP LUGS — TOTAL kVA B 13.1
MOUNTING: SUIRFACE — TOTAL kVA C 13.6 — LOCATION ELEC 3036
SC RATING: 10,000 AIC — TOTAL kVA 40.1
NOTES: 1. PROVIDE W/ FEED THRU LUGS.

DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
RECEPTS RM 3289	0.8			1	20	20	2	1.1			RECEPTS NURSE WORK 3267A
RECEPTS RM 3276		0.8		3	20	20	4		1.1		RECEPTS NURSE WORK 3267
RECEPTS EXAM 3287			1.1	5	20	20	6			0.8	FLOOR RECEPTS NURSE 3285
RECEPTS EXAM 3286	1.1			7	20	20	8	0.8			FLOOR RECEPTS NURSE 3263
RECEPTS EXAM 3278		1.1		9	20	20	10		0.8		FLOOR RECEPTS NURSE 3235
RECEPTS EXAM 3277			1.1	11	20	20	12			1.3	CORRIDOR RECEPTS
RECEPTS EXAM 3266	1.1			13	20	20	14	1.3			CORRIDOR RECEPTS
RECEPTS EXAM 3265		1.1		15	20	20	16		1.1		RECEPTS RMS 3283, 3284
RECEPTS EXAM 3254			1.1	17	20	20	18			0.9	RECEPTS RMS 3282, 3283
RECEPTS EXAM 3255	1.1			19	20	20	20	0.9			RECEPTS RMS 3261, 3262
RECEPTS EXAM 3256		1.1		21	20	20	22		1.1		RECEPTS RMS 3259, 3261
RECEPTS EXAM 3237			1.1	23	20	20	24			1.1	RECEPTS RMS 3233, 3234
RECEPTS EXAM 3238	1.1			25	20	20	26	0.9			RECEPTS RMS 3232, 3233
RECEPTS EXAM 3239		1.1		27	20	20	28		1.1		CORRIDOR RECEPTS
RECEPTS EXAM 3227			1.1	29	20	20	30			1.1	RECEPTS NURSE WORK 3218A
RECEPTS EXAM 3228	1.1			31	20	20	32	1.1			RECEPTS NURSE WORK 3218
RECEPTS EXAM 3229		1.1		33	20	20	34		0.6		RECEPTS STRESS ECHO 3252
RECEPTS STRESS ECHO 3252			0.9	35	20	20	36			0.6	RECEPTS STRESS ECHO 3252
FREEZE PROTECT. PUMP HWP-5	0.6			37	20	20	38				SPARE
SPARE				39	20	20	40				SPARE
SPARE				41	20	20	42				SPARE
SUB-TOTAL	6.9	6.3	6.4		NEUTRAL BUS / GROUND BUS			6.1	5.8	5.8	SUB-TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE 400 AMP BUS — TOTAL kVA A 13.0 — PANEL NO. PP2E
MAIN BREAK 400 AMP TRIP — TOTAL kVA B 12.1
MOUNTING: SURFACE — TOTAL kVA C 12.2 — LOCATION ELEC 3314
SC RATING: 10,000 AIC — TOTAL kVA 37.3
NOTES: 1. PROVIDE W/ FEED THRU LUGS.

DIRECTORY	kVA LOAD A	kVA LOAD B	kVA LOAD C	CKT NO.	BKR AMPS	BKR AMPS	CKT NO.	kVA LOAD A	kVA LOAD B	kVA LOAD C	DIRECTORY
CORRIDOR RECEPTS	1.1			1	20	20	2	0.6			RECEPTS PHARMACY WINDOWS
RECEPTS PROCEDURE 3223		0.8		3	20	20	4		0.6		RECEPTS PHARMACY WINDOWS
RECEPTS PROCEDURE 3223			0.8	5	20	20	6			0.8	RECEPTS PHARMACY MANAGER
RECEPTS RMS 3198, 3203	0.9			7	20	20	8	0.8			RECEPTS PHARMACY DROP
RECEPTS WAITING 3244		1.1		9	20	20	10		0.8		PHARMACY RECEPTS
RECEPTS WAITING 3199			1.1	11	20	20	12			0.8	PHARMACY RECEPTS
RECEPTS REGISTRATION 3179	0.8			13	20	20	14	0.8			PHARMACY RECEPTS POWER POLE
RECEPTS REGISTRATION 3179		0.6		15	20	20	16		0.6		PHARMACY RECEPTS
RECEPTS CORR. 3247			0.8	17	20	20	18			0.8	PHARMACY RECEPTS
RECEPTS IT/SET-UP 3315	0.6			19	20	20	20	1.0			PHARMACY REFREIGERATOR
RECEPTS IT/SET-UP 3315		0.4		21	20	20	22		0.4		PHARMACY COUNTER RECEPTS
RECEPTS IT/SET-UP 3315			0.4	23	20	20	24			1.0	PHARMACY SCRIPT PRO
RECEPTS IT/PHONE 3316	0.4			25	20	20	26	0.8			PHARMACY FLOOR RECEPTS
RECEPTS IT/PHONE 3316		0.6		27	20	20	28		1.0		PROCEDURE 3244 EXAM LIGHTS
RECEPTS IT/PHONE 3316			0.4	29	20	20	30				SPARE
IT/PHONE UPS RECEPT	1.2			31	20	20	32				SPARE
		1.2		33		20	34				SPARE
IT/PHONE UPS RECEPT			1.2	35	20	20	36				SPARE
	1.2			37		20	38				SPARE
SPARE				39	20	20	40				SPARE
SPARE				41	20	20	42				SPARE
SUB-TOTAL	6.2	4.7	4.7		NEUTRAL BUS / GROUND BUS			4.0	3.4	3.4	SUB-TOTAL

VOLTAGE: 208Y/120V 3 PHASE 4 WIRE 400 AMP BUS — TOTAL kVA A 10.2 — PANEL NO. PP2H
MAIN LUGS ONLY 400 AMP LUGS — TOTAL kVA B 8.1
MOUNTING: SURFACE — TOTAL kVA C 8.1 — LOCATION ELEC 3314
SC RATING: 10,000 AIC — TOTAL kVA 26.4
NOTES: 1. PROVIDE W/ FEED THRU LUGS.

NOTE:

1. SEE G001 FOR PROJECT GENERAL NOTES
2. SEE SHEET E-001 FOR LEGEND AND GENERAL NOTES.

REV.	DESCRIPTION	DATE

ISSUED FOR G.M.P. & PERMITTING
4-3-09

CURRENT ISSUE STATUS:

PROJECT NORTH

MAG NORTH

SMRT
ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070
www.smrtinc.com

MARTIN'S POINT HEALTH CARE
MEDICAL OFFICE BUILDING
PORTLAND, MAINE

PANEL SCHEDULES
SHEET 2

SHEET TITLE:

SCALE:	NONE	DATE:	
PROJECT MANAGER:	SLB	GRAPHIC SCALE:	0" 1"
JOB CAP/DRAWN:	TCM/CDS		
A/E OF RECORD:	DJT	SHEET No.	EP602
SMRT CAD FILE:	EP602-08139		
PROJECT No.	08139		

©COPYRIGHT 2008 SMRT INC.

PROGRESS PRINT