
PROJECT PARCEL SITE

PORTLAND TAX ASSESSOR'S MAP & LOT NUMBERS

C-001

SITE DEVELOPMENT PLANS MARTIN'S POINT REDEVELOPMENT PROJECT PORTLAND, MAINE **APRIL 2006** RELEASED FOR BID - PHASE I ONLY



LOCATION MAP

INDEX

COVER SHEET

GENERAL NOTES & LEGEND

EXISTING CONDITIONS & DEMOLITION PLAN

SITE LAYOUT AND UTILITY PLAN - PHASE 1

SITE LAYOUT PLAN - PHASE 2

SITE GRADING & EROSION CONTROL PLAN - PHASE 1

SITE GRADING & DRAINAGE PLAN - PHASE 2

SITE LAYOUT PLAN EXPANDED VIEW

SITE GRADING PLAN - SELECT EXPANDED VIEWS

* C-7 EROSION & SEDIMENT CONTROL PLAN

* C-8 UTILITY PLAN

SITE DETAILS C-9

UTILITY DETAILS

C-11 WATER DETAILS EROSION CONTROL DETAILS

EROSION & SEDIMENT CONTROL NARRATIVE

MISCELLANEOUS SITE DETAILS

UTILITY PROFILES

LANDSCAPE PLAN

LANDSCAPE DETAILS

LIGHTING PLAN EXISTING CONDITIONS WATERSHED PLAN

POSTDEVELOPMENT WATERSHED PLAN

BOUNDARY & TOPOGRAPHIC SURVEY, BY OWEN HASKELL

UTILITIES

WATER ATTN: DAVE COFFIN PORTLAND WATER DISTRICT P.O. BOX 3553 PORTLAND, MAINE 04104 (207) 774-5961

CITY OF PORTLAND

162 CANCO ROAD PORTLAND, MAINE 04103

PERMITS

STATUS PUBLIC HEARING SCHEDULED FOR LOCAL MAJOR SITE PLAN PERMIT APRIL 25, 2006

TRAFFIC MOVEMENT PERMIT CITY OF PORTLAND

STATE
MAINE GENERAL CONSTRUCTION PERMIT TO BE FILED PRIOR TO CONSTRUCTION

UNDER DELEGATED REVIEW BY THE PUBLIC HEARING SCHEDULED FOR MeDEP SITE LOCATION OF DEVELOPMENT

MeDEP STORMWATER PERMIT

MeDEP NRPA PERMIT-BY-RULE TO BE SUBMITTED APRIL 2006

ZONING DISTRICT: R-P RESIDENTIAL-PROFESSIONAL

SPACE AND BULK REQUIREMENTS:

PREPARED BY

DeLuca-Hoffman Associates, Inc. 778 MAIN STREET, SUITE 8 SOUTH PORTLAND, MAINE 04106

PDT ARCHITECTS

49 DARTMOUTH STREET PORTLAND, MAINE 04103

OWEN HASKELL, INC. 16 CASCO STREET

PORTLAND, MAINE 04101-2979 207.774.0424 ENVIRONMENTAL ENGINEER:

HOFFMAN ENGINEERING, INC. 640 TEN ROD ROAD NORTH KINGSTOWN, RHODE ISLAND 02852 401.294.9032

NATURAL RESOURCES CONSULTANT: NORMANDEAU ASSOCIATES, INC. 253 MAIN STREET YARMOUTH, MAINE 04096 207.846.3598


S.W. COLE ENGINEERING 286 PORTLAND ROAD GRAY, MAINE 04039

207.657.2866

CASEY & GODFREY ENGINEERS 263 WATER STREET GARDINER, MAINE 04345 207.582.4526

OWNER: MARTIN'S POINT HEALTH CARE 331 VERANDA STREET PORTLAND, ME 04103

APPLICANT:
MARTIN'S POINT HEALTH CARE



MARTIN'S POINT REDEVELOPMENT PROJECT

COVER SHEET

MARTIN'S POINT HEALTH CARE

^{*} SHEETS NOT REQUIRED FOR PHASE I WORK

GENERAL NOTES

GENERAL NOTES:

1. OWNER:

MARTIN'S POINT HEALTH CARE 331 VERANDA STREET PORTLAND, ME 04103

- 2. CONSULTANTS USED FOR PLAN PREPARATION:
- THE PROJECT IS SITUATED ON TWO LOTS WHICH HAVE THE FOLLOWING TAX ASSESSOR AND ACREAGE INFORMATION:

PORTLAND TAX ASSESSOR

MAP LOT NO. APPROX. ACREAGE 434 C-005 434 C-001 4.6 7.0

- 4. THE PROJECT DRAWINGS PROVIDE ONLY A PORTION OF THE SITE WORK REQUIREMENTS CONSTRUCTION SHALL OCCUR ONLY USING PROJECT SPECIFICATIONS PREPARED BY OSLUCIA-HERMA ASSOCIATES, INC. OR THEIR SUBCONSULTANTS AND DRAWINGS WHICH HAVE A REVISION BLOCK BUCK INCIDENT AND THE STATE DEPARTMENT OF THIS SPECIAL COMPLY WITH THE STATE DEPARTMENT OF THIS SPECIAL TION SPECIAL DISC. AS PART OF THIS PROJECT SHALL BE COMPACTED TO 95 PERCENT OPTIMIN DESIGN FOR AST THE STATE DEPARTMENT OF THIS PROJECT SHALL BE COMPACTED TO 95 PERCENT OPTIMIN DESIGN FOR AST THE AST 1952 VILLESS NOTED OR SPECIFIED OTHERWISE IN THE CONTRACT ORAWINGS.
- THE CONTRACTOR SHALL REFER TO THE PROJECT MANUAL FOR CONSTRUCTION SPECIFICATIONS AND BIDDING PROCEDURES.
- THE CONTRACTOR SHALL REFER TO THE ARCHITECTURAL PLANS FOR EXACT LOCATIONS AND DIMENSIONS OF THE ENTRANCE, PAVING, EXIT PORCHES, PRECISE BULLDING DIMENSIONS, AND EXACT BUILDING UTILITY ENTRANCE POINTS.
- ALL REQUIRED AND NECESSARY INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES AND/OR UTILITY SERVICE COMPANES SHALL BE PERFORMED PRIOR TO ANNOUNCED BUILDING POSSESSION AND THE FINAL SERVICE CONNECTIONS.
- THE CHARGE OF SPECIFICALLY CAUTIONED THAT THE LOCATION AND OR THE ELEVATION OF THE EXISTING UITLUTES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UITLUT COMPANIES AND WHERE POSSIBLE MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE FRUED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AND DIG SAFE AT LEAST ZP AUDIES PROPE TO ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELICATE THE AUST AND THE RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

THE UTILITIES INVOLVED WITH THIS PROJECT ARE LISTED BELOW:

UTILITY

OWNER PORTLAND WATER DISTRICT ATTH: DAVE COFFIN P.O. BOX 3553 PORTLAND, MAINE 04104 (207) 774-5961 WATER

CITY OF PORTLAND ATTN: FRANK BRANCELEY 55 PORTLAND STREET PORTLAND, MAINE 04101 (207) 874-8846 SANITARY SEWER

POWER

CENTRAL MAINE POWER COMPANY ATTN: PAUL DUPERRE 182 CANCO ROAD PORTLAND, MAINE 04103 (207) 828-2882

TELEPHONE

VERIZON ATTN: SUE SURETTE 5 DAVIS FARM ROAD PORTLAND, MAINE 04103 (207) 797-1842

DIGSAFE 1-888-344-7233

- MAINTENANCE OF EROSION CONTROL MEASURES IS OF PARAMOUNT IMPORTANCE TO THE OWNER AND THE CONTRACTOR IS RESPONSIBLE FOR COMPLINEN WITH ALL EROSION CONTROL MEASURES SHOWN ON THE FLANS. ADDITIONAL EROSION CONTROL MEASURES SHOWN ON THE PARAMETER OF DEEDED NOCESSARY BY OWNER WAS VIEW OF THE OWNER OR FOREMAND AND THE OWNER OR FOREMAND AND THE OWNER OR FLOREMAND AND ADDITIONAL COST TO THE OWNER.
- ALL MATERIAL SCHEDULES SHOWN ON THE PLANS ARE FOR GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL PREPARE HIS OWN MATERIAL SCHEDULES SHEDD UPON HIS PRAN REVEW. ALL SCHEDULES SHALL BE VERRIED IN THE FIELD BY THE CONTRACTOR PRIOR TO CRICIARON MATERIALS OF PERFORMING WORD.

LANDSCAPE NOTES:

- ALL PLANT MATERIALS SHALL MEET THE STANDARDS AS SET FORTH
 BY THE AMERICAN ASSOCIATION OF NURSER ME. ALL TREES, SHRUB
 BEDS, ETC. ARE TO BE MULCHED WITH 4" OF SHREDDED HARDWOOD
 BARK MULCH.
- ALL DISTURBED AREAS ARE TO RECEIVE A MINIMUM OF 4" OF TOPSOIL PRIOR TO PERMANENT SEEDING.

GRADING & DRAINAGE NOTES:

ALL STORM DRAIN PIPE SHALL BE SDR-35 POLYVINYL CHLORIDE PIPE OR HDPE N-12 UNLESS EXPOSED TO SUNLIGHT, IN WHICH CASE HDPE N-12 SHALL BE USED.

EROSION CONTROL NOTES:

- LAND DISTURBING ACTIVITIES SHALL BE ACCOMPLISHED IN A MANNER AND SEQUENCE THAT CAUSES THE LEAST PRACTICAL DISTURBANCE OF THE SITE.
- PRIOR TO BEGINNING ANY CLEARING/LAND DISTURBING ACTIVITIES, THE CONTRACTOR SHALL INSTALL THE PERIMETER SILT FENCES AND THE CONSTRUCTION ENTRANCE.
- ALL GROUND AREAS GRADED FOR CONSTRUCTION WILL BE GRADED, LOAMED AND SEEDED AS SOON AS POSSIBLE.
- PRIOR TO PAVING, THE CONTRACTOR SHALL FLUSH SILT FROM ALL STORM ORAIN LINES.
- SILT FENCES SHALL BE INSPECTED, REPAIRED AND CLEANED AS NECESSARY OR AS DIRECTED BY THE ENGINEER.
- THE CONTRACTOR SHALL REPAIR AND ADD STONE TO THE CONSTRUCTION ENTRANCE AS IT BECOMES SATURATED WITH MUD TO ENSURE THAT IT WORKS AS PLANNED DURING CONSTRUCTION.
- SILT REMOVED FROM AROUND INLETS AND BEHIND THE SILT FENCES SHALL BE PLACED ON A TOPSOL STOCKPILE AND MIXED INTO IT FOR LATER USE IN LANDSCAPING OPERATIONS.
- 8. THE CONTRACTOR IS CAUTIONED THAT FAILURE TO COMPLY WITH THE SCOURNE OF CONSTRUCTION, EROSION/SEDIMENT CONTROL PLAN, AND OTHER TREMER REQUIREMENTS MAY RESULT IN MOMENTARY PENALTIES. THE CONTRACTOR SHALL BE ASSESSED ALL SUCH PENALTIES AT NO COST TO THE OWNER OF PERMITTEE.

DEMOLITION NOTES:

- THE FOLLOWING ITEMS ARE TYPICAL OF THE MATERIALS WHICH MILL BE ENCOUNTERED DURING SITE CLEARING/DEMOLITION. THE BIDDER IS ADVISED IT OM MIST THE SITE TO CONFIRM DEMOLITION ITEMS SINCE THE LIST IS NOT ALL—ROCUSIVE OF THE SITE CONDITIONS WHICH MAY BE ENCOUNTERED:
 - CONCRETÉ FOUNDATIONS/SLABS
- CONCRETE FOUNTHINGS STABS
 BITUMINUS ASPHALT PAYEMENT
 CONCRETE PADS AND BLOCKS
 UNDERGROUND UTILITY LINES (ELECTRIC, WATER, SEWER)

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	PROPERTY/ROW LINE	
	CONSTRUCTION CENTERLINE -	
	GRANITE BOLLARD	•
9	IRON PIPE/ROD FOUND	
<u>A</u>	SURVEY CONTROL POINT	
O IRS	IRON ROD SET	
\$ 6-1	APPROX. TEST BORING LOCATION BY S.W. COLE	
& P-1	APPROX. TEST PROBE LOCATION BY S.W. COLE	⊕ B-1
₩ n=-:	HAND AUGER PROBES BY HEI 11/2005	
\$ 40−1	TEST PITS BY HEI 12/2005	
₽ 700 €	TEST PITS BY TEWHEY ASSOC. 04/2005	
\bigcirc	TREELINE	$\sim\sim\sim$
0	DECIDUOUS TREE	
*	CONIFEROUS TREE	
-12-	SIGN	-
	LIMIT OF WORK	
Ů	LIGHT POST	T S
,id	UTILITY POLE	ø
2259	ELECTRIC METER	
700	GRADING CONTOUR LINE	100
× 90.03	GRADING SPOT GRADE	107.70
	SILT FENCE	
	CATCH BASIN SEDIMENT TRAP	
	BUILDING	
	EDGE OF PAVEMENT	
	PAVED ISLAND w/CURB	
	CURB	
	PAVEMENT STRIPING	\square
e ja	FIRE HYDRANT	+
◆賞CB	CATCH BASIN	■ CB1
Own	MANHOLE	● DMH1
* 🖔	WATER GATE/VALVE	H
	FENCE	
	OVERHEAD WIRES -	
12"w	WATER LINE -	2"W
10"SD	STORM DRAIN LINE	10"50
	SANITARY SEWER LINE -	6"SAN
	UNDERGROUND ELECTRIC -	UGE
	- UNDERGROUND TELEPHONE -	ugt ———
	SIDEWALK	

P.E. DWIGHT D. ANDERSON JC. #9275

MARTIN'S POINT REDEVELOPMENT PROJECT


ASSOCIATES, INC.
779 MAIN STREET, SUTE 8
SOUTH FORTHARD, ME 04105
3017/5/1031
WWW.DELUCAHOFTMAN.COM

GENERAL NOTES & LEGEND
 DRAWN:
 LECJ
 DATE:
 NOV. 2005


 DESIGNED:
 DDA
 SCALE:
 N.T.S.

 CHECKED:
 DDA
 JOB NO.
 234401


 FILE NAME:
 234401-GEN
 MARTIN'S POINT HEALTH CARE




4.01\DWG\PERMIT SET\234401-SP.dwg, C-4A SITE LAYOUT PH1, 4/26/2066 5:04:43 PM, DDavis





:\2344.01\DWG\PERMIT SET\234401-SP.dwg, C-5A GRADING 30 SCALE PH1, 4/26/2006 5:12:18 PM, DDavis







































6'-0" MAX, SPACING*

ELEVATION VIEW





10' MIN. 20' MN.

PLAN VIEW

SECTION VIEW

STABILIZED CONSTRUCTION ENTRANCE


5" ø 2'-0" NYLON REINFORCED CELLULOSE GENERAL PURPOSE CONTAINMENT BOOM BY WRANGLER ZONE ENVIRONMENTAL PRODUCTS OR EQUAL

PROVIDE TEMPORARY ATTACHMENT FOR END OF BOOM ON CATCH BASIN SIDES OPPOSITE OUTLET PIPE


-EXISTING GROUND


NOTE: CONTRACTOR SHALL ADD STONE TO OR REMOVE AND RECONSTRUCT THE STABILIZED CONSTRUCTION ENTRANC AS MUD/SILT MATERIAL ACCUMULATI

(OPTIONAL)









HOMBAL PLAN RPRAP SEE SCHEDULE BELOW

—12° DEPTH, MOOT TYPE D SUBBASE GRAVEL


SECTION VIEW


42" 24' 28' 12" 27" 44" 28' 32' 12" 27

DeLUCA—HOFFMAN ASSOCIATES, INC. 778 MAIN STREET, SUITE 8 SOUTH PORTLAND, ME 04106 207,773-1731 WOWN DELUCAHOFFMAN COM

REDEVELOPMENT PROJECT EROSION CONTROL DETAILS

MARTINS POINT HEALTH CARE





Existing and Proposed Drainage Features

The site has steep topography sloping from Elevation 67 at the Marine Hospital building point to about elevation 30 at the lower parking area to the north. Drainage emanates from the site in all describes.

Limited existing formal drainage currently exists on the site.

The proposed drainage systems are not being designed to reduce peak discharge rates at or below existing levels. Instead, the flow will be conveyed in new storm drains to stable outfall points. The control of the peak runoff rates is discussed in more detail in the Stormwater Management Report provided as part of this application.

Critical Areas

The critical areas of the site are the steep slopes along the edge of the project and where grading will be required within the 75-foot setback from the resource boundary.

Erosion/Sedimentation Control Devices

The Contractor as part of the site development will implement the following erosion and sediment control devices. These devices shall be installed as indicated on the plans or as described within this report. For further reference, see the Maine Erosion and Sediment Control Handbook for

Siltation fence shall be installed downslope of any disturbed areas to trap runoff borne sediments until the site is revegetated. The silt fence shall be installed per the detail provided in the plan set and inspected immediately after each rainfall and at least daily during prolonged rainfall. Repairs shall be made immediately by the Contractor if there are any signs of erosion or sedimentation below the fence line. Proper placement of stakes and keying the bottom of the fabric into the ground is critical to the fence's effectiveness. If there are signs of undercutting at the center or the edges, or impounding of large volumes of water behind the fence, the barrier shall be replaced with a stone check dam.

Silt fence is shown by three types depending upon the timing and intent as follows:

Silt Fence	Type Purpose	Time of Installation
Type 1	To trap sediment along the grading edge where the new contours nearly parallel existing contours.	At initial site preparation, prior to other work.
Туре 2	To trap sediment from the work area; install in short sections parallel to existing contour; typically occurs where proposed and existing contours form a "V" shape.	At initial site preparation, prior to other work or as fills are blended to existing grades along the contour.
Туре 3	To trap sediment along the base of proposed contours, typically in cut areas.	During construction after new grade is shaped. Time betwee work in area and shaping new grade to allow sift fence to be installed shall be minimized.

- 2. Straw or hay mulch including hydroseeding is intended to provide cover for denuded or seeded areas until revegetation is established. Mulch placed on slopes of less than 10 percent shall be anchored by applying water, mulch placed on slopes steeper than 10 percent shall be covered with a fabric netting and anchored with staples in accordance with the manufacturer's recommendations. Proposed drainage channels, which are to be revegetated, shall receive Curlex blankets by American Excelsior or equal. Mulch application rates are provided in Attachment A of this section. Hay mulch shall be available on either a tall times in roduct or provide immediate lamparage shall ization when processor. on site at all times in order to provide immediate temporary stabilization when necessary. Where necessary for concentrated runoff to be conveyed down a slope, a temporary stone channel or pipe sluice shall be used to convey runoff down the slope
- Water quality systems will be required to provide water quality enhancement and sedimentation control for stormwater runoff from the parking and drive areas after
- 4. Riprap slopes, ditch linings, stone check dams, hay bale barriers, and culvert outlet aprons are intended to reduce runoff velocities and protect denuded soil surfaces from concentrated flows. Installation details and stone sizes are provided in the construction plan set on the
- 5. A construction entrance will be constructed at all access points onto the site to prevent
- Stone sediment traps or a premanufactured SillSack $^{\text{TM}}$ will be installed at catch basin inlets to prevent silt from entering the storm drain system. Installation details are provided in the plan set on the erosion control detail sheets.
- 7. Reinforced turf and mechanically stabilized turf slopes will be used on extremely steep slopes in areas designated on the drawings.
- 8. Dirtbags™ will be required to be on site and available for construction dewatering. The Contractor will be required to provide four Dirtbags ™ with one prepared for operation prior to commencing any trenching operations.
- 9. Loam and seed is intended to serve as the primary permanent revegetative measure for all denuded areas not provided with other erosion control measures, such as riprap. Specifi-areas as shown on the landscape plan will receive sod. Application rates are provided in Attachment A of this section for temporary and permanent seeding.
- 10. Sorbent oil bags will be required in catch basins which receive runoff from paved areas. The sorbent bags shall be places in the basin immediately prior to paving and remain in place to 60 60 days after paving operations are complete. After this time, the sorbent bags shall be removed and disposed of at an appropriate facility. The Contractor shall notify the Owner of the disposition location for the sorbent bags.
- 11. Water will be the principal means to control fugitive dust.

Temporary Erosion/Sedimentation Control Measures
The following are planned as temporary erosion/sedimentation control measures during

- 1. A crushed stone-stabilized construction entrance shall be placed at any construction access
- Type 1 and 2 siltation fence shall be installed along the downgradient side of the proposed improvement areas prior to work in these areas. Type 2 and 3 siltation fence shall be installed as work progresses. The siltation fence will remain in place and properly maintained until the site is acceptably revegetated.
- 3. Dirtbags™ shall be installed in accordance with the details in the plan set. The Dirtbags' Interest on the project is to receive any water pumped from excavations during construction. A Dirthag™ shall be installed any prepared for operation prior to any trenching on site. When Dirthag™ shall be installed any prepared for expective they shall be cleaned or replaced. Stone under the Dirthag™ shall be removed and replaced concurrently.
- 4. Temporary stockpiles of stumps, grubbings, or common excavation will be protected as follows:
- a. Temporary stockpiles shall not be located within 100 feet of the resource limits and at least
- Inactive stockpiles shall be stabilized within 5 days by either temporarily seeding the stockpile with a hydroseed method containing an emulsified mulch tackifier or by covering the stockpile with mulch. If necessary, mesh shall be installed to prevent wind from
- All denuded areas, which have been rough graded, shall receive mulch or erosion control
 mesh fabric within 14 days of initial disturbance of soil.

- All soils disturbed between November 1 and April 1 will be covered with mulch within 5 days
 of disturbance, prior to any predicted storm event of the equivalent of ½" of equivalent rainfall in a 24-hour period, or prior to any work shutdown lasting more than 35 hours (including weekends and holidays). The mulch rate shall be double the normal rate.
- 7. For work which is conducted between November 1 and April 15 of any calendar year, all denuded areas will be covered with hay mulch, applied at twice the normal application rate and (in areas over 10% grade) anchored with a fabric netting. The time period for applying mulch shall be limited to 5 days for all areas or immediately in advance of a predicted rainfall.
- Offsite roadways shall be swept to control mud and dust as necessary. A street sweeper shall be available from the Contractor on immediate notice or request from the Owner, City or regulatory agency. A water truck shall be used to control dust both on the site and along points of ingress and egress.
- During grubbing operations stone check dams or hay bale barriers shall be installed at any evident concentrated flow discharge points.
- 10. Silt fencing with a maximum stake spacing of 6 feet should be used, unless the fence is Slit frencing with a maximum stake spacing of 6 feet should be used, unless the fence is supported by wire fence reinforcement of minimum 14 gauge and with a maximum mesh spacing of 6 inches, in which case stakes may be spaced a maximum of 10 feet apart. The bottom of the fence should be properly anchorred a minimum of 6" per the plan detail and backfilled. Any slit fence identified by the owner or reviewing agencies, as not being properly installed during construction shall be immediately repaired in accordance with the
- 11. Storm drain catch basin inlet protection shall be provided through the use of stone sediment barriers or a premanufactured SiltSack™ as distributed by A. H. Harris Company, Portland, Maine. Stone sediment barrier installation details are provided in the plan set. The barriers or SiltSacks™ shall be inspected after each rainfall and repairs made as necessary, including or SitSacks™ shall be inspected after each rainfall and repairs made as necessary, including the removal of sediment. Sediment shall be removed and the barrier or SittSack ™ restore to its original dimensions when the sediment has accumulated to ½ the design depth of the barrier. Sediment shall be removed from SittSacksTM as necessary. Inlet protection shall be removed when the tributary drainage area has been stabilized
- 12. All slopes over 4:1 shall receive erosion control mesh
- 13. Slopes steeper than 3:1 shall receive reinforced turf unless rip rap or other nonvegetative stabilization measures are required by the contract.
- 14. Type 2 and 3 silt fence shall be installed as construction progresses
- 15. Areas of visible erosion shall be stabilized with crushed stone. The Owner's representative in consultation with the engineer shall determine the size of the stone.
- 16. Catch basins shall all be installed with an opening 2'-6" below finish grade to receive a 4" underdrain with an end cap. A 3"-0" stub of underdrain surrounded by 6" of %" crushed stone and filter fabric shall be installed.
- 17. All catch basins which receive parking lot runoff shall have a sorbent bag installed as described in section 14.5 of this narrative.

- Standards for Stabilizing Sites for the Winter

 1. Standard for the timely stabilization of ditches and channels: The contractor shall construct and stabilize all stone-lined ditches and channels on the site by November 15. The contractor shall construct and stabilize all grass-lined ditches and channels on the site by September 15. If the contractor fails to stabilize a ditch or channel to be grass-lined by
- Install a sod lining in the ditch. The contractor shall line the ditch with properly install sod by October 1. Proper installation includes the applicant pinning the sod onto the soi with wire pins, rolling the sod to guarantee contact between the sod and underlying sol, watering the sod to promote root growth into the disturbed soil, and anchoring the sod with jute or plastic mesh to prevent the sod strips from sloughing during flow conditions
- Install a stone lining in the ditch. The contractor shall line the ditch with stone riprap by November 15. The contractor shall hire a registered professional engineer to determine the stone size and lining thickness needed to withstand the anticipated flow velocities and flow depths within the ditch. If necessary, the contractor shall regrade the ditch prior to placing the stone lining so as to prevent the stone lining from reducing the ditch's
- Standard for the timely stabilization of disturbed slopes: The contractor shall construct and
 stabilize stone-covered slopes by November 15. The contractor shall seed and mulch all
 slopes to be vegetated by September 15. The department viil consider any area having a
 grade greater than 15% (10H: 11V) to be a slope. If the contractor fails to stabilize any slope
 to be vegetated by September 15, then the contractor shall take one of the following actions
 to slobilize the slope for late fall and winter.
- Stabilize the soil with temporary vegetation and erosion control mesh. By October 1 the contractor shall seed the disturbed slope with winter rye at a seeding rate of 3 pounds per 1000 square feet and apply erosion control mats over the mulched slope. The contractor shall monitor growth of the rye over the next 45 days. If the rye fails to grow at least three inches or fails to cover at least 75% of the disturbed slope by November
- ii. Stabilize the slope with sod. The contractor shall stabilize the disturbed slope with properly installed sod by October 1. Proper installation includes the contractor pinning the sod onto the slope with wire pins, rolling the sod to guarantee contract between the sod and underlying soil, and watering the sod to promote root growth into the disturbed soil. The contractor shall not use late-season sod installation to stabilize slopes having a grade greater than 33% (3H: 1V) or having groundwater seeps on the slope fac
- iii. Stabilize the slope with woodwaste compost. The contractor shall place a six-inch layer of woodwaste compost on the slope by November 15. Prior to placing the woodwaste compost, the contractor shall remove any snow accumulation on the disturbed slope. The contractor shall not use woodwaste compost to stabilize slopes having grades greater than 50% (2H: 1V) or having groundwater seeps on the slope face.
- iv. Stabilize the slope with stone rip rap. The contractor shall place a layer of stone riprap on the slope by November 15. The contractor shall hire a registered professional engineer to determine the stone size needed for stability and to design a filter layer for
- Standard for the timely stabilization of disturbed soil: By September 15, the contractor shall seed and mulch all disturbed soils on areas having a slope less than 15%. If the contractor fails to stabilize these soils by this date, then the contractor shall take one of the following actions to stabilize the soil for late fall and winter
- Stabilize the soil with temporary vegetation. By October 1, the contractor shall seed the disturbed soil with winter rye at a seeding rate of 3 pounds per 1000 square feet, lightly mulch the seeded soil with hay or straw at 75 pounds per 1000 square feet, and anchor the mulch with plastic netting. The contractor shall monitor the growth of the rye over the 45 days. If the rye fails to grow at least three inches or fails to cover at least 75% of the disturbed soil before November 15, then the contractor shall mulch the area for -winter protection as described in item iii of this standard
- ii. Stabilize the soil with sod. The contractor shall stabilize the disturbed soil with properly installed sod by October 1. Proper installation includes the contractor pinning the sod onto the soil with wire pins, rolling the sod to guarantee contact between the sod and underlying soil, and watering the sod to promote root growth into the disturbed soil.

iii. Stabilize the soil with mulch. By November 15, the contractor shall mulch the disturbed soil by spreading hav or straw at a rate of at least 150 pounds per 1000 square feet on the area so that no soil is visible through the mulch. Prior to applying the mulch, the contractor shall remove any snow accumulation on the disturbed area. Immediately after applying the mulch, the contractor shall anchor the mulch with plastic netting to prevent wind from moving the mulch off the disturbed soil.

Sedimentation Sumps
The use of shallow sediment sumps on the downgradient side of erodible stockpiles and areas
The sediment sumps may be where denuded conditions will be prolonged is encouraged. The sediment sumps may be installed and used in conjunction with the underdrain inlets at catch basins.

Permanent Erosion Control Measures
The following permanent erosion control measures have been designed as part of the Erosion/Sedimentation Control Plan:

- 1. All storm drain pipes which are not connected to a formal inlet or outlet shall have riprap aprons at their outlet to protect the outlet and receiving channel from scour and deterioration. Installation details are provided in the plan set. The aprons shall be installed and stabilized prior to directing runoff to the tributary pipe or culvent. It is noted that all inlets and outlets over 18" in diameter are to have a flared concrete inlet and an aluminum bar rack. Pipes less than 18 inches in diameter are to have an HDPE flare. Riprap shall not be extended above the area shown on the plans.
- All areas disturbed during construction, but not subject to other restoration (paving, riprap, etc.) will be loamed, limed, fertilized, mulched, and seeded. Fabric netting, anchored with staples, shall be placed over the mulch in areas where the finish grade slope is greater than 10 percent except in the areas with over 3:1 slopes where reinforced turf is required. Native topsoil shall be stockpiled and temporarily stabilized with seed and mulch and reused for final restoration when it is of sufficient quality. Where necessary, compost shall be added and
- 3. Catch basins shall be provided with sediment sumps for all outlet pipes that are 12" in
- 4. Permanent water quality measures will be installed.

Timing and Sequence of Erosion/Sedimentation Control Measures

The following construction sequence shall be required to insure the effectiveness of the erosion dimentation control measures are optimized. These measures are separate from the te requirements to be employed during the building demolition phase of the project.

Note: For all grading activities, the Contractor shall exercise extreme caution not to overexpose the site by limiting the disturbed area.

- Install crushed stone-stabilized construction entrances from Veranda Street the as shown on the Erosion and Sedimentation Control Drawing.
- 2. Install Type 1 and appropriate Type 2 siltation.
- Establish and prepare Dirtbag[™] area
- 4. Perform demolition activities and major site cuts and fills and blasting.
- 5. Install water quality systems and the storm drain system.
- 6. Construct diversion and drainage channels to direct flow to new storm drain and inlets where
- 7. Install stone and hay bale check dams at any concentrated flow discharge points.
- 8. Prepare the subgrade, parking areas, building, and drive loop
- Install storm drain, underground electric, foundations and other utility work. Install inlet and outlet protection immediately after the installation of any inlets. Pump any accumulated water to the Dirtbag™
- 10. Bring initial site work area to subgrade including binder pavement, stabilization of all slopes,
- 11. Construct other site improvements and utilities
- 12. Raise catch basins to grade and install inlet protection devices.
- 13. Install sorbent bags in catch basins which will receive runoff from pavement
- 14. Install final payement as detailed on the site plans
- 15. Loam, lime, fertilize, seed and mulch all remaining disturbed and denuded areas.
- 16. Remove all accumulated sediment from silt barriers
- 17. Review stability of the site. If a 75% catch of grass is achieved, remove all other temporary

Soil will be considered disturbed if it does not have an established stand of vegetation covering at least 75% of the soil surface or has not been mulched with hay applied at a rate of 230

It is anticipated that site work may be suspended prior to winter. If so, the General Contractor shall schedule a meeting with the City, Owner, and Owner's representatives to review the site conformance with the plan. This meeting shall be scheduled at least 10 days prior to winter shutdown. The Owner may elect to provide the Contractor with a punch list for measures to be complete before the interim shutdown. The Owner's punch list shall not obviate the Contractor's responsibility for compliance with the erosion control requirements of the project or permits.

Construction of Improvements at Veranda Street may be conducted concurrently or following site

Contracting Procedure
A General Contractor under contract to Martin's Point will construct the project. The Contractor shall submit a schedule for the completion of the work which will satisfy the following criteria:

- 1. The above construction sequence should generally be completed in the specified order however, several separate lems may be constructed simultaneously. Work must also be scheduled or phased to prevent the extent of the exposed areas as specified below. The intent of this sequence is to provide for erosion control and to have structural measures such as sitt fence and construction entrances in place before large areas of land are denuded.
- 2. The work shall be conducted in sections which will:

NOTE: THIS EROSION AND SEDIMENT CONTROL NARRATIVE

APPLIES TO THE FULL DEVELOPMENT OF THE SITE BEYOND

THE LIMITS OF PHASE I WORK, CONTRACTOR IS REQUIRED.

TO FOLLOW ALL EROSION AND SEDIMENT CONTROL

REQUIREMENTS APPLICABLE TO PHASE LWORK

- a. Limit the amount of exposed area to those areas in which work is expected to be undertaken during the proceeding 30 days
- b. Revegetate disturbed areas as rapidly as possible. All areas shall be permanently stabilized within 7 days of final grading or before a predicted storm event; or temporarily stabilized within 7 days of initial disturbance of soil for areas identified as critical (refer to paragraph 14.4.A) and 14 days for all other areas.

- Incorporate planned inlets and drainage system as early as possible into the construction phase. The ditches shall be immediately lined or revegetated as soon as their installation
- Once final grade has been established, the Contractor may choose to dormant seed the disturbed areas prior to placement of mulch and placement of fabric netting anchored with
- If dormant seeding is used for the site, all disturbed areas shall receive 4" of loam and seed at an application rate of 5#/1000 s.f.

All areas seeded during the winter months will be inspected in the spring for adequate catch. All areas insufficiently vegetated (less than 75 percent catch) shall be revegetated by replacing loam, seed and mulch.

- b. If dormant seeding is not used for the site, all disturbed areas shall be revegetated in the
- 4. The area of denuded non-stabilized construction shall be limited to the minimum area practicable. An area shall be considered to be denuded until the subbase gravel is installed in parking areas or the areas of future loam and seed have been loamed, seeded, and mulched. The mulch rate shall be twice the rate specified in the seeding plan. [For example, 115#/1.000 s.f. x 2 = 230#/1,000s.f.]
- 5. Within the exposed work area, temporary sedimentation sumps shall be provided at the interface between parking areas and graded slopes (refer to paragraph 14.7). This shall be accomplished by creating an area 18* below adjacent temporary grades. The sedimentation area shall have a bottom width of 3' and 3:1 side slopes. Culverts to allow access shall be installed by the Contractor. Along the sedimentation sumps, barriers shall be provided at sufficient intervals to permit runoff to be accumulated to a minimum depth of 12" before
- 6. The schedule shall be subject to the approval of the Owner

The Contractor must install any added measures, which may be necessary to control erosion/sedimentation from the site and fugitive dust emissions dependent upon the actual site and weather conditions.

The applicant may be required to retain a third party inspector. The Contractor shall cooperate with the third party inspector and permit access to the site by the inspector at all times.

The Contractor shall note that no area within 50 feet of a slope with a vertical drop of more than 3' in 50 feet shall remain denuded for a period of over 5 days before it is temporarily stabilized. Temporary stabilized of the stabilized within 14 days. For construction between November 1 and April 15 of any calendar year, all areas shall be temporarily stabilized at the earlier time frames specified above

Provisions for Maintenance of the Erosion/Sedimentation Control Features The Owner will contract the project. The project is subject to the requirement of a MeDEP Site In e Owner will contract the project. The project is subject to the requirement of a MeDEP Site Location of Development Permit administered through the City of Portland and a MeDEP Permit for Stormwater Pollution Prevention Plan during Construction. These permits require the Contractor to prepare a list and designate by name, address and telephone number all individuals who will be responsible for implementation, inspection and maintenance of all erosion control measures identified within this section and as contained in the Erosion and Sedimentation Control Plan of the contract drawings. Specific responsibilities of the inspector(s) will include:


- 1. Execution of the Contractor/Subcontractor Certification contained in Attachment B by any and all parties responsible for erosion control measures on the site as required by the MeDEP.
- Assuring and certifying the Owner's construction sequence is in conformance with the specified schedule of,this section. A weekly certification stating compliance, any deviations, and corrective measures necessary to comply with the erosion control requirements of this section shall be prepared and signed by the inspector(s).
- 3. In addition to the weekly certifications, the inspector(s) shall maintain written reports recording construction activities on site which include
- · Dates when major grading activities occur in a particular areas
- · Dates when major construction activities cease in a particular area, either temporarily or
- 4. Inspection of this project work site on a weekly basis and after each significant rainfall event (0.5 inches or more within any consecutive 24 hour period) during construction until permanent erosion control measures have been properly installed and the site has been stabilized. Inspection of the project work site shall include:
- Identification of proper erosion control measure installation in accordance with the erosion control detail sheet or as specified in this section.
- Determine whether each erosion control measure is properly operating. If not, identify damage to the control device and determine remedial measures.
- measures that should be used to improve conditions Inspect areas of recent seeding to determine percent catch of grass. A minimum catch of rcent is required prior to removal of erosion control mea
- Record date of installation of sorbent bags in catch basins, the dates of paving, the date
 of removal, and the disposal method and location.

Accumulated sitt/sediment should be removed when the depth of sediment reaches 50 percent of the barrier height. Accumulated silf/sediment should be removed from behind silt fencing when the depth of the sediment reaches 6 inches. 5. If inspection of the site indicates a change should be made to the erosion control plan, either

to improve effectiveness or correct a site-specific deficiency, the inspector shall immediately implement the corrective measure and notify the owner of the change. Once construction has been completed, long term maintenance of the detention pond and catch basins will be the responsibility of the applicant. The catch basin sumps shall be inspected in April and October of each year. Sediment shall be removed when the depth of sediment reaches

All certifications, inspection forms and written reports prepared by the inspector(s) shall be filed with the Owner, and the MeDEP General Construction Permit File contained on the project site. All written certifications, inspection forms, and written reports must be filed within one (1) week of

Preconstruction Conference
Prior to any construction at the site, representatives of the Contractor, and the site design engineer shall arrange for and meet with the Owner to discuss the scheduling of the site construction. On or before that meeting, the Contractor will prepare a detailed schedule and a marked-up site plan indicating areas and components of the work and key dates showing date of disturbance and completion of the work. Three copies of the schedule and marked-up site plan shall be provided to the Owner.



MARTIN'S POINT REDEVELOPMENT PROJECT


EROSION AND SEDIMENT CONTROL NARRATIVE

778 MAIN STREET, SUITE 8
SOUTH PORTLAND, ME 94108
207.775.1924

MARTINS POINT HEALTH CARE

eLUCA-HOFFMAN

ASSOCIATES, INC



MARTINS POINT HEALTH CARE

G:\2344.01\DWG\PERMIT SET\234401-DET.dwg, SHEET 14 MISC. 4/26/2006 5:21:20 PM, DDavis

god Helkoni he

\B6044\86044.dwg Ned Dec 07 13:01:59 2005



MARTIN'S POINT - PHASE ONE MARINE HOSPITAL RENOVATION 331 Veranda Street, Portland ME 04103

CLIENT:


MARTIN'S POINT HEALTH CARE PORTLAND, MAINE

ARCHITECT:



CONSULTANTS:

- STRUCTURAL Becker Structural Portland, ME
- CIVIL DeLuca Hoffman Associates, Inc. South Portland, ME
- CONTRACTOR Ledgewood Construction South Portland, ME
- SPECIFICATIONS Lowell Specifications



I. THESE NOTES ARE INTENDED FOR GENERAL REFERENCE AND INFORMATION AND TO AUGMENT THE CONTRACT.

2. ALL WORK INCLUDED IN THIS CONTRACT SHALL CONFORM TO ALL NATIONAL, STATE, AND LOCAL CODES, ORDINANCES AND AGENCY REQUIREMENTS INCLUDING, BUT NOT LIMITED TO: HAZARDOUS MATERIAL REMOVAL, SOLID WASTE DISPOSAL, SEISMIC DESIGN, AND

- NEW: MAY BE USED TO INDICATE ITEMS WHICH SHALL BE FURNISHED AND INSTALLED BY THIS CONTRACT. TYPICALLY USED TO ENSURE CLARITY BETWEEN VARIOUS COMPONENTS OF THE DRAWINGS, NOT ALL ITEMS ARE LABELED AS "NEW" WHEN IT IS OBVIOUS BY OTHER INDICATION.

- EXISTING: EXISTING BUILDING OR SITE COMPONENTS WHICH ARE IN PLACE AT THE START OF CONSTRUCTION.

NOT ALL ITEMS ARE LABELED AS "EXISTING" WHEN IT IS

OBVIOUS BY OTHER INDICATION. CONSULT THE

ARCHITECT FOR CLARIFICATION.
- REPAIR: RESTORE TO PROPER OPERATING AND AESTHETIC CONDITION. - RESTORE: BRING BACK TO FORMER CONDITION, BY

REPAIRING OR PATCHING AS REQUIRED. - PATCH: RESTORE TO CONDITION MATCHING EXISTING ADJACENT CONSTRUCTION, SURFACE TEXTURE AND FINISH

- N.I.C. (NOT IN CONTRACT): WORK WHICH IS NOT INCLUDED IN THIS CONTRACT, BUT WHICH MAY REQUIRE CONTRACTOR COORDINATION.

- REMOVE: DISMANTLE AND/OR EXTRACT FROM THE PREMISES ENTIRELY. DISPOSE OF OFF SITE UNLESS NOTED OTHERWISE.

- REPLACE: DISMANTLE AND/OR EXTRACT FROM THE PREMISES ENTIRELY. DISPOSE OF OFF SITE UNLESS NOTED OTHERWISE. PROVIDE NEW MATERIAL AS INDICATED.

- DEMOLISH: DISMANTLE AND/OR EXTRACT FROM THE PREMISES ENTIRELY. DISPOSE OF OFF SITE UNLESS NOTED OTHERWISE

- SALVAGE: REMOVE AND REINSTALL OR REMOVE AND DELIVER TO THE OWNER, AS INDICATED. 4. COORDINATE THE WORK OF ALL SUBCONTRACTORS.

5. PROVIDE WORK HOLES AND ACCESS HOLES TO INSTALL NEW SYSTEMS IN CONCEALED SPACES, AS REQUIRED OR INDICATED. REPAIR THE OPENINGS AS 6. IT IS THE INTENT OF THE DRAWINGS AND SPECIFICATIONS TO HAVE THE CONTRACTOR PROVIDE A COMPLETE, FULLY OPERATIONAL BUILDING. PROVIDE ALL LABOR, MATERIALS AND INCIDENTALS NECESSARY TO ACHIEVE THIS INTENT. FAILURE OF THE DRAWINGS OR SPECIFICATIONS TO INDICATE EACH INCIDENTAL SHALL NOT RELIEVE THE CONTRACTOR FROM PROVIDING THE NECESSARY ITEMS AS PART OF THIS CONTRACT. THE DRAWINGS SHOW THE DESIGN AND LAYOUT, DESCRIBE THE QUALITY LEVEL AND CONSTRUCTION TECHNIQUES IN A GENERAL SENSE ONLY. ALL DETAILS ARE TYPICAL. WHAT IS SHOWN IN ONE CONDITION APPLIES TO ALL OTHER SIMILAR CONDITIONS, UNLESS NOTED OTHERWISE.

7. VERIFY THE FOLLOWING ITEMS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT PRIOR TO PROCEEDING WITH WORK, AND PROCEED WITH THE WORK ONLY AFTER SUCH DISCREPANCIES ARE RESOLVED BY

- THE SIZE AND LOCATION OF ALL EXISTING UTILITIES. - DISCREPANCIES BETWEEN OR WITHIN THE CONTRACT **DOCUMENTS**

- UNSUITABLE SOILS: REPORT THE LOCATION OF ALL UNSUITABLE SOIL MATERIALS BELOW ANTICIPATED LEVELS OF FOOTINGS OR SLABS PRIOR TO SETTING

- MECHANICAL, ELECTRICAL AND PLUMBING COORDINATION HAVING POTENTIAL IMPACT ON CEILING HEIGHTS OR BUILDING APPEARANCE - DIMENSIONAL DISCREPANCIES

8. PROVIDE BOND-OUTS, BLOCKING, SLEEVES AND PIPES AS REQUIRED FOR ALL WALL, FLOOR, ROOF, AND CEILING PENETRATIONS THROUGH STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF STRUCTURAL, MECHANICAL, PLUMBING AND ELECTRICAL COMPONENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SEALING ALL PENETRATIONS IN FIRE RATED ASSEMBLIES AND SMOKE ASSEMBLIES TO CONFORM TO U.L. RATED ASSEMBLIES AND ALL NFPA AND BOCA BUILDING CODE REQUIREMENTS. ALL PENETRATIONS SHALL ALSO COMPLY WITH THE ACOUSTICAL ASSEMBLY RATING REQUIRED FOR EACH

9. DO NOT PENETRATE STRUCTURAL BEAMS, COLUMNS, OR

Project No. 05-108 April 24, 2006 **Bid Documents**

DRAWING LIST

#	DRAWING TITLE
TI	TITLE SHEET

CIVIL DRAWINGS

AOI

COVER SHEET GENERAL NOTES AND LEGEND SITE LAYOUT AND UTILITY PLAN PAHSE I C-4A C-5A SITE GRADING & EROSION CONTROL PLAN -

PHASE

MATER DETAILS EROSION CONTROL DETAILS

EROSION AND SEDIMENT CONTROL NARRATIVE

MISCELLANEOUS SITE DETAILS

ARCHITECTURAL DRAWINGS

CODE PLAN BASEMENT & FIRST FLOOR DEMOLITION PLAN SECOND AND THIRD FLOOR DEMOLITION PLAN EXTERIOR DEMOLITION ELEVATIONS

BASEMENT AND FIRST FLOOR PLAN Al.2 SECOND AND THIRD FLOOR PLAN BASEMENT AND FIRST FLOOR CEILING PLAN A2.I

SECOND AND THIRD FLOOR CEILING PLAN A2.2 A41

EXTERIOR ELEVATIONS A4.2 EXTERIOR ELEVATIONS, BUILDING SECTIONS

A4.3 PARTIAL EXTERIOR ELEVATIONS

WALL SECTIONS, A6.2 WALL SECTION DETAILS

A6.3 DOOR AND WINDOW DETAILS A7.I ENLARGED CORE PLAN AND DETAILS

ENTRY STAIR / RAMP DRAWINGS

STRUCTURAL DRAWINGS

GENERAL NOTES & TYP DETAILS

EXIST FIRST & SECOND FLOOR FRAMING PLANS EXIST THIRD FLOOR & ROOF FRAMING PLANS

CONCRETE SECTIONS & DETAILS FRAMING SECTIONS & DETAILS FRAMING SECTIONS & DETAILS

DARTMOUTH STREET PORTLAND, ME 04101 207 775-1059 207 775-2094 FAX × COPYRIGHT 2006 PDT Architects

ROOM 321

325

[35]

ROOM 333

ROOM

120

ROOM 124

126

ROOM 199

Reuse or reproduction of the contents of this document is no permitted without written Щ

 \mathbf{Z}

 \vdash ¥ Renovation \mathbb{X} Ω Z A \dashv H \aleph [ospital 0 പ് Z 0 arine \mathbf{S} Z Z H

05-108

 \simeq ¥

 \mathbb{X}

3/32"=1'-0"

Bid Document

24 April 2006

Code Plans

SHEET N

ROOM ROOM IIS REMOVE ALL WALL TILE TO BASE WALL ROOM 104 ROOM REMOVE ALL WALL TILE TO BASE WALL **200**M REMOVE MAIL ---BOX AND BASE ROOM 102 ROOM 124 103 114 ROOM ROOM IOO ROOM 125 repositioned Floor Level EXISTING DOOR STOP SYSTEM ROOM ROOM 140 **|----**REMOVE EXISTING FRAMING FOR NEW CONSTRUCTION ROOM -REPLACE LOWER PANES W CLEAR GLASS ROOM 184 @ ₹ ROOM [27] - EXPOSE FLOOR FRAMING -OVER EXIST WINDOWS AT ALL LOAD BEARING WALLS ROOM [45] ROOM 198 ROOM 44 ROOM 192 2 A4.1 2 FIRST FLOOR LEGEND EXISTING PARTITIC TO REMAIN

A4.I

OVER EXIST WINDOWS AT ALL LOAD BEARING WALLS

GENERAL PATCHING AND REPAIR NOTES

DAMAGES: EXISTING BUILDING OR SITE COMPONENTS, NOT SCHEDULED FOR NORK, WHICH ARE DAMAGED SHALL BE REPLACED OR RESTORED TO ORIGINAL CONDITION BY METHODS APPROVED BY THE ARCHITECT.

ROOM 107

REPLACE LOWER-PANES W/ CLEAR

- 2. PATCHING: AFTER REMOVAL OF BUILDING COMPONENTS AS INDICATED, PATCH AND PREPARE THE REMAINING EXISTING EXPOSED SURFACES TO RECEIVE NEW NORK AND FINISH. FOR EXAMPLE. LEVEL FLOORS AT MALL REMOVALS, TOOTH-IN NEW CMU AT OPENINGS, PIECE-IN NEW PLASTER BACKING AND FINISH FLUSH; PIECE IN NEW CEILING SUSPENSION SYSTEM.
- WHERE NEW CONSTRUCTION EITHER INFILLS OR ABUTS EXISTING CONSTRUCTION, THE FINISHED FACES SHALL ALIGN, AND THE SURFACES SHALL BE FINISHED TO MATCH.
- 4. PATCH AND LEVEL EXISTING FLOORS TO RECEIVE NEW FINISHES AS INDICATED IN THE ROOM FINISH SCHEDULE.
- AFTER REMOVAL OF BUILDING COMPONENTS, ANY RESULTING HOLES SHALL BE PATCHED. MAINTAIN EXISTING FIRE- OR SMOKE-RATINGS AS INDICATED. SUCH PATCHES SHALL BE FLUSH MITH ADJACENT SURFACES AND FINISHED TO MATCH.
- ALL WALL, AND FLOOR FINISHES TO BE REMOVED, ALL ACT & CEILING GRIDS.

DEMOLITION KEY NOTES:

MALL DEMO

REMOVE INDICATED WALLS IN THEIR ENTIRETY PATCH AND REPAIR TO MATCH ADJACENT SURFACES, WII - REMOVE WALL PANELS FINISH AND PREP SURFACE FOR PAINT CELLINGS

REMOVE SUSPENDED CEILINGS ON ALL FLOORS. CI - REMOVE DROPPED SOFFIT

DI - REMOVE DOOR, DOOR FRAME AND THRESHOLD, IF ANY.

GENERAL DEMOLITION AND REMOVAL NOTES

- THE DEMOLITION DRAWINGS PROVIDE GENERAL COORDINATION INFORMATION ONLY, AND ARE SCHEMATIC IN NATURE. THEY DO NOT IDENTIFY ALL INDIVIDUAL ITEMS TO BE REMOVED. IN INSTANCES WHERE WALLS ARE NDICATED FOR REMOVAL, REMOVE ALL DOORS, WINDOWS, AND MISCELLANEOUS HARDWARE, ELECTRICAL AND MECHANICAL ITEMS CONTAINED WHITHIN THE WALL. REMOVE ANY EXISTING CONSTRUCTION WHICH LOSICALLY IS IN THE WAY OF NEW CONSTRUCTION OR PROHIBITS THE NEW CONSTRUCTION SHOWN ON THE ARCHITECTURAL FLOOR PLANS. NOTE: SOME DEMOLITION WORK IS INDICATED ON THE BUILDING ELEVATIONS.
- 2. VERIFY EXISTING STRUCTURAL CONDITIONS PRIOR TO DEMOLITION OR REMOVALS.
- PROTECT FROM DAMAGE AND WEATHER ANY EXISTING BUILDING COMPONENTS, WHICH ARE EXPOSED AS A RESULT OF DEMOLITION OR REMOVALS.
- 4. SOME ASBESTOS-CONTAINING MATERIAL MAY BE ENCOUNTERED, AND SHOULD BE ANTICIPATED. THE CONTRACTOR MAY DISCOVER MISCELLANEOUS UNDISCOVERED PIECES OF ASBESTOS WHICH NEED TO BE REMOVED. NOTIFY THE ARCHITECT IMMEDIATELY UPON DISCOVERY OF POTENTIALLY ASBESTOS CONTAINING MATERIAL.
- REMOVE ALL EXISTING PLUMBING AND MECHANICAL ITEMS NOT TO BE USED IN NEW CONSTRUCTION, AND REMOVE ENTIRE ELECTRICAL SYSTEM AND ALL COMPONENTS, USED OR UNUSED. COORDINATE THE INFORMATION ON DRAWINGS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT PRIOR TO PROCEEDING MITH THE WORK.
- REMOVAL OF THE MATERIALS AS INDICATED SHALL BE DONE WITHOUT DISTURBING ADJACENT SURFACES TO REMAIN OR THE CURRENT CONDITION OF THE BUILDING ELEMENTS.
- REMOVE ALL DAMAGED AND/OR DISCARDED BUILDING CONSTRUCTION MATERIAL FROM CONCEALED SPACES, FRIOR TO CLOSING- OR SEALING-OFF CONCEALED SPACES, THE CONTRACTOR SHALL ALLOW FOR AN INSPECTION OF COMPONENTS WHICH WILL NOT BE VISIBLE WHEN THE SPACES HAVE BEEN SEALED.
- 8. CUT TRENCHES IN EXISTING CONCRETE FLOORS WITH NO MORE THAN A 1:2 SLOPE. PATCH CONCRETE TO MATCH ADJACENT THICKNESS AND FINISH PRIOR TO THE INSTALLATION OF UNDERLAYMENT OR NEW FINISHES.
- ALL DEMOLITION/REMOVAL DEBRIS IS THE PROPERTY OF THE CONTRACTOR, UNLESS NOTED OTHERWISE.
- IO. SALVAGE: SALVAGE CERTAIN COMPONENTS FOR LIMITED REUSE TO MATCH EXISTING CONDITIONS FOR PATCH AND REPAIR AS INDICATED
- THE CONTRACTOR MAY REPLACE SALVAGED ITEMS WITH NEW AND IDENTICAL MATERIALS ONLY WITH THE ARCHITECT'S PRIOR APPROVAL.
- AT ALL EXISTING OPENINGS WHERE DOOR HAS ALREADY BEEN REMOVED, REMOVE HINGES, STRIKE PLATES AND ANY OTHER HARDWARE 13. PLIMBING AND HEATING SHAFT DEMOLITION NOT SHOWN ON DEMOLITION PLANS COORDINATE ADDITIONAL DEMOLITION TO ACCOMPDATE MECHANICAL AND ELECTRICAL

enovation \mathbb{Z} Д \boldsymbol{Z} A $\vec{\Box}$ ~ Hospital0 4 Z 0 arine Д \mathbf{Z} H \approx

ROOM

ROOM

COPYRIGHT 2006 PDT Architects Reuse or reproduction of the contents of this document is no permitted without written permission of PDT Architects

 \mathbf{Z}


 \mathbf{X} 05-108

1/8"=1'-0" ISSUE

24 April 2006

TITLE Demolition Basement and First Floor

SHEET



-REMOVE FIRE ESCAPE

ACESS TO ROOM

3 ROOF PLAN

DI - REMOVE DOOR, DOOR FRAME AND THRESHOLD, IF ANY.

NI

THE CONTRACTOR MAY REPLACE SALVAGED ITEMS WITH NEW AND IDENTICAL MATERIALS ONLY WITH THE ARCHITECT'S PRIOR APPROVAL.

12. AT ALL EXISTING OPENINGS WHERE DOOR HAS ALREADY BEEN REMOVED, REMOVE HINGES, STRIKE PLATES AND ANY OTHER HARDWARE

IS. PLUMBING AND HEATING SHAFT DEMOLITION NOT SHOWN ON DEMOLITION PLANS COORDINATE ADDITIONAL DEMOLITION TO ACCOMPDATE MECHANICAL AND ELECTRICAL.

DARTMOUTH STREET PORTLAND, ME 04101 207 775-1059 207 775-2694 FAX I

ပ

COPYRIGHT 2006 PDT Architects

ĮΠ

 \mathbf{Z} Ą enovation Ξ Д \mathbf{z} \forall \Box \simeq Hospital 0 Д \mathbf{z} 0 arine α \mathbf{Z} \mathbb{R}

X

DRWN, CHK

AS NOTED

Bid Documen 24 April 2006

econd and Third Floor Plans

D1.2



DARTMOUTH STREET PORTLAND, ME 04101 207 775-1059 207 775-2694 FAX ш

COPYRIGHT 2006 PDT Architects

Reuse or reproduction of the contents of this document is no permitted without written permission of PDT Architects

Щ

 \mathbf{Z} K Renovation \mathbb{X} Ω Z A \Box H \mathbf{z} Hospital 0 Д \mathbf{Z} Η 0 arine ď

Z

 \approx

 \mathbb{X}

X

JOB NO 05-108

DRWN. CHK

SCALE: AS NOTED


Bid Docu

24 April 2006 TITLE

DEMOLITION

SHEET

D4.1





COPYRIGHT 200

 Ξ

 \mathbf{Z}

 \forall enovation \mathbb{X} Ω \mathbf{Z} V \Box K H \approx ospital 0 ď H \mathbf{Z} I \vdash 0

0 \mathbf{d}

arin \mathbf{S}

Z

H \simeq

¥

 \mathbb{X}


05-108 DRWN. CHK

1/8"=1'-0"

ISSUE Bid Documents 24 April 2006

Lower Level and First Floor Plan

SHEET



ARCHITECTURE INTERIOR DESIGN PLANNING

 \mathbf{Z}

¥ Renovation \mathbb{Z} Ω \mathbf{Z} \forall \Box H \simeq Hospital 0 Д \mathbf{Z} 0 Marine Д $\mathbf{z}^{\mathbf{z}}$ \approx \mathbb{X}


05-108

SCALE: AS NOTED

24 April 2006

Second and

Third Floor Plan



- Ceiling plans shall govern over all other plans for location of fixtures and diffusers.
- Ceiling plans do not show every fixture or component. Refer to electrical, plumbing, mechanical and structural drawings for extent of all ceiling penetrations and installations and coordinate prior to installation.
- 3. Center grid layout in all rooms unless noted otherwise.
- All components mounted in or below a suspended acoustic ceiling shall be centered in the ceiling tile or in the 2x2 portion of tegular tiles. This shall include, but not be limited to, light fixtures, diffusers, speakers, and sprinkler heads.
- Prior to the installation of ceilings, allow for an above-ceiling inspection of components that will not be visible when the ceilings have been installed.
- Provide complete coverage of building w/ NFPA 13 type sprinkler system. Verify adequate system pressure and modify existing system to provide complete coverage (including porches and concealed attic spaces)

GRAPHIC LEGEND:

EMERGENCY EXIT SIGNAL

CEILING TYPES:

CI- 24x48 SUSPENDED ACQUETICAL TILE
SIMILATED AS 24X24 TILES
C25 5/6' GVB
G3- NOT SPECIFIED
C4- ONE HOUR RATED 6YP9UM BOARD
EXP-EXPOSED TO STRUCTURE ABOVE
OPEN TO ABOVE (SECOND
FLOOR)

24×24 FLUORESCENT

0 24×48 FLUORESCENT

12x48 SURFACE MTD FLUORESCENT ____

RECESSED CAN MALL SCONCE 19.72

CEILING TYPE C3 - %" PAINTED GWB

MECHANICAL SUPPLY OR RETURN

Hospital arine

05-108

DRWN. CHK

COPYRIGHT 2006 PDT Architects

闰

 \mathbf{Z}

A

 \mathbb{Z}

Д

Z

Y \dashv

H

 \approx

0

 α

 \mathbf{z}

Η Ö

Д

S'S

 \approx

 Ξ

Renovation


SCALE: 1/8"=1'-0"

ISSUE Bid Documents 24 April 2006

Lower Level

and First Floor Ceiling Plan

A2.1



Provide complete coverage of building m/ NFPA 13 type aprinkler system. Verify adequate system pressure and modify existing system to provide complete coverage (including porches and concealed attic spaces)

MECHANICAL SUPPLY OR RETURN

SHEET A2.2

Second and Third Floor

Ceiling Plan



DARTMOUTH STREET PORTLAND, ME 04101 207 775-1059 207 775-2694 FAX I



COPYRIGHT 2006 PDT Architects

Щ \mathbf{Z}

¥

ration \mathbb{X} Ω Renov Z V \Box H \approx Hospital 0 \mathbf{Z} \vdash 0 arine ൧് \mathbf{s} \mathbf{z} H \simeq \mathbb{X}

JOB NO 05-108


DRWN. CHK

SCALE: AS NOTED

Bid Documents 24 April 2006

ELEVATIONS

A4.1



L Q d

COPYRIGHT 2006 PDT Architects

ĮΤÌ \mathbf{Z} A \mathbb{Z} Ω \mathbf{z} ¥

Renovation \Box H \mathbb{R} Hospital 0 Q, \mathbf{Z} 0 Marine \mathbf{Z} \approx \mathbb{X}


JOB NO. 05-108

SCALE: AS NOTED

Bid Documents 24 April 2006

ELEVATIONS, BLDG. SECTIONS

SHEET



x

COPYRIGHT 2006 PDT Architects

闰 \mathbf{Z}

 \vdash

V

 \mathbb{Z}

Ω

Z

0

Д

 \mathbf{Z}

0

S \boldsymbol{Z}


H


 \approx


 \mathbb{Z}

PARTIAL ELEVATIONS

A4.3







ARCHITECTU INTERIOR DESIC PLANNIN

COPYRIGHT 200 PDT Architects

 \square

 \mathbf{Z}

¥ ration \mathbb{X} Ω enov \mathbf{Z} ¥ Г 2 \vdash \simeq Hospital 0 Ъ Z 0 Д arin Z \mathbf{Z}

JOB NO 05-108

DRWN. CHK EJR


SCALE: AS NOTED

ISSUE

Bid Document 24 April 2006

DOOR & WINDOW DETAILS

A6.3



ပ I O œ

L a d

COPYRIGHT 2006 PDT Architects Reuse or reproduction of the contents of this document is no permitted without written permission of PDT Architects.

ĮΪ \mathbf{Z}

 \vdash

A

 \mathbb{X}

Renovation Д \mathbf{Z} \forall \dashv H \approx Hospital 0 Д \mathbf{Z} 0 Marine ď Z S H \mathbb{R} \mathbb{X}

IOB NO. 05-108

DRWN. CHK

SCALE: AS NOTED


Bid Documents 24 April 2006

TITLE Enlarged Bathrrom P

SHEET

and Elevations

A7.1



--

COPYRIGHT 2006 PDT Architects

团 \mathbf{z} ¥ enovation \mathbb{Z}

 \mathbf{z} A \simeq Hospital 0 Ц Z 0 I arine S. S \aleph \mathbb{X}

JOB NO. 05-108

SCALE: AS NOTED

Bid Document 24 April 2006

Entry Ramp and Stair Drawings

SHEET

A7.2

- STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH JOB SPECIFICATIONS AND ARCHITECTURAL, MECHANICAL, ELECTRICAL, PLUMBING, AND SITE DRAWINGS. CONSULT THESE DRAWINGS FOR LOCATIONS AND DIMENSIONS OF OPENINGS, CHASES, INSERTS, RECLETS, SLEEVES, DEPRESSIONS, AND OTHER DETAILS NOT SHOWN ON STRUCTURAL DRAWINGS.
- ALL DIMENSIONS, EXISTING CONDITIONS, AND AS-BUILT CONDITIONS MUST BE VERIFIED IN THE FIELD. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE STRUCTURAL ENGINEER BEFORE PROCEEDING WITH THE AFFECTED PART OF THE WORK.
- THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE ONLY AFTER THE STRUCTURAL WORK CONTAINED IN THE S— DRAWINGS IS COMPLETED. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE ERECTION PROCEDURES AND SEQUENCE TO INSURE THE SAFETY OF THE BULDING AND ITS COMPONENTS DURING ERECTION. THIS INCLUDES THE ADDITION OF INCESSARY SHORING, SHEETING, TEMPORARY BRACING, OUTS OR TIEDDWINS, SUCH MATERIAL SHALL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER COMPLETION OF THE PROJECT.
- SECTIONS AND DETAILS SHOWN ON ANY STRUCTURAL DRAWINGS SMALL BE CONSIDERED TYPICAL FOR SIMILAR CONDITIONS AS DETERMINED BY THE STRUCTURAL ENGINEER. THE STRUCTURAL ENGINEER RESERVES THE RIGHT TO INTERPRET DETAILS TO ADDRESS OTHER PROJECT CONDITIONS.
- THE CONTRACTOR SHALL SUBMIT COMPLETE SHOP DRAWINGS FOR ALL PARTS OF THE WORK, INCLUDING DESCRIPTION OF SHORING, AND CONSTRUCTION METHODS AND SEQUENCING WHERE APPLICABLE. NO PERFORMANCE OF THE WORK INCLUDING, BUT NOT LIMITED TO, DEMOLITION OF DESTING STRUCTURE, OR FABRICATION OR ERECTION OF NEW STRUCTURAL ELEMENTS, SHALL COMMENCE WITHOUT REVIEW OF THE SHOP DRAWINGS BY THE ARCHITECT AND ENGINEER. SUBMIT ONE COPY AND ONE SEPA. COPY WILL BE REVIEWED AND SEPIA WILL BE RETURNED. FOR SHOP DRAWINGS AND SUBMITTALS REQUIRED, REFERENCE THE PROJECT SPECIFICATIONS.
- ALL APPLICABLE FEDERAL, STATE, AND MUNICIPAL REGULATIONS SHALL BE FOLLOWED, INCLUDING THE FEDERAL DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND HEALTH ACT.
- 8. IN ACCORDANCE WITH THE INTERNATIONAL BUILDING CODE (2003 EDITION, SECTION 1704.1), A STATEMENT OF SPECIAL INSPECTIONS IS REQUIRED AS A CONDITION FOR PERMIT ISSUANCE BY THE LOCAL CODE OFFICIAL. THIS STATEMENT SHALL INCLUDE A COMPLETE LIST OF MATERIALS AND WORK REQUIRING SPECIAL INSPECTIONS, THE INSPECTIONS TO BE PERFORMED AND A LIST OF THE HIDDROLLAS, APPROVED AGENCIES AND FIRMS INTENDED TO BE RETAINED FOR CONDUCTING SUCH INSPECTIONS.
- 9. REFERENCE THE PROJECT SPECIFICATIONS FOR ALL TESTING REQUIREMENTS.

DESIGN LOADS

- 1. BUILDING CODE: INTERNATIONAL BUILDING CODE, 2003 EDITION ASCE 7—02 MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES.
- 2. DESIGN FLOOR LIVE LOADS:

 LIVE LOADS ARE ASSUMED TO BE LESS THAN OR EQUAL TO HISTORIC USE. AREAS OUTSIDE OF CORRIDORS AND STAIRS ARE LIMITED TO <u>TO PSF</u> ALLOWABLE LIVE LOAD. POTENTIAL USES:

 OFFICES: 50 PSF + 20 PSF PARTITION ALLOWANCE PRIVATE ROOMS AND CORRIDORS SERVING THEM: 40 PSF LOBBIES AND FIRST FLOOR CORRIDORS: 100 PSF

 STAIRS: 100 PSF
- DESIGN ROOF SNOW LOAD:
 GROUND SNOW LOAD (Pg):
 SNOW EXPOSURE FACTOR (co):
 SNOW LOAD IMPORTANCE FACTOR (ct):
 1.0
 SNOW LOAD THERMAL FACTOR (ct):
 1.1
 FLAT ROOF SNOW LOAD (PF):
 46 PSF 46 PSF + DRIFT
- DESIGN WIND LOAD:
 BASIC WIND EASED:
 100 MPH
 WIND LOAD IMPORTANCE FACTOR (IW): 1.00
 WIND EXPOSURE:
 0 INTERNAL PRESSURE COEFFICIENT: ±0.18
 COMPONENTS & CLADDING LOADS PER ASCE 7-02
- 5. DESIGN SEISMIC LOADS:
 BUILDING SEISMIC STSTEM IS EXISTING BEARING WALL / ORDINARY PLAIN MASONRY
 SHEAR WALLS. CHANGE OF OCCUPANCY WILL NOT RESULT IN STRUCTURE BEING
 RECLASSIFIED TO A HIGHER SEISMIC USE GROUP. STRUCTURE IS NOT REQUIRED TO BE
 SEISMICALLY UPGRADED.

FOUNDATION NOTES (SOIL SUPPORTED)

- FOUNDATION DESIGN IS BASED ON SHALLOW SPREAD FOOTINGS BEARING ON SUTFABLE UNDISTURBED NATIVE SOILS AND/OR NEW COMPACTED STRUCTURAL FILL EXTENDING TO UNDISTURBED NATIVE SOIL.
- EXTEND BOTTOM OF EXTERIOR FOOTINGS AT LEAST 4.5 FEET BELOW THE FINAL EXTERIOR GRADE FOR PROTECTION AGAINST FROST.
- 5. ALL PAYEMENT, EXISTING FOUNDATIONS AND UNCONTROLLED GRANULAR FILL SHALL BE REMOVED FROM THE AREA OF THE PLANNED FOUNDATION TO AT LEAST 4 FEET BEYOND THE FOOTING LIMIT.
- COMPACTED STRUCTURAL FILL SHALL BE USED TO BACKFILL TO THE DESIGN FOOTING SUBGRADE AND BENEATH ALL SLABS ON GRADE. STRUCTURAL FILL SHALL BE A CLEAN SAND—GRAVEL MIXTURE MEETING THE THE FOLLOWING GRADATION:

	 ****	THE TOLLOW
REEN OR SIEVE SIZE	PET	RCENT PASSIN
6 INCH		100
3 INCH		90-100
1/4 INCH		25-90
NO. 40		0-30

- 7. STRUCTURAL FILL SHALL BE PLACED IN UNIFORM LIFTS NOT EXCEEDING B INCHES IN LOOSE THICKNESS AND SHALL BE COMPACTED TO 95 PERCENT OF MAXIMUM ORY DENSITY PER ASTM O-1557, MODIFIED PROCTOR TEST. COMPACT ADJACENT TO FOUNDATION WALLS SUPPORTING LIMBULANCED FILL (RETAINING WALLS) TO 94 TO 96 PERCENT OF MAXIMUM DRY DENSITY PER ASTM O-1557. HAND OFFERIED EQUIPMENT SHALL BE USED FOR COMPACTION WITHIN 8 FEET OF NEW FOUNDATION WALL
- B. NO BACKFILL SHALL BE PLACED AGAINST FOUNDATION WALLS RETAINING EARTH, UNLESS WALLS ARE ADEQUATELY BRACED TO PREVENT MOVEMENT OR STRUCTURAL DAMAGE.
- PROVIDE PVC DRAINPIPE AROUND THE PERIMETER OF THE STRUCTURE. LOCATE AT THE BOTTOM OF THE FOUNDATION WALLS AND PROVIDE POSITIVE GRANTLY FLOW TO PROPERLY DESIGNED OUTLET. REFER TO SITE DRAWINGS FOR ADDITIONAL INFORMATION.
- 10. SOUS EXPOSED AT THE BASE OF ALL SATISFACTORY FOUNDATION EXCAVATIONS SHALL BE PROTECTED AGAINST ANY DETRIMENTAL CHANGE IN CONDITION, SUCH AS DISTIRBANCE FROM RAIN OR FROST. SURFACE RUNOFF SHALL BE DRAINED AWAY FROM THE EXCAVATIONS AND NOT BE ALLOWED TO POND, FOUNDATION EXCAVATIONS SHALL BE ALGUATELY PROTECTED FROM RAINFALL OR FREEZING CONDITIONS, GROUNDMATER SHALL BE ANTICHATED FOR EXCAVATIONS AND APPROPRIATE DEWATERING MEASURES SHALL BE EMPLOYED.
- 11. SLOPE FOOTING EXCAVATIONS AS REQUIRED FOR STABILITY AND SAFETY IN ACCORDANCE WITH OSHA REQUIREMENTS. PROVIDE SHEETING OR SHORING IN ACCORDANCE WITH OSHA GUIDELINES, BRACED EXCAVATIONS SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF MAINE.

CONCRETE NOTES

- CONCRETE WORK SHALL CONFORM TO "ACI MANUAL OF CONCRETE PRACTICE", LATEST EDITION. THIS PUBLICATION IS AVAILABLE THROUGH THE AMERICAN CONCRETE INSTITUTE (248) 848—3800.
- 2. ALL CONCRETE SHALL HAVE A 28-DAY COMPRESSIVE STRENGTH OF 3,000 PSI, U.N.O. EXTERIOR SLAB-ON-GRADE SHALL HAVE A 28-DAY COMPRESSIVE STRENGTH OF 4,500 PSI. ADDITIONAL CONCRETE MIKE PERFORMANCE DATA INCLUDING AIR CONTENT, WATER-CEMENT RATIO, AIR CONTENT, AGGREGATE SIZE, SLUMP, ETC. HAS GEEN INCLUDED IN THE PROJECT SPECIFICATIONS. SEE THE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

 3. CONCRETE SHALL NOT BE PLACED IN WATER OR ON FROZEN GROUND.
- PROVIDE PVC SLEEVES WHERE PIPES PASS THROUGH EXTERIOR CONCRETE, OR SLABS.
- 5. REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60 DEFORMED BARS AND SHALL BE DETAILED, FABRICATED AND PLACED IN ACCORDANCE WITH ACI 315, LATEST EDITION.
- 6. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A-185 AND BE PROVIDED IN FLAT
- 7. FIBER REINFORCEMENT SHALL BE TYPE III SYNTHETIC VIRGIN HOMOPOLYMER POLYPROPYLENE FIBERS CONFORMING TO ASTM C1116.
- MINIMUM CONCRETE PROTECTIVE COVERING FOR REINFORCEMENT, UNLESS NOTED OTHERWISE, SHALL BE AS FOLLOWS:
 - A) SURFACES CAST AGAINST AND PERMANENTLY IN CONTACT WITH EARTH, 3.0°
 B) FORMED SURFACES IN CONTACT WITH EARTH OR EXPOSED TO WEATHER

 §S BARS, 5/8" DIAMETER WIRE, AND SMALLER, 1.5"

 §THROUGH §11 BARS, 2.0"
 C) SURFACES NOT IN CONTACT WITH EARTH OR EXPOSED TO WEATHER

 WALLS, SLABS, JOISTS §11 BARS AND SMALLER, 1.0"

 BEAMS, GIRDERS, AND COLUMNS; ALL REINFORCEMENT, 1.5"
- 9. REINFORCEMENT SHALL BE CONTINUOUS AROUND CORNERS AND AT INTERSECTIONS. PROVIDE LAPPED BARS AT NECESSARY SPLICES OR HOOKED BARS AT DISCONTINUOUS ENDS. PROVIDE TENSION LAP SPLICES PER THE SCHEDULE THIS DRAWING, FOR ALL REINFORCING UNLESS OTHERWISE SHOWN ON PLAN.
- 10. WELDING OF REINFORCEMENT IS NOT PERMITTED.
- 17 PIOLE DETAILS.

 12. CONSTRUCTION JOINTS SHOWN ON DRAWINGS ARE MANDATORY. OMISSIONS, ADDITIONS, OR CHANGES SHALL NOT BE MADE EXCEPT WITH THE SUBMITTAL OF A WRITTEN REQUEST TOCKETHER WITH LOCATIONS FOR APPROVAL OF THE STRUCTORY ELEMENTS FROM STRUCTION JOINTS ARE NOT SHOWN, OR WHEN ALTERNATE LOCATIONS FOR APPROVAL OF THE STRUCTURE LOCATIONS FOR APPROVAL OR SHOWN OF WHEN ALTERNATE LOCATIONS AND CONCRETE PLACING SEQUENCE SHALL BE SUBMITTED TO THE STRUCTURE INCONCRETE PLACING SEQUENCE SHALL BE SUBMITTED TO THE STRUCTURE INCONCRETE REVIEW PRIOR TO PREPARATION OF THE REINFORCEMENT SHOP DRAWINGS CONCRETE SHALL BE PLACED MITHOUT HORIZONIAL CONSTRUCTION JOINTS EXCEPT WHERE SHOWN OR NOTED. VERTICAL CONSTRUCTION JOINTS AND STOPS IN CONCRETE BEAMS/GRADE BEAMS SHALL BE MADE AT MIDSPAN OR AT POINTS OF MINIMUM SHEAR, UNLESS NOTED OTHERWISE.
- 13. SPACING OF CONSTRUCTION JOINTS, UNLESS NOTED OTHERWISE SHALL BE AS FOLLOWS:

 A) FOOTINGS AND WALLS
 A) FOOTINGS AND WALLS
 B) SLABS ON GRADE

 MAX LENGTH 40'-0" NOR 15'-0" FROM ANY CORNER®*
 SEE FOUNDATION PLAN

- ** EXCEED ONLY WHERE INTERMEDIATE CONTRACTION JOINTS ARE PROVIDED. MINIMUM OF 72 HOURS SHALL ELAPSE BETWEEN ADJACENT CONCRETE PLACEMENTS.
- 14. ANCHOR RODS SHALL BE HEADED RODS CONFORMING TO ASTM F1554, GRADE 36 KSI WELDABLE STEEL, UNLESS NOTED OTHERWISE ON DRAWINGS. ANCHOR RODS THAT ARE TO BE IN CONTACT WITH PRESSURE TREATED LUMBER SHALL BE HOT—DIPPED
- 15. ALL GROUT BENEATH BASE PLATES & BEARING PLATES SHALL BE "5-STAR" 5000-PSI NON-SHRINK GROUT BY U.S. GROUT CORP.
- 16. SLAB THICKNESSES INDICATED ON THE DRAWINGS ARE MINIMUMS. PROVIDE SUFFICIENT CONCRETE TO ACCOUNT FOR STRUCTURE DEFLECTION, SUBGRADE FLUCTATIONS, AND TO OBTAIN THE SPECIFIED SLAB ELEVATION AT THE FLATNESS AND LEVELNESS INDICATED.

REBAR	LAP SPLICE	TABLE	
BAR SIZE	LAP LENGTH		
	3,000 PS1	4,000 PS1	
# 3	30*	24"	
# 4	36"	32"	
# 5	48"	42"	

- STRUCTURAL STEEL FABRICATION, ERECTION, AND CONNECTION DESIGN SHALL CONFORM TO AISC "SPECIFICATION FOR THE DESIGN FABRICATION, AND ERECTION OF STRUCTURAL STEEL" 9TH EDITION, AND THE "CODE OF STANDARD PRACTICE, LATEST EDITION.
- STRUCTURAL STEEL: STEEL PLATES, SHAPES, AND BARS, CONFORM TO ASTM A36 UNLESS NOTED OTHERWISE (U.N.O.). STRUCTURAL STEEL SHAPES DESIGNATED ON THE DRAWNIOS FOR WIDE-FLANCE SECTIONS: ASTM A992 (ASTM A572 GRADE 50 WITH SPECIAL REQUIREMENTS PER AISC TECHNICAL BULLETIN \$3 DATED MARCH, 1997)
- J. STRUCTURAL TUBING: CONFORM TO ASTM A500 GRADE B46 KSI.
- 4. FIELD CONNECTIONS SHALL BE BOLTED USING ASTM A325N HIGH
- WHERE WELDING IS INDICATED, ALL WELDING SHALL CONFORM TO AWS D1.1— LATEST EDITION. ELECTRODES SHALL BE CONFORM TO AWS AS.1 ETOXX SERIES WITH PROPER ROD TO PRODUCE OPTIMUM WELD (LOW HYDROGEN).
- 6. SEE CONCRETE NOTES AND DRAWINGS FOR ANCHOR BOLT INFORMATION, TYP.
- PROVIDE ALL MISCELLANEOUS ANGLES, PLATES, ANCHORS, BOLTS, ETC., SHOWN ON ARCHITECTURAL DRAWNINGS FOR SUPPORT OF BLOCKING, PARAPETS, FINISHES, ETC. COORDINATE WITH MISCELLANEOUS METAL FABRICATOR TO ENSURE COMPLETE COVERAGE OF ALL ITEMS.


TIMBER, NOTES

- 1. ALL TIMBER FRAMING SHALL BE IN ACCORDANCE WITH THE AITC TIMBER CONSTRUCTION MAINLE LATEST EDITION, AND THE AF & PA NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION (NDS) 2001 EDITION.
- 2. INDIVIDUAL TIMBER FRAMING MEMBERS SHALL BE VISUALLY GRADED. MINIMUM GRADE NOT/NO2 SPRUCE-PINE-FIR KILN DRIED TO 19% MAXIMUM MOISTURE CONTENT UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
- 3. PRESSURE TREATED LUMBER SHALL BE USED FOR SILL MEMBERS, EXTERIOR EXPOSURE, OR WHERE SHOWN ON THE DRAWINGS. TIMBER SHALL BE SOUTHERN YELLOW PINE TREATED WITH CCA OR ACQ TO 0.4 #/CF IN ACCORDANCE WITH AWPA C-18. ACZA IS STRICTLY PROHIBITED.
- - A. ROOFS: 8d NAILS AT 6" AT PANEL EDGES AND 12" AT INTERMEDIATE SUPPORTS.


 B. WALLS: 8d NAILS AT 6" AT PANEL EDGES AND 12" AT INTERMEDIATE SUPPORTS.
- 5. ALL BUILT-UP BEAMS AND COLUMNS SHALL BE NAILED AS FOLLOWS (FASTENING IN EACH PLY):


UNIFORMLY LOADED BEAMS:
BEAM DEPTH <18" — 2 ROWS OF 18d NAILS AT 12" O.C., STAGGERED
BEAM DEPTH >=18" — 3 ROWS OF 18d NAILS AT 12" O.C., STAGGERED
NOTE: SIDE LOADED BEAMS REQUIRE ADDITIONAL FASTENING. SEE DETAILS.

- 6. FASTENING NOT SPECIFIED SHALL CONFORM WITH IBC TABLE 2304.9.1.
- 7. ALL TIMBER CONNECTION HARDWARE (JOIST HANGERS, POST BASES, SHEARWALL HOLDOWNS, ETC) SHALL BE AS INDICATED ON THE DRAWINGS AND MANUFACTURED BY SIMPSON STRONG-TIE. ALL CONNECTION HARDWARE SHALL BE HOT-DIPPED GALWANIZED G-90 (U.N.O.). PROVIDE VICOR ISOLATION BARRIERS PER SIMPSON TECHNICAL BULLETINS. CONNECTION HARDWARE USED IN CONJUNCTION HITH PRESERVATIVE TREATMENT SHALL BE GALWANIZED G18S (ZMAX.) USE FASTENERS & HANGERS OF SAME MATERIAL & COATING, REPER TO MANUFACTURER'S LITERATURE FOR PROPER HANDLING AND INSTALLATION GUIDELINES.
- 8. FASTENERS USED IN COMJUCTION WITH PT LUMBER, BUT NOT AT TIMBER CONNECTION HARDWARE REFERENCED IN NOTE 10, SHALL BE POST HOT DIPPED GALVANIZED (ASTM A153.)



TYP SLAB ON GRADE CONTRACTION JOINT DETAIL





TYP STEP FOOTING DETAIL t = FOOTING THICKNESS

16 207-8

COPYRIGHT 2006 Reuse or reproduction of t contents of this document is permitted without writte permission of PDT Archite

 \mathbf{Z}

Y

on \mathbb{X} ati Q enov \mathbf{z} spital 0 Ц 0 \mathbf{Z} 0 arine S \mathbf{Z} \vdash H \simeq \forall \mathbb{Z}

PAUL B. BECKER 6554 MALA

TOB NO 05-108 DRWN, CHK


APP

SCALE NOTED

24 April 2006

GENERAL NOTES

SHEET



COPYRIGHT 2006 PDT Architects

Щ \mathbf{z} \vdash on K M Д \mathbf{Z} \forall

Renovati 1 Hospital 0 Д \mathbf{Z} 0 Marine Д N, S \vdash H \simeq V \mathbb{X}


PAUL B. BECKER 6554 Middle

DSB

NOTED

BID DOCUMENTS 24 April 2006

EXIST FIRST & SECOND FLOOR FRAMING PLANS



COPYRIGHT 2006 PDT Architects

П

 \mathbf{Z}

A

Renovation \mathbb{Z} Д \mathbf{Z} Y Γ \approx Hospital 0 Д \mathbf{Z} 0 Marine Ъ S_{1} ΙI

M PAUL S B. BECKER 6554

 \approx

A

05-108

DRWN. CHK APP DSB


SCALE: NOTED

BID DOCUMENTS 24 April 2006

EXIST THIRD

FLOOR & ROOF FRAMING PLANS

S3



COPYRIGHT 2000 PDT Architects

[T] \mathbf{Z} A \mathbb{Z}

Hospital Renovation Q Z 0 Marine TIN'S PO \approx A

PAUL B. BECKER 6554


DRWN. CHK APP DSB

NOTED

BID DOCUMENTS 24 April 2006

CONCRETE SECTIONS & DETAILS

SHEET



COPYRIGHT 2006 PDT Architects Reuse or reproduction of the contents of this document is

permitted without written permission of PDT Architec


ΙŢ \mathbf{Z}

A \mathbb{Z} Renovati \Box \mathbf{z} A \simeq Hospital 0 Ы \mathbf{Z} 0 arine α S \mathbf{z} Z H \approx \forall \mathbb{Z}

B. BECKER 6554

BID DOCUMENTS 24 April 2006

S5



BECKERR Structural engineers, inc. 75 York Steet Perland, Perla

COPYRIGHT 2006 PDT Architects

DARTMOUTH STREET PORTLAND, ME 04101 207 775-1059 207 775-2694 FAX

 \mathbf{Z}

¥

Marine Hospital Renovation \approx V \mathbb{Z}

JOB NO. 05-108

DRWN. CHK APP DSB

SCALE: NOTED

BID DOCUMENTS 24 April 2006

TITLE FRAMING SECTIONS & DETAILS

SHEET

S6