
434-C-5
331 Veranda St.
Expansion
Martin's Pt.

PROJECT PARCEL SITE

PORTLAND TAX ASSESSOR'S MAP & LOT NUMBERS

SITE DEVELOPMENT PLANS MARTIN'S POINT REDEVELOPMENT PROJECT PHASE 2 PORTLAND, MAINE FINAL SITE PLAN SUBMISSION FEBRUARY 03, 2009



LOCATION MAP

INDEX

C-1.0 COVER SHEET

GENERAL NOTES & LEGEND C-2.0

EXISTING CONDITIONS & DEMOLITION PLAN

SITE LAYOUT PLAN - PHASE 2

SITE GRADING & DRAINAGE PLAN - PHASE 2

SITE LAYOUT PLAN- SELECT EXPANDED VIEWS

C-6.2 SITE GRADING PLAN - SELECT EXPANDED VIEWS

EROSION & SEDIMENT CONTROL PLAN

C-8.0 UTILITY PLAN

C-9.0 SITE DETAILS C-10.0 UTILITY DETAILS

C-11.0 WATER DETAILS

C-12.0 EROSION CONTROL DETAILS

C-13.0 EROSION & SEDIMENT CONTROL NARRATIVE

C-14.0 MISCELLANEOUS SITE DETAILS C-15.0 UTILITY PROFILE

C-15.1 ACCESS DRIVE PROFILES

LS-1.0 LANDSCAPE PLAN

1 S-2.0 LANDSCAPE DETAILS

LS-3.0 VEGETATION PRESERVATION AND CONSTRUCTION MANAGEMENT PLAN

LT-1.0 LIGHTING PLAN

BOUNDARY & TOPOGRAPHIC SURVEY BY OWEN HASKELL

UTILITIES

WATER
ATTN: DAVE COFFIN
PORTLAND WATER DISTRICT
P.O. BOX 3553
PORTLAND, MAINE 04104

SANITARY SEWER ATTN: FRANK BRANCEL ATTN: FRANK BRANCELE: CITY OF PORTLAND 55 PORTLAND STREET PORTLAND, MAINE 04101 (207) 874-8846

POWER
ATTN: PAUL DUPERRE
CENTRAL MAINE POWER COMPANY
162 CANCO ROAD PORTLAND, MAINE 04103 (207) 828-2882

PERMITS

LOCAL MAJOR SITE PLAN PERMIT

MAJOR SITE PLAN AMENDMENT

CITY OF PORTLAND - PLANNING BOARD

CITY OF PORTLAND

UNDER DELEGATED REVIEW BY THE

TRAFFIC MOVEMENT PERMIT CITY OF PORTLAND

STATE
MAINE GENERAL CONSTRUCTION PERMIT MeDEP SITE LOCATION OF DEVELOPMENT

MeDEP STORMWATER PERMIT MeDEP STORMWATER PERMIT MODIFICATION

MeDEP NRPA PERMIT-BY-RULE

STATUS APPROVED WITH CONDITIONS APRIL 25, 2006 (VALID THROUGH MAY 6,2009)

SUBMITTED FEBRUARY 3, 2009

SUBMITTED JUNE 9, 2006-

APPROVED WTIH CONDITIONS APRIL 25, 2006 (VALID THROUGH MAY 6, 2009)

APPROVED FEBRUARY 27, 2007

SUBMISSION SCHEDULED FOR FEB. 2009

SUBMITTED JUNE 9, 2006-

ZONING DISTRICT: R-P RESIDENTIAL-PROFESSIONAL

SPACE AND BULK REQUIREMENTS:

MINIMUM LOT SIZE: MINIMUM STREET FRONTAGE: [SETBACKS SHOWN ON SITE PLAN] MAXIMUM IMPERVIOUS SURFACE RATIO: MAXIMUM FLOOR AREA RATIO:

REQUIRED 6,000 SF 60 FEET

PREPARED BY

CIVIL ENGINEER: DeLuca-Hoffman Associates, Inc. 778 MAIN STREET, SUITE 8 SOUTH PORTLAND, MAINE 04106

ARCHITECT: SMRT 144 FORE STREET PORTLAND, MAINE 04101

SURVEYOR: Owen Haskell, Inc.

16 CASCO STREET PORTLAND, MAINE 04101-2979 207.774.0424

ENVIRONMENTAL ENGINEER: Hoffman Engineering, Inc. 640 TEN ROD ROAD NORTH KINGSTOWN, RHODE ISLAND 02852

NATURAL RESOURCES CONSULTANT: Normandeau Associates, Inc. 253 MAIN STREET YARMOUTH, MAINE 04096 207.846.3598

GEOTECHNICAL ENGINEER: S.W. Cole Engineering 286 PORTLAND ROAD 207.657.2866

TRAFFIC ENGINEER: Maine Traffic Resources 25 VINE STREET GARDINER, MAINE 04345 207 582 5252 TEL

OWNER: MARTIN'S POINT HEALTH CARE 331 VERANDA STREET PORTLAND, ME 04103

APPLICANT:
MARTIN'S POINT HEALTH CARE

PRELIMINARY NOT FOR CONSTRUCTION

10	08.07.08	PiARS	- CONSTRUCTION GRAWANGS
0.06.750	0.080/HTD	0.08292	
0.08.750	0.08165	0.08165	0.08165
0.08.750	0.08165	0.08165	0.08165
0.08.750	0.08165	0.08165	0.08165
0.08.750	0.08165	0.08165	0.08165
0.08.750	0.08165	0.08165	0.08165
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165		
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165	0.08165	
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.750	0.08165		
0.08.75			

MARTIN'S POINT REDEVELOPMENT PROJECT PHASE 2

COVER SHEET

MARTIN'S POINT HEALTH CARE

GENERAL NOTES

GENERAL NOTES:

OWNER:

MARTIN'S POINT HEALTH CARE 331 VERANDA STREET PORTLAND, ME 04103

- (REFER TO COVER SHEET)
- 3. THE PROJECT IS SITUATED ON TWO LOTS WHICH HAVE THE FOLLOWING TAX ASSESSOR AND ACREAGE INFORMATION:

PORTLAND TAX ASSESSOR MAP LOT NO.

APPROX. ACREAGE 4.6 7.0

- 434 C-005 434 C-001
- 1. THE PROJECT DOAWINGS PROVIDE ONLY A PORTION OF THE SITE WORK RECURRIENTS, CONSTRUCTION SHALL OCCUR ONLY USING PROJECT ON THE PROJECT SHALL BE COMPACTED TO 95 PERCENT OF THIS PROJECT SHALL BE COMPACTED TO 95 PERCENT OFTHER OF THE PROJECT SHALL BE COMPACTED TO 95 PERCENT OFTHER ON THE PROJECT SHALL BE COMPACTED TO 95 PERCENT OFTHER ON THE CONTRACT DRAWINGS.
- 6. THE CONTRACTOR SHALL REFER TO THE ARCHITECTURAL PLANS FOR EXACT LOCATIONS AND DIMENSIONS OF THE ENTRANCE, PAUNIC, EXIT PORCHES, PRECISE BUILDING DIMENSIONS, AND EXACT BUILDING UTILITY ENTRANCE POINTS.
- 7. ALL REQUIRED AND NECESSARY INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO ANNOUNCED BUILDING POSSESSION AND THE FINAL SERVICE CONNECTIONS.
- FINAL SERVICE COMPRECIONS.

 THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR THE ELEVATION OF THE EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE WARDON UTILITY COMPANIES AND WARDER POSSIBLE MEASUREMENTS TAKEN, HIM PERIOL THIS HOROMATION OF THE PROPERTY OF THE PROPERTY OF THE PROPERTY OF THE PROPERTY AND DIG CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AND DIG SAFE AT LEAST 72 HOURS PRIOR TO ANY EXCHANION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REDCAFE ALL DISTRICT UTILITY CONTRACTOR OF THE CONTR

THE UTILITIES INVOLVED WITH THIS PROJECT ARE LISTED BELOW:

UTILITY WATER

PORTLAND WATER DISTRICT ATIN: DAVE COFFIN P.O. BOX 3553 PORTLAND, MAINE 04104 (207) 774—5961

SANITARY SEWER

CITY OF PORTLAND ATIN: FRANK BRANCELEY 55 PORTLAND STREET PORTLAND, MAINE 04101 (207). 874—8846

POWER

CENTRAL MAINE POWER COMPANY ATN: PAUL DUPERRE 162 CANCO ROAD PORTLAND, MAINE 04103 (207) 828–2882

TELEPHONE

VERIZON
ATTN: SUE SURETTE
5 DAVIS FARM ROAD
PORTLAND, MAINE 04103
(207) 797-1842

1-888-344-7233

- 10. ALL MATERIAL SCHEDULES SHOWN ON THE PLANS ARE FOR GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL PREPARE HIS OWN MATERIAL SCHEDULES BASED UPON HIS PLAN REVIEW. ALL SCHEDULES SHALL BE VERRIED IN THE FIELD BY THE CONTRACTOR PRIOR TO GODERNIS MATERIALS OF BEFOREMISM WOMEN.

LANDSCAPE NOTES:

- 1. SEE DETAILED LANDSCAPE NOTES ON SHEET LS-2.0.
- ALL PLANT MATERIALS SHALL MEET THE STANDARDS AS SET FORTH
 BY THE AMERICAN ASSOCIATION OF NURSERYMEN. ALL TREES, SHRUB
 BEDS, ETC. ARE TO BE MULCHED WITH 3" OF SHREDDED HARDWOOD
 BARK MULCH.
- 4. ALL FLANTS INDICATED TO BE TRANSPLANTED SHALL BE MOVED PRIOR TO OTHER DEMOLITION OR CONSTRUCTION MODICATED FOR THE DE-STUDIAGE MALE THAN SHEET THES STATE OF THE DE-STUDIAGE MALE THAN SHEET THE STATE OF THE DESTRUCTION FROM DAMAGE, ALL TRANSPLANTED MATERIAL SHALL BE GUARANTEED FOR ON. 12AR.

GRADING & DRAINAGE NOTES:

ALL STORM DRAIN PIPE SHALL BE SDR-35 POLYWNYL CHLORIDE PIPE OR HDPE N-12 UNLESS EXPOSED TO SUNLIGHT, IN WHICH CASE HDPE N-12 SHALL BE USED.

EROSION CONTROL NOTES:

- SEE C-7.0 AND C-13.0 FOR FULL EROSION AND SEDIMENT CONTROL PLAN.
- LAND DISTURBING ACTIVITIES SHALL BE ACCOMPLISHED IN A MANNER AND SEQUENCE THAT CAUSES THE LEAST PRACTICAL DISTURBANCE OF THE SITE.
- ALL GROUND AREAS GRADED FOR CONSTRUCTION WILL BE GRADED, LOAMED AND SEEDED AS SOON AS POSSIBLE.
- PRIOR TO PAVING, THE CONTRACTOR SHALL FLUSH SILT FROM ALL STORM DRAIN LINES.
- SILT FENCES SHALL BE INSPECTED, REPAIRED AND CLEANED AS NECESSARY OR AS DIRECTED BY THE ENGINEER.
- THE CONTRACTOR SHALL REPAIR AND ADD STONE TO THE CONSTRUCTION ENTRANCE AS IT BECOMES SATURATED WITH MUD TO ENSURE THAT IT WORKS AS PLANNED DURING CONSTRUCTION.
- SILT REMOVED FROM AROUND INLETS AND BEHIND THE SILT FENCES
 SHALL BE PLACED ON A TOPSOIL STOCKPILE AND MIXED INTO IT
 FOR LATER USE IN LANDSCAPING OPERATIONS.
- THE CONTRACTOR IS CAUTIONED THAT FAILURE TO COMPLY WITH THE SCOURNES OF CONSTRUCTION, EROSON/SEDIMENT CONTROL PLAN, AND OTHER PERMIT REQUIREMENTS WAY RESULT IN MONETARY PENALTIES. THE CONTRACTOR SHALL BE ASSESSED ALL SUCH PENALTIES AT NO COST TO THE OWNER OF PERMITTED.

DEMOLITION NOTES:

- THE FOLLOWING ITEMS ARE TYPICAL OF THE MATERIALS WHICH WILL IS ENCOUNTERED DURNO STEE CLEARING/DEMOLITION. THE BIODERS IS ADVEST DY NST THE SITE OF CONFIRM DEMOLITION ITEMS SINCE THE LIST IS NOT ALL—INCLUSIVE OF THE SITE CONDITIONS WHICH MAY BE ENCOUNTED.
 - CONCRETE FOUNDATIONS/SLABS
 BITUMINOUS ASPHALT PAVEMENT
 - CONCRETE PADS AND BLOCKS
 - UNDERGROUND UTILITY LINES (ELECTRIC, WATER, SEWER)
- ALL EXCAVATION WORK SHALL BE SUBJECT TO THE CITY OF PORTLAND STREET OPENING ORDINANCE.
- 3. TREE REMOVAL SHALL BE PERFORMED IN ACCORDANCE WITH THE "VEGETATION PRESERVATION AND CONSTRUCTION MANAGEMENT PLAN" AND AS FURTHER DESCRIBED IN THE LANGSAPE NOTES AND TREES TO BE REMOVED ARE TO BE MARKED AND REVIEWED WITH OWNER PRIOR TO REMOVED.

LEGEND

EXISTING	DESCRIPTION	PROPOSED
	PROPERTY/ROW LINE	
	CONSTRUCTION CENTERLINE -	
	GRANITE BOLLARD	٥
•	IRON PIPE/ROD FOUND	
<u> </u>	SURVEY CONTROL POINT	
ORS	IRON ROD SET	
⊕ 6-1	APPROX. TEST BORING LOCATION BY S.W. COLE	₩ '
. ≜ . P-1	APPROX. TEST PROBE LOCATION BY S.W. COLE	⊕ 8-1
₩ [©] 112—1	HAND AUGER PROBES BY HEI 11/2005	
⊕на~1	TEST PITS BY HEI 12/2005	
-TW−1	TEST PITS BY TEWHEY ASSOC. 04/2005	
~~~	TREELINE	· ~ ~ ·
	TO THE PARTY OF TH	
$\odot$	DECIDUOUS TREE	
<b></b>	CONIFEROUS TREE	
	SIGN	· ·
	LIMIT OF WORK	and realized Printed Annual Printed
☆	LIGHT POST	
ø	UTILITY POLE	ě
Mate N	ELECTRIC METER	~
	GRADING CONTOUR LINE	100
×90.03	GRADING SPOT GRADE	107.70
× 90.03	SILT FENCE	
	CATCH BASIN SEDIMENT TRAP	
	CATCH DASIN SEDIMENT TRAP	
777777		
V////	BUILDING	
	CDCC OF DIVERSE	
	EDGE OF PAVEMENT -	
	PAVED ISLAND w/CURB	
	CURB	7777 C
	PAVEMENT STRIPING	
•	FIRE HYDRANT	*
⊕ EE CB	CATCH BASIN	■ CB1
OMH	MANHOLE	
₩ 🕅	WATER GATE/VALVE	' ₩
<del></del>	FENCE	
OHE	OVERHEAD WIRES	OHE
12"w	WATER LINE	2"W ———
10"SD	STORM DRAIN LINE	10°SD
12"SAH	SANITARY SEWER LINE	6°SAH
	UNDERGROUND ELECTRIC	UGE
ugt	UNDERGROUND TELEPHONE	UGT
	SIDEWALK	
-3	GUIDERAIL	<del>\0.0.0.</del>
	WALL	5

# PRELIMINARY NOT FOR CONSTRUCTION





MÄRTIN'S POINT REDEVELOPMENT PROJECT PHASE 2


GENERAL NOTES & LEGEND


MARTIN'S POINT HEALTH CARE


DH DeLUCA-HOFFMAN ASSOCIATES, INC. 778 MAIN STREET, SUITE 6 SOUTH PORTLAND, ME 04106 207,775.1121 WWW.DeLUCAHOFFMAN.COM















AREAS OF PROPOSED GRIND ARE TO BE GROUND FULL DEPTH, EXCE WHERE EXISTING ADJACENT PAYEMENT IS TO REMAIN AND BE MATCHES INTO, REFER TO DETAIL I' ON SHEET C-14.0. SOME AREAS OF GRIND MLL RECEIVE A FULL DEPTH PAYEMENT SECTION ASSOCIATED WITH UTILITY WORK IN THESE AREAS.





MART IN'S POINT REDEVELOPMENT PROJECT PHASE 2

SEETINE SITE LAYOUT PLAN - SELECT EXPANDED VIEWS


CLUBT


MART IN'S POINT REDEVELOPMENT PROJECT PHASE 2


SEETINE SITE LAYOUT PLAN - SELECT EXPANDED VIEWS


CUET CLUBT































































1 12.22.05 ISSUED TO CUENT FOR REVIEW
REV DATE DESCRIPTION

MARTINS POINT HEALTH CARE








NOTE: KEEP CONCRETE CLEAR OF PIPE JOINT, NUTS AND BOLTS


SPACER (LENSTH AS REQUIRED)


A FIRE HYDRANT INSTALLATION DETAIL

NTS.

SEE NOTE 3 IN THRUST BLOCK NOTES DETAIL










3'-0" WIN, 6" DIAMETER OR GREATER

SEE NOTE 3 IN THRUST BLOCK NOTES DETAIL

BACKFILL WITH EXCAVATED MATERIAL OR SELECT BACKFILL AS REQUIRED



11 02.03.09 FINAL SITE PLAN SUBMISSION TO CITY REV DATE DESCRIPTION

*E. DWIGHT D. ANDERSON
C. #927#

MARTINS POINT HEALTH CARE

Existing and Proposed Drainage Features
The site has steep topography sloping from Elevation 67 at the Marine Hospital building point to about elevation 30 at the lower parking area to the north. Drainage emanates from the site in all directions.

Limited existing formal drainage currently exists on the site.

The proposed drainage systems are not being designed to reduce peak discharge rates at or below existing levels. Instead, the flow will be conveyed in new storm drains to stable outfall points. The control of the peak runoff rates is discussed in more detail in the Stormwater Management Report

Critical Areas

This cal Idea areas of the site are the steep stopes along the edge of the project and where grading will be required within the 75-foot setback from the resource boundary.

Erosion/Sedimentation Control Devices
The Contractor as part of the site development will implement the following erosion and sediment control devices. These devices shall be installed as indicated on the plans or as described within this report. For further reference, see the Maine Erosion and Sediment Control Handbook for

1. Siltation fence shall be installed downslope of any disturbed areas to trap runoff borne sediments until the site is revegelated. The silt fence shall be installed per the detail provided in the plan set and inspected immediately after each rainfall and at least daily during prolonged rainfall. Repairs shall be made immediately by the Contractor if there are any signs of erosion or sedimentation below the fence line. Proper placement of stakes and keying the bottom of the fabric into the ground is critical to the fence's effectiveness. If there are signs of undercutting at the center or the edges, or impounding of large volumes of water behind the fence, the barrier shall be replaced with a stone check dam.

Silt fence is shown by three types depending upon the timing and Intent as follows:

SCHEDULE OF SILT FENCE REQUIREMENTS					
Silt Fence	Type Purpose	Time of Installation			
Type 1	To trap sediment along the grading edge where the new contours nearly parallel existing contours.	At initial site preparation, prior to other work.			
Туре 2	To trap sediment from the work area; install in short sections parallel to existing contour; typically occurs where proposed and existing contours form a "V" shape.	At initial site preparation, prior to other work or as fills are blended to existing grades along the contour.			
Гуре 3	To trap sediment along the base of proposed contours, typically in cut areas.	During construction after new grade is shaped. Time between work in area and shaping new grade to allow sit fence to be installed shall be minimized.			

- 2. Straw or hay mulch including hydroseeding is intended to provide cover for denuded or seeded areas until revegetation is established. Mulch placed on slopes of less than 10 percent shall be anchored by applying water, mulch placed on slopes steeper than 10 percent shall be covered with a fabric netting and anchored with staples in accordance with the manufacturer's recommendations. Proposed drainage channels, which are to be revegetated, shall receive Curlex blankets by American Excelsior or equal. Mulch application rates are provided in Attachment A of this section. Hay mulch shall be available on site at all times in order to provide immediate temporary stabilization when necessary. Where necessary for concentrated runoff to be conveyed down a slope, a temporary stone channel or pipe sluice shall be used to convey runoff down the slope.
- Water quality systems will be required to provide water quality enhancement and sedimentation control for stormwater runoff from the parking and drive areas after
- 4. Riprap slopes, ditch linings, stone check dams, hay bale barriers, and culvert outlet aprons are intended to reduce runoff velocities and protect denuded soil surfaces from concentrated flows. Installation details and stone sizes are provided in the construction plan set on the erosion control detail sheets.
- A construction entrance will be constructed at all access points onto the site to prevent tracking of soil onto Veranda Street.
- Stone sediment traps or a premanufactured SlitSack™ will be installed at catch basin inlets to prevent slit from entering the storm drain system. Installation details are provided in the plan set on the erosion control detail sheets.
- 7. Reinforced turf and mechanically stabilized turf slopes will be used on extremely steep slopes in areas designated on the drawings
- Dirtbags[™] will be required to be on site and available for construction dewatering. The Contractor will be required to provide four Dirtbags [™] with one prepared for operation prior to commencing any trenching operations.
- Loam and seed is intended to serve as the primary permanent revegetative measure for all
  denuded areas not provided with other erosion control measures, such as riprap. Specific
  areas as shown on the landscape plan will receive sool. Application rates are provided in
  Attachment A of this section for temporary and permanent seeding.
- 10. Sorbent oil bags will be required in catch basins which receive runoff from payed areas. The sorbent longs shall be places in the basin immediately prior to paving and remain in place for 60 days after paving operations are complete. After this time, the sorbent bags shall be removed and disposed of at an appropriate facility. The Contractor shall notify the Owner of the disposition location for the sorbent bags.
- 11. Water will be the principal means to control fugitive dust.

Temporary Erosion/Sedimentation Control Measures
The following are planned as temporary erosion/sedimentation control measures during

- A crushed stone-stabilized construction entrance shall be placed at any construction access points from Veranda Street.
- Type 1 and 2 siltation fence shall be installed along the downgradient side of the proposed improvement areas prior to work in these areas. Type 2 and 3 siltation fence shall be installed as work progresses. The siltation fence will remain in place and properly maintained until the site is acceptably revegetated.
- 3. Dirtbags™ shall be installed in accordance with the details in the plan set. The Dirtbags¹™ function on the project is to receive any water pumped from excavations during construction. A Dirtbag¹™ shall be installed any prepared for operation prior to any trenching on site. When Dirtbags™ are observed to be at 50% capacity, they shall be cleaned or replaced. Stone under the Dirtbag¹™ shall be removed and replaced concurrently.
- 4. Temporary stockpiles of stumps, grubbings, or common excavation will be protected as
- Temporary stockpiles shall not be located within 100 feet of the resource limits and at least 50 feet upgradient of the perimeter silt fence.
- Inactive stockpiles shall be stabilized within 5 days by either temporarily seeding the stockpile with a hydroseed method containing an emulsified mulch tackifier or by covering the stockpile with mulch. If necessary, mesh shall be installed to prevent wind from the mulch.
- All denuded areas, which have been rough graded, shall receive mulch or erosion control mesh fabric within 14 days of initial disturbance of soil.

- 6. All soils disturbed between November 1 and April 1 will be covered with mulch within 5 days of disturbance, prior to any predicted storm event of the equivalent of ½" of equivalent rainfall in a 24-hour period, or prior to any work shutdown lasting more than 35 hours (including weekends and holidays). The mulch rate shall be double the normal rate.
- 7. For work which is conducted between November 1 and April 15 of any calendar year, all denuded areas will be covered with hay mulch, applied at twice the normal application rate and (in areas over 10% grade) anchored with a fabric netting. The time period for applying mulch shall be limited to 5 days for all areas or immediately in advance of a predicted rainfall
- Offsite roadways shall be swept to control mud and dust as necessary. A street sweeper shall be available from the Contractor on immediate notice or request from the Owner, City or regulatory agency. A water truck shall be used to control dust both on the site and along points of ingress and egress.
- During grubbing operations stone check dams or hay bale barriers shall be installed at any evident concentrated flow discharge points.
- 10. Silt fencing with a maximum stake spacing of 6 feet should be used, unless the fence is supported by wire fence reinforcement of minimum 14 gauge and with a maximum mesh spacing of 6 inches, in which case stakes may be spaced a maximum of 10 feet apart. The bottom of the fence should be properly anchored a minimum of 6° per the plan detail and backfilled. Any silt fence identified by the owner or reviewing agencies, as not being properly installed during construction shall be immediately repaired in accordance with the installation details.
- 11. Storm drain catch basin inlet protection shall be provided through the use of stone sediment barriers or a premanufactured SiltSack™ as distributed by A. H. Harris Company, Portland, Maine. Stone sediment barrier installation details are provided in the plan set. The barriers or SiltSack™ whall be inspected after each rainfall and repairs made as necessary, including the removal of sediment. Sediment shall be removed and the barrier or SiltSack™ restored to its original dimensions when the sediment has accumulated to ½ the design depth of the barrier. Sediment shall be removed from SiltSacksTM as necessary. Inlet protection shall be removed when the tributary drainage area has been stabilized.
- 12. All slopes over 4:1 shall receive erosion control mesh.
- 13. Slopes steeper than 3:1 shall receive reinforced turf unless rip rap or other nonvegetative stabilization measures are required by the contract.
- 14. Type 2 and 3 silt fence shall be installed as construction progres
- 15. Areas of visible erosion shall be stabilized with crushed stone. The Owner's representative in consultation with the engineer shall determine the size of the stone.
- 16. Catch basins shall all be installed with an opening 2'-6" below finish grade to receive a 4" underdrain with an end cap. A 3"-0" stub of underdrain surrounded by 6" of 3/2" crushed stone and filter fabric shall be installed.
- 17. All catch basins which receive parking lot runoff shall have a sorbent bag installed as described in section 14.5 of this narrative.

- Standards for Stabilizing Sites for the Winter

  1. Standard for the timely stabilization of ditches and channels: The contractor shall construct and stabilize all stone-lined ditches and channels on the site by November 15. The contractor shall construct and stabilize all grass-lined ditches and channels on the site by September 15. If the contractor fails to stabilize a ditch or channel to be grass-lined by September 15, then the contractor shall take one of the following actions to stabilize the ditch for late fall and winter.
- Install a sod lining in the ditch. The contractor shall line the ditch with properly installed sod by October 1. Proper installation includes the applicant pinning the sod onto the soil with wire pins, rolling the sod to guarantee contact between the sod and underlying soil, watering the sod to promote root growth into the disturbed soil, and anchoring the sod with jute or plastic mesh to prevent the sod strips from sloughing during flow conditions.
- Install a stone lining in the ditch. The contractor shall line the ditch with stone riprap by November 15. The contractor shall hire a registered professional engineer to determine the stone size and lining thickness needed to withstand the anticipated flow velocities and flow depths within the ditch. If necessary, the contractor shall regrade the ditch prior to placing the stone lining so as to prevent the stone lining from reducing the ditch's cross-sectional area.
- Standard for the timely stabilization of disturbed slopes; The contractor shall construct and stabilize stone-covered slopes by November 15. The contractor shall seed and mulch all slopes to be vegetated by September 15. The department will consider any area having a grade greater than 15% (10H: 1V) to be a slope. If the contractor falls to stabilize any slope to be vegetated by September 15, then the contractor shall take one of the following actions to stabilize the slope for late fall and winter.
  - Stabilize the soil with temporary vegetation and erosion control mesh. By October 1 the contractor shall seed the disturbed slope with winter rye at a seeding rate of 3 pounds per 1000 square feet and apply erosion control mats over the mulched slope. The contractor shall monitor growth of the rye over the next 45 days. If the rye fails to grow at least three inches or fails to cover at least 75% of the disturbed slope by November 15, then the contractor shall cover the slope with a layer of woodwaste compost as described in item iii of this standard or with stone rip rap as described in item iv of this standard.
- ii. Stabilize the slope with sod. The contractor shall stabilize the disturbed slope with properly installed sod by October 1. Proper installation includes the contractor pinning the sod onto the slope with wire pins, rolling the sod to guarantee contract between the sod and underlying soil, and watering the sod to promote root growth into the disturbed soil. The contractor shall not use late-season sod installation to stabilize slopes having a grade greater than 33% (3H: 1V) or having groundwater seeps on the slope face.
- iii. Stabilize the slope with woodwaste compost. The contractor shall place a six-inch layer of woodwaste compost on the slope by November 15. Prior to placing the woodwaste compost, the contractor shall remove any snow accumulation on the disturbed slope. The contractor shall not use woodwaste compost to stabilize slopes having grades greater than 50% (2H: 1V) or having groundwater seeps on the slope face.
- iv. Stabilize the slope with stone rip rap. The contractor shall place a layer of stone riprap on the slope by November 15. The contractor shall hire a registered professional engineer to determine the stone size needed for stability and to design a filter layer for underneath the riprap.
- Standard for the timely stabilization of disturbed soil: By September 15, the contractor shall seed and mulch all disturbed soils on areas having a slope less than 15%. If the contractor fails to stabilize these soils by this date, then the contractor shall take one of the following actions to stabilize the soil for late fail and winter.
  - Stabilize the soil with temporary vegetation. By October 1, the contractor shall seed the disturbed soil with winter rye at a seeding rate of 3 pounds per 1000 square feet, lightly mulch the seeded soil with hay or straw at 75 pounds per 1000 square feet, and anchor the mulch with plastic netting. The contractor shall monitor the growth of the rye over the 45 days. If the rye fails to grow at least three inches or fails to cover at least 75% of the disturbed soil before November 15, then the contractor shall mulch the area for
- ii. Stabilize the soil with sod. The contractor shall stabilize the disturbed soil with properly installed sod by October 1. Proper installation includes the contractor pinning the sod onto the soil with wire pins, rolling the sod to guarantee contact between the sod and underlying soil, and watering the sod to promote root growth into the disturbed soil.

iii. Stabilize the soil with mulch. By November 15, the contractor shall mulch the disturbed soil by spreading hay or straw at a rate of at least 150 pounds per 1000 square feet on the area so that no soil is visible through the mulch. Prior to applying the mulch, the contractor shall remove any snow accumulation on the disturbed area. Immediately after applying the mulch, the contractor shall anchor the mulch with plastic netting to prevent wind from moving the mulch off the disturbed soil.

Sedimentation Sumps
The use of shallow sediment sumps on the downgradient side of erodible stockpiles and areas where denuded conditions will be prolonged is encouraged. The sediment sumps may be installed and used in conjunction with the underdrain inlets at catch basins.

<u>Permanent Erosion Control Measures</u>
The following permanent erosion control measures have been designed as part of the Erosion/Sedimentation Control Plan:

- 1. All storm drain pipes which are not connected to a formal inlet or outlet shall have riprap aprons at their outlet to protect the outlet and receiving channel from scour and deterioration. Installation details are provided in the plan set. The aprons shall be installed and stabilized prior to directing runoff to the tributary pipe or culvert. It is noted that all inlets and outlets over 18° in diameter are to have a flared concrete inlet and an aluminum bar rack. Pipes less than 18 inches in diameter are to have an HDPE flare. Riprap shall not be extended above
- 2 All areas disturbed during construction, but not subject to other restoration (paving, riprag All areas disturbed during construction, but not subject to other restoration (paying, riprap, tect.) will be loamed, limed, fertilized, mulched, and seeded. Fabric netting, anchored with staples, shall be placed over the mulch in areas where the finish grade slope is greater than 10 percent except in the areas with over 3:1 slopes where reinforced turf is required. Native topsoil shall be stockpiled and temporarily stabilized with seed and mulch and reused for final restoration when it is of sufficient quality. Where necessary, compost shall be added and interest the greater than the property of the soil. plended to increase the organic content of the soil.
- Catch basins shall be provided with sediment sumps for all outlet pipes that are 12" in diameter or greater.
- 4. Permanent water quality measures will be installed.

# Timing and Sequence of Erosion/Sedimentation Control Measures The following construction sequence shall be required to insure the effectiveness of the erosion and sedimentation control measures are optimized. These measures are separate from the separate requirements to be employed during the building demolition phase of the project.

Note: For all grading activities, the Contractor shall exercise extreme caution not to overexpose the site by limiting the disturbed area.

- Install crushed stone-stabilized construction entrances from Veranda Street the as shown on the Erosion and Sedimentation Control Drawing.
- 2. Install Type 1 and appropriate Type 2 siltation.
- Establish and prepare Dirtbag ™ area.
- 4. Perform demolition activities and major site cuts and fills and blasting.
- 5. Install water quality systems and the storm drain system
- 6. Construct diversion and drainage channels to direct flow to new storm drain and inlets where grades permit.
- 7. Install stone and hay bate check dams at any concentrated flow discharge points
- Install storm drain, underground electric, foundations and other utility work. Install inlet and outlet protection immediately after the installation of any inlets. Pump any accumulated water to the Dirbag.⁹⁸
- 10. Bring initial site work area to subgrade including binder pavement, stabilization of all slopes,
- 11. Construct other site improvements and utilities.
- 12. Raise catch basins to grade and install inlet protection devices.
- 13. Install sorbent bags in catch basins which will receive runoff from pavement.
- Install final payement as detailed on the site plans.
- 15. Loam, lime, fertilize, seed and mulch all remaining disturbed and denuded areas
- 16. Remove all accumulated sediment from silt barriers.
- 17. Review stability of the site. If a 75% catch of grass is achieved, remove all other temporary Soil will be considered disturbed if it does not have an established stand of vegetation cor at least 75% of the soil surface or has not been mulched with hay applied at a rate of 230

It is anticipated that site work may be suspended prior to winter. If so, the General Contractor shall schedule a meeting with the City, Owner, and Owner's representatives to review the site for conformance with the plan. This meeting shall be scheduled at least 10 days prior to winter shutdown. The Owner may elect to provide the Contractor with a punch list for measures to be complete before the interim shutdown. The Owner's punch list shall not obviate the Contractor's responsibility for compliance with the erosion control requirements of the project or permits.

Construction of Improvements at Veranda Street may be conducted concurrently or following site

Contracting Procedure
A General Contractor under contract to Martin's Point will construct the project. The Contractor shall submit a schedule for the completion of the work which will satisfy the following criteria:

- The above construction sequence should generally be completed in the specified order; however, several separate items may be constructed simultaneously. Work must also be scheduled or phased to prevent the extent of the exposed areas as specified below. The intent of this sequence is to provide for erosion control and to have structural measures su as silt fence and construction entrances in place before large areas of land are denuded.
- 2. The work shall be conducted in sections which will:
- Limit the amount of exposed area to those areas in which work is expected to be undertaken during the proceeding 30 days.
- b. Revegetate disturbed areas as rapidly as possible. All areas shall be permanently stabilized within 7 days of final grading or before a predicted storm event; or temporarily stabilized within 7 days of initial disturbance of soil for areas identified as critical (refer to paragraph 14.4.A) and 14 days for all other areas.

- Incorporate planned inlets and drainage system as early as possible into the construction
  phase. The ditches shall be immediately lined or revegetated as soon as their installation
  is complete.
- Once final grade has been established, the Contractor may choose to dormant seed the disturbed areas prior to placement of mulch and placement of fabric netting anchored with

All areas seeded during the winter months will be inspected in the spring for adequate catch. All areas insufficiently vegetated (less than 75 percent catch) shall be revegetated by replacing loam, seed and mulch.

- b. If dormant seeding is not used for the site, all disturbed areas shall be revegetated in the
- 4. The area of denuded non-stabilized construction shall be limited to the minimum area practicable. An area shall be considered to be denuded until the subbase gravel is installed in parking areas or the areas of future loam and seed have been loamed, seeded, and mulched. The mulch rate shall be twice the rate specified in the seeding plan. [For example,
- 5. Within the exposed work area, temporary sedimentation sumps shall be provided at the interface between parking areas and graded slopes (refer to paragraph 14.7). This shall be accomplished by creating an area 18° below adjacent temporary grades. The sedimentation area shall have a bottom width of 3° and 3:1 side slopes. Culverts to allow access shall be installed by the Contractor. Along the sedimentation sumps, barriers shall be provided at sufficient intervals to permit runoff to be accumulated to a minimum depth of 12" before overflowing.
- 6. The schedule shall be subject to the approval of the Owner.

The Contractor must install any added measures, which may be necessary to control erosion/sedimentation from the site and fugitive dust emissions dependent upon the actual site and weather conditions.

The applicant may be required to retain a third party inspector. The Contractor shall cooperate with the third party inspector and permit access to the site by the inspector at all times.

The Contractor shall note that no area within 50 feet of a slope with a vertical drop of more than 3' in 50 feet shall remain denuded for a period of over 5 days before it is temporarily stabilized. Temporary stabilization shall be the installation of mulching. All other areas shall be stabilized within 14 days. For construction between November 1 and April 15 of any calendar year, all areas shall be temporarily stabilized at the earlier time frames specified above.

Provisions for Maintenance of the Erosion/Sedimentation Control Features
The Owner will contract the project. The project is subject to the requirement of a MeDEP Site Location of Development Permit administered through the City of Portland and a MeDEP Permit for Stormwater Pollution Prevention Plan during Construction. These permits require the Contractor to prepare a list and designate by name, address and telephone number all individuals who will be responsible for implementation, inspection and maintenance of all erosion control measures identified within this section and as contained in the Erosion and Sedimentation Control Plan of the contract drawings. Specific responsibilities of the inspector(s) will include:

- Execution of the Contractor/Subcontractor Certification contained in Attachment B by any and all parties responsible for erosion control measures on the site as required by the MeDEP.
- Assuring and certifying the Owner's construction sequence is in conformance with the specified schedule of this section. A weekly certification stating compliance, any deviations, and corrective measures necessary to comply with the ensoinn control requirements of this section shall be prepared and signed by the inspector(s).
- In addition to the weekly certifications, the inspector(s) shall maintain written reports recording construction activities on site which include:
- Dates when major grading activities occur in a particular areas
- Dates when major construction activities cease in a particular area, either temporarily or
- Dates when an area is stabilized.
- 4. Inspection of this project work site on a weekly basis and after each significant rainfall event (0.5 inches or more within any consecutive 24 hour period) during construction until permanent erosion control measures have been properly installed and the site has been stabilized. Inspection of the project work site shall include:
- entification of proper erosion control measure installation in accordance with the erosion control detail sheet or as specified in this section
- Determine whether each erosion control measure is properly operating. If not, identify damage to the control device and determine remedial measures.
- Identify areas that appear vulnerable to erosion and determine additional erosion control
  measures that should be used to improve conditions.
- Inspect areas of recent seeding to determine percent catch of grass. A minimum catch of 75 percent is required prior to removal of erosion control measures.


 Record date of installation of sorbent bags in catch basins, the dates of paving, the date
of removal, and the disposal method and location. computated sitt/sediment should be removed when the depth of sediment reaches 50 percent of the barrier height. Accumulated sill/sediment should be removed from behind silt fencing when the depth of the sediment reaches 6 inches.

If inspection of the site indicates a change should be made to the erosion control plan, either to improve effectiveness or correct a site-specific deficiency, the inspector shall immediately implement the corrective measure and notify the owner of the change.

Once construction has been completed, long term maintenance of the detention pond and catch basins will be the responsibility of the applicant. The catch basin sumps shall be inspected in April and October of each year. Sediment shall be removed when the depth of sediment reaches

All certifications, inspection forms and written reports prepared by the inspector(s) shall be filed with the Owner, and the MeDEP General Construction Permit File contained on the project site. All written certifications, inspection forms, and written reports must be filed within one (1) week of the inspection of the

Preconstruction Conference
Prior to any construction at the site, representatives of the Contractor, and the site design
engineer shall arrange for and meet with the Owner to discuss the scheduling of the site
construction. On or before that meeting, the Contractor will prepare a detailed schedule and a
marked-up site plan indicating areas and components of the work and key dates showing date of
disturbance and completion of the work. Three copies of the schedule and marked-up site plan





MARTIN'S POINT REDEVELOPMENT PROJECT PHASE 2 EROSION AND SEDIMENT CONTROL NARRATIVE


DELUCA-HOFFMAN ASSOCIATES, INC. 778 MAIN STREET, SUITE 8
SOUTH PORTLAND, ME 04101
207.775.1121
WWW.DELUCAHOFFMAN.COM


MARTINS POINT HEALTH CARE


PRELIMINARY NOT FOR CONSTRUCTION





























### LANDSCAPE NOTES

- IN ARIES OF NEW CONSTRUCTION OR RENAMING WORK, EXISTING PLANT IMPERIAL AND EXISTING GRASS NOT INDICATED TO REMAIN SHAL BE RELEVICED, MEARS NIGGLETED TO BE SEEDED SHALL BE LOANED IN ACCORDANCE WITH APPLICABLE DETAILS AND RESERDED. DUSTRIC TREES TO BE PRESERVED SHALL BE PROTICTED DURING CONSTRUCTION AND SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.

- ALL PLANTS SHALL HAVE THEIR LOCATIONS STAKED AND APPROVED BY THE LANDSCAPE ARCHITECT OR OWNER PRIOR TO PLANT INSTALLATION. ALL PLANTS SHALL BE ORIENTED FOR BEST APPEARANCE.

- PRIOR TO SEEDING, APPLY FERTILIZER AND LIME IN ACCORDANCE WITH SOIL TEST RECOMMENDATIONS.
   SEED MIX A LAWAYS: 35% KENTUCKY BLUEGRASS, 35% CREEPING RED FESCUE, 25% CHEWING FESCUE.

		BOTANICAL NAME				
KEY	QTY T	COMMON NAME REES	SIZE	ROOT	SPACING	REMARKS
В	7	Abies balsamea Balsam Fir	6-7' ht.	B&8		
P	4T	Acer platanoides Norway Maple	1 1/2" cal.			transplanted on site
R	6	Acer rubrum 'Red Sunset' Red Sunset Red Maple	2 1/2-3" cal.	B&B		5' ct. min. in pkg. islands
R	6T	Acer rubrum 'Red Sunset' Red Sunset Red Maple	3" cal.	B&B		transplanted on site
s	5	Acer saccharum 'Green Mountain' Green Mountain Sugar Maple	2-2 1/2" cal.	B&B	-	
3P	7	Betula papyrifera 'Whitespire' Japanese Whitespire Birch	8-10' ht.	B&B		multi-trunked
3P	5T	Betula papyrifera 'Whitespire' Japanese Whitespire Birch	1 1/2" cal. clump	8&8		transplanted on site
cc	15	Crataegus crus-galli inermis Thomless Cockspur Hawthorn	2-2 1/2" cal.	8&8		4-5' ct. min.
CK	6	Cornus kousa Kousa Dogwood	6-7" ht.	B&B		multi-trunked
WS	5	Magnolia soulangeana Saucer Magnolia	5-6' ht.	8&B		
PA	4	Picea abies Norway Spruce	6-7' ht.	B&B		
PN	8	Pinus nigra Austrian Pine	6-7' ht.	8&8		
PS	6	Pinus strobus White Pine	6-7' ht.	B&B		
QA	12	Quercus alba White Oak	2 1/2-3" cal.	B&B		
SH	5	Carya ovata Shagbark Hickory	2-2 1/2" cal.	B&B		
ST	1	Cotinus coggygria Smokebush	1 1/2-2" cal.	B&B		
тс	17	Tsuga canadensis Canadian Hemlock	6-7' ht.			pest-free; Maine source
то	9	Thuja occidentalis 'Techny' Mission Arborvitae	5-6' ht.	B&B	6' o.c.	
UA	1	Ulmus americana 'Valley Forge' Valley Forge American Elm	3 1/2-4" cal.	B&B		specimen
AM	5	SHRUBS & ORNAMENTAL GRASSES  Aronia melanocarpa	24-30" ht.	cont./B&B	5' o.c.	1
cs	14	Red Chokeberry Cornus sericea	24-30" ht.	cont./B&B	5' o.c.	
FG	3	Red Osier Dogwood  Mscanthus 'Purpurascens'	full	3 gal.	5' o.c.	
HY	1	Flame Grass Hydrangea arborescens 'Grandiflora'	24-30" ht.	cont/B&B		
MP	5	Hills of Snow Hydrangea Myrica pensylvanica	2-3' ht.	8&8	<del> </del>	
RH	2	Northern Bayberry  Rhododendron 'Boule de Neige'	24-30" ht.	B&B	6' o.c.	white flower
RHP	-	Boule de Neige Rhododendron Rhododendron 'PJM'	24-30" ht.	B&B	6' o.c.	magenta flower
RR	59	PJM Rhododendron Rosa rugosa	18-24" ht.	cont.	4' o.c.	mageria ilores
SP	3	Rugosa Rose Spiraea x bumalda 'Anthony Waterer'	24-30" spr.	B&B	5' o.c.	ļ
SRA	-	Anthony Waterer Spirea  Syringa x prestoniae 'James MacFarlane'	4-5' ht.	B&B	2' o.c.	hedge
SRB		James MacFarlane Ulac  Syringa meyeri 'Palibin'	24-30" ht.	B&B	2 0.0.	- leage
SS	14	Dwarf Korean Lilac Clethra ainifolia	24-30" spr.	cont/B&E	5' o.c.	
TM	17	Summersweet Taxus cuspidata 'Green Wave'	18-24" ht.	B&B	4' o.c.	
vc	8	Green Wave Yew Vibumum cassinoides	24-30" ht.	cont./B&E		
VM	13	Witherod Viburnum  Viburnum x burkwoodii 'Mohawk'	24-30" ht.	cont./B&E	in hedge	<b>.</b>
		Mohawk Viburnum GROUND COVER & PERENNIALS	24-00 III.	Lonisbac	1 4 0.0.	
DM	29	Dryopteris marginalis Marginal Wood Fern	full	1 gal.	3' o.c.	
HE	170	Hemerocallis 'Stella D' Oro' & 'Ruby Stella'	3-4 ppp full	1 gal.	2' o.c.	
JH	25	Daylity, mixed red & yellow Juniperus horizontalis 'Bar Harbor'	15-18" spr.	2 gal.	5' o.c.	
		Bar Harbor Juniper MISCELLANEOUS				
		Shredded Bark Mulch	3" depth			Incl. tree & shru water rings
		Seed Mix A	1			Lawn seed mix
		Seed Mix B				Low maint. seed mix
		Seed Mix C				Erosion control Upland seed m
		Seed Mix D				Shade tolerant seed mix

			UNDSCAPE
8	02.03.09	FINAL SITE PLAN SUBMISSION TO CITY	SHELLEY
7	01.09.09	DESIGN DEVELOPMENT SUBMISSION	III STEEL TO
6	06,09,06	SUBMITTED TO MEDEP	ILE BRUNELLE S
5	05.26.06	SITE PLANS REVISED PER CONDITIONS OF CITY APPROVAL	Wo 2583 / /
4	04.11.06	FINAL SITE PLAN SUBMISSION TO CITY	1 VI Suighman Att
3	04.03.06	SECOND SUBMISSION TO PHPB	V Marie John Jan J
2	02.28.06	SECOND SKETCH PLAN SUBNISSION TO CITY	AND THE OF WHITE
1	02,27.05	SUBMISSION TO PHPB	
REV	DATE	DESCRIPTION	P.E. SHELLEY E. BRUNELLE, RLA

DeLUCA-HOFFMAN ASSOCIATES, INC. 778 MAIN STREET, SUITE B SOUTH PORTLAND, ME 04108 397-775-1191 WWW.DELUCAHOFFMAN. MARTIN'S POINT REDEVELOPMENT PROJECT PHASE 2 
 SEB
 DATE:
 JAN. 2009

 SEB
 SCALE:
 NTS

 SEB
 JOB NO.
 2344.06
 MARTIN'S POINT HEALTH CARE

