


- BRING TO SUBGRADE AS REQUIRED W/ GRANULAR BORROW COMPACTED TO 90% OF MAXIMUM DENSITY.

- COMPACT GRAVEL SUBBASE, BASE COURSE TO 92% OF MAXIMUM DENSITY USING HEAVY ROLLER COMPACTION.
- 2. CONTRACTOR SHALL SET GRADE STAKES MARKING SUBBASE AND FINISH GRADE ELEVATIONS FOR CONSTRUCTION
- 3. ACCESSIBLE PARKING SPACES AND ACCESS AISLES CANNOT EXCEED A SLOPE OF 1:50 IN ANY DIRECTION.

PAVED PARKING LOT/ DRIVEWAY SECTION


NOT TO SCALE



SIDEWALKS ON ACCESSIBLE ROUTES CANNOT EXCEED A SLOPE OF 1:20 IN DIRECTION OF TRAVEL NOR 1:50 CROSS SLOPE.


BITUMINOUS SIDEWALK

NOT TO SCALE




- 1. PROVIDE CONTRACTION CONTROL JOINTS EVERY 6' IN EACH DIRECTION.
- SIDEWALKS ON ACCESSIBLE ROUTES CANNOT EXCEED A SLOPE OF 1:20 IN DIRECTION OF TRAVEL NOR 1:50 CROSS SLOPE.

6" CONCRETE PAVING NOT TO SCALE





- 1. PROVIDE SHOP DRAWINGS INCLUDING MATERIALS, FABRICATION DETAILS, LAYOUT AND FINISH OF HANDRAILS FOR ENGINEERS APPROVAL.
- 2. ENDS OF HANDRAIL SHALL BE EITHER ROUNDED OR RETURNED SMOOTHLY TO GROUND.
- 3. ALL HAND RAILS SHALL MEET APPLICABLE ADA STANDARDS.
- 4. ALL LANDINGS SHALL HAVE A MAXIMUM CROSS SLOPE OF 2%. ALL RAMP SLOPES SHALL NOT EXCEED 1:12.
- 5. SET RAIL TO BUTT AGAINST EACH EDGE OF SIDEWALK BOTH SIDES OF RAMP.

RAMP HANDRAIL DETAIL
NOT TO SCALE



HANDICAP SIGNS/SYMBOLS NOT TO SCALE





WTC					WTC			
			-22-17 100% CONSTRUCTION DOCUMENTS	-11-17 90% MAINE HOUSING SUBMISSION	-30-17 50% MAINE HOUSING SUBMISSION	MTC 09-28-16 ISSUED FOR REVIEW	DATE: STATUS:	THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS. INC.
				09-11-17	03-30-17	09-28-16	DATE:	SHALL NOT BE OR OTHERWIS
			WTC 11	WTC 09	WTC 03-	WTC	REV: BY:	PLAN HORIZED
			Ω	ပ	മ	⋖	REV:	THIS



COMMUNIT DETAILS THFIELD AVENUE AND, MAINE

PROJECT NO. SCALE 16173 AS SHOWN