

ESTIMATE

Evan Michelle Fitts



Estimate # 000268
Date 01/14/2018

LNE CONSTRUCTION

6 Collinsbrook Rd
Brunswick, Me 04011

Phone: 844-0784
Email: rollinsluke80@gmail.com

Description	Total
Drywall and finish kitchen walls and ceilings and dining room ceiling Install new drywall on all walls in kitchen and ceiling in preparation for new kitchen upgrade Install new drywall on ceiling in dining room to create a smooth finish	\$1,100.00
Frame,drywall and finish double door opening Frame in old double door opening install Sheetrock and finish with mud	\$300.00
Frame new opening and install existing double doors Enlarge existing 3-0 door opening in original exterior walls to except double doors. Including install of triple 11-1/4 LVL header	\$450.00
Frame Sheetrock and finish new 4' archway from kitchen to living Frame arch way with double 11-1/4 LVL header to carry existing load	\$375.00
Raise existing arch to match new arch	\$225.00
Wall paper removal and skimcoat walls prep for paint Complete approximately 1/2 the removal and prep of wallpaper customer to remove and prep other half	\$500.00
Subtotal	\$2,950.00
Total	\$2,950.00

Lucas Rollins

Evan Michelle Fitts