Quote

Agility#:

Quote#: 660255

Boise Cascade Building Materials Distribution
Boise Structural Solutions

20 Pomerleau St.
Biddeford, Me 04005

Tel: 877-291-5276
Fax: 877-782-0999

Customer: MEPO01 - RUFUS DEERING LMC 0342

383 COMMERCIAL STREET
PORTLAND, ME04104

Contact: JOHN LABRIE
Email: JLABRIE@RUFUSDEERING.COM
Phone: **Fax:**

Job Name: NAPOLITANO

PORTLAND, ME

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/07/14

Prepared By:	Date Quoted:	Delivery Date:	Last Revised:	Price Protected Until:
CHIPPER EXT 2751	07/01/2014			**07/08/2014**

ROOF TRUSSES **Designed per: IBC2009/TPI2007 Code.**

PROFILE	LBL	QTY / PLY	OVRALL LGTH / WEIGHT	NET SPAN	PITCH TOP	PITCH BOT	TYPE	SPC	OVERHANG LEFT	OVERHANG RIGHT	CUT	LOADING TLL-TDL-BLL-BDL / Heel Height Left	Heel Height Right	CANTILEVER LEFT	CANTILEVER RIGHT	BRG SIZE LEFT	BRG SIZE RIGHT		
A660255-0001	001	12	24-00-00	24-00-00	6.00	0.00	FINK	24	01-00-00	01-00-00	P	46.2-10-0-10 Grnd Snow=60		00-00-00	00-00-00	00-05-08	00-05-08		
		1	96 lbs									01-00-00	01-00-00			**BRG#:**	2		
A660255-0002	002	2	24-00-00	24-00-00	6.00	0.00	GESI	24	01-00-00	01-00-00	P	46.2-10-0-10 Grnd Snow=60		00-00-00	00-00-00	24-00-00	00-00-00		
		1	97 lbs									01-00-00	01-00-00			**BRG#:**	1		

Total Weight: 1346 lbs

Report Date/Time: 7/1/2014 3:13:00 PM

Agility#: Quote#: 660255

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/07/14

Boise Cascade Building Materials Distribution
Boise Structural Solutions

20 Pomerleau St.
Biddeford, Me 04005

Tel: 877-291-5276
Fax: 877-782-0999

Customer: MEPO01 - RUFUS DEERING LMC 0342

383 COMMERCIAL STREET
PORTLAND, ME04104

Contact: JOHN LABRIE
Email: JLABRIE@RUFUSDEERING.COM
Phone: **Fax:**

Job Name: NAPOLITANO

PORTLAND, ME

Prepared By:	Date Quoted:	Delivery Date:	Last Revised:	Price Protected Until:
CHIPPER EXT 2751	07/01/2014			07/08/2014

Quote Source: VERBAL

Job Notes To Customer:

Plan Date:

Special Instructions For Design:

12" Heels

SUB-TOTAL:	
DISCOUNTS:	
GRAND TOTAL:	

****** QUANTITY CHANGES WILL EFFECT PRICES* MAXIMUM UNLOADING TIME IS 1 HOUR***
TRUSS SYMBOLS CONCEPTUAL ONLY NOT FOR DESIGN
****** ALL TRUSSES ARE CUSTOM BUILT AND CANNOT BE RETURNED**
UNLESS SPECIFICALLY NOTED ON THIS QUOTE PRICE DOES NOT INCLUDE:
TREATED LUMBER, SEALED LAYOUTS, BRACING AND / OR HANDLING DRAWINGS
METAL HARDWARE, ENGINEERED LUMBER (LVL,I-JOISTS, ETC.)

BSS WILL BE CLOSED FOR BUSINESS ON FRIDAY JULY FOURTH IN HONOR OF INDEPENDENCE DAY!