



- NOTES:
1. PROVIDE LADUR TIE HORIZ REINF @ 16" O.C., U.N.O.
  2. PROVIDE BOND BEAMS W/2#5 CONT AT MID HEIGHT AND TOP OF ALL WALLS.
  3. ALL REINFORCED CELLS ARE TO BE FULLY GROUTED.
  4. LAP BARS AT SPICES MIN. 48 BAR DIAMETERS.
  5. PROVIDE 2#5 MIN ABOVE & BELOW ALL OPENINGS. EXTEND 24" MIN BEYOND EDGE OF OPENING EA SIDE.
  6. ALL CMU WALL REINF SHALL BE REVIEWED BY THE STRUCTURAL ENGINEER OR THEIR DESIGNATED REPRESENTATIVE PRIOR TO GROUTING.