

**E3 Addressable Fire Alarm System
Casco Bay Ferry Terminal
Portland, Maine**

[Click Here to Return to
Bill of Material/Index](#)

System Narrative

In the event of an alarm from an actuated device, the following shall

occur: (Devices reporting an alarm: Manual Station, Smoke, or Waterflow)

- 1) Notify Central Station monitoring company via the Digital Communicator (DACT)
- 2) Sound a Code 3 Temporal on all Horn Circuits
- 3) Flash all strobe appliance circuits in a synchronized manner
- 4) Annunciate audibly, visually, and in plain English the active initiating device at the fire alarm control panel and remote Annunciator

In the event of a supervisory condition from an actuated device, the following shall occur:

(Devices reporting a supervisory: Sprinkler Tamper Switch, Duct Smoke Detector)

- 1) Notify the Central Station monitoring company via the Digital Communicator (DACT)
- 2) Annunciate audibly, visually, and in plain English the active initiating device at the fire command center and remote Annunciator

In the event of a system trouble report, the following shall occur:

- 1) Notify the Central Station monitoring company via the Digital Communicator (DACT)
- 2) Annunciate audibly, visually, and in plain English the active initiating device at the fire command center and remote Annunciator