

SEQUENCE OF OPERATION MATRIX

	<div style="display: flex; justify-content: space-between;"> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">Alarm Signal to Central Station via DACT</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">Annunciate at Fire Alarm Control Panel</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">Activate Evacuation Sequence</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">Activate Associated Air Handler Functions</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">Supervisory Signal to Central Station via MODCOM</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">Trouble Signal to Central Station via MODCOM</div> </div>						
System Inputs	A	B	C	D	E	F	System Inputs
Manual Pull Stations	x	x	x				Manual Pull Stations
Area Smoke Detector	x	x	x	x			Area Smoke Detector
Waterflow Device	x	x	x	x			Waterflow Device
Duct Smoke Detector		x		x	x		Duct Smoke Detector
Sprinkler Tamper		x			x		Sprinkler Tamper
Fire Alarm - AC Failure		x				x	Fire Alarm - AC Failure
Fire Alarm - Low Battery		x				x	Fire Alarm - Low Battery
Signal Line Open Circuit		x				x	Signal Line Open Circuit
Signal Line Ground Fault		x				x	Signal Line Ground Fault
Horn/Strobe Circuit Open		x				x	Horn/Strobe Circuit Open
Horn/Strobe Circuit Ground		x				x	Horn/Strobe Circuit Ground
System Ground Fault		x				x	System Ground Fault
	A	B	C	D	E	F	