



TRAILER

SPECIFICATIONS

Length	46' 3"	14.10 m
Width	8' 2"	2.49 m
Height	13' 2"	4.01 m
Storage Space	31' 7" x 5' 8" x 7' 8"	9.64 x 1.75 x 2.35 m
Storage Compartment	10" x 13" x 3' 7"	0.25 x 0.33 x 1.10 m
Storage Capacity	10000 lb	4536 kg
Weight	29400 lb	13335 kg

STAGE FLOOR

Length and Depth	32' x 24'	9.75 x 7.32 m
Length and Depth with Extension Platforms	56' x 32'	17.07 x 9.75 m
Height from Ground	3' 6" to 5' 3"	1.07 to 1.60 m
Design Live Load	100 lb/ft ²	490 kg/m ²
Type of Surface	Plywood on steel	

ROOF

Length and Depth	34' 5" x 27' 7"	10.50 x 8.41 m
Clearance (Inclined roof)	20' to 17' 9"	6.10 m to 5.42 m
Maximum Height with Banner	30' 9"	9.36 m
Type of Surface	Fibreglass bonded on steel	
Lifting Capacity †	12000 lb	5443 kg
Load Bearing Capacity †	18500 lb	8391 kg
6 Rigging Points	1000 lb each	454 kg each
4 Rigging Bars	30 lb/lin. ft	45 kg/lin. m
4 Trusses - Central Roof (2), Downstage & Upstage	2000 lb each or 30 lb/lin. ft	907 kg each or 45 kg/lin. m
2 Front Overhang Extensions - 4' 9" (1.4 m)	750 lb each at 42"	340 kg each at 1.08 m
2 Front Overhang Extensions - 8' (2.4 m)	350 lb each at 42"	159 kg each at 1.08 m
2 Lateral Overhang Rigging Beams	2500 lb each at 6' 4"	1134 kg each at 1.93 m

PRACTICAL ASPECTS

Installation Time once Levelling Complete	1.5 Hour - Less without windwalls
Personnel Required	1 Certified technician and 1 stagehand
Site Preparation	None
Heavy Machinery Required	None
Mode of Transportation	1 Fifth-wheel tractor
Gust Wind Resistance	60 mph (97 km/h) with windwall or 90 mph (145 km/h) without windwall
Promotional Visibility *	Rolling billboard or multiple banner options
Windwalls *	Weatherproof - fire retardant vinyl or scrim (blow-through material)
Vertical and Horizontal Banner Supports *	Quick to install - Offers close to 714 sqft. (66 m ²) of promotional space
Floor Extension Platforms *	Integrated brackets - easy to install
Line Array Rigging Beams *	Reversible, slides down and crosses over overhang rigging beams

Values indicated are nominal. Due to STAGELINE'S product improvement policy, technical specifications may change without notice.

† Please refer to rigging plan.

* Offered in option.



Fax: 450 589-1711

info@stageline.com

450 589-1063

1-800-267-8243 in N.A.

www.stageline.com