

City of Portland, Maine - Building or Use Permit

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

Permit No: 2013-00838	Date Applied For: 04/26/2013	CBL: 444 A003001
---------------------------------	--	----------------------------

Location of Construction: 6 COMMERCIAL ST	Owner Name: CITY OF PORTLAND	Owner Address: 389 CONGRESS ST	Phone:
Business Name:	Contractor Name: Dan Bolduc	Contractor Address: 147 Fore St Portland	Phone (207) 420-0413
Lessee/Buyer's Name Our Tickets, Tours and Events	Phone: 2074200413	Permit Type: Tents	

Proposed Use: Same: City of Portland Ocean Gateway Ship Terminal	Proposed Project Description: Erect 120' x 60' tent, set up Friday, June 21, 2013 and breakdown Saturday, June 22, 2013.for 2013 Hotwing Challenge
--	--

Dept: Zoning **Status:** Approved **Reviewer:** Marge Schmuckal **Approval Date:** 05/09/2013
Note: **Ok to Issue:**

Dept: Building **Status:** Approved w/Conditions **Reviewer:** Tammy Munson **Approval Date:** 05/17/2013
Note: **Ok to Issue:**

1) This permit DOES NOT authorize any construction activities. The tent/stage must be removed at the end of the event.

Dept: Fire **Status:** Approved w/Conditions **Reviewer:** Chris Pirone **Approval Date:** 05/17/2013
Note: spoke with Dan Bolduc he is aware of the NFPA requirements and the conditions of approval. **Ok to Issue:**

- 1) The cooking equipment arrangement and type shall be evaluated at the inspection.
- 2) The fire department shall inspect the premise prior to the event.
- 3) Fire extinguishers will be required per NFPA 10.
- 4) A minimum 1 radio equipped firefighter shall be hired.
- 5) A minimum of __ trained crowd managers shall be provided and on duty inside of the occupied tents during the event.
- 6) EXITs
 - a.The main entrance shall have minimum clear width of 10 feet.
 - B.The divider in the main tent shall maintain an exit opening of 6 feet.
 - C.A main corridor for the main tent shall be maintained a minimum of 50 inches. Where a chair is placed between a table and the corridor the measurement shall be made from the table and add 19 inches for each chair (ie. Chair at both sides 38" + 50"= 88").
 - D.An exit from the main tent to the outside directly across from the main entrance shall be provided. Minimum clear width shall be 6 feet.
 - E.The auction tent shall have 2 exits perpendicular from the main tent. Minimum clear width shall be 36".
 - F.The catering tent shall have one additional exit across from the main tent. Minimum clear width shall be 36".
- 7) Emergency lighting and approved illuminated EXIT signs are required for events held outside of day light hours. A back up generator with transfer switch shall meet this requirement if the following is met:
 - a.All lighting is powered from the generator circuit.
 - B.The lighting illuminates the face of the EXIT signs.
 - C.An auto transfer and start shall be provided or dedicated staff shall be provided for that purpose.
- 8) All tents shall meet the flame propagation performance criteria contained in NFPA 701. A certificate or other evidence of acceptance by an organization acceptable to the AHJ shall serve as evidence that the tent fabric materials have the required flame propagation performance.
- 9) Cooking within the tents has not been reviewed and approved.
- 10 Fuel-fired heating equipment and propane tanks shall be installed outside of the tents and not with 5 feet of the tents or an exit discharge.
- 11 If the sides of the tents are to be enclosed at least two remotely located and marked exits shall be provided.

Location of Construction: 6 COMMERCIAL ST	Owner Name: CITY OF PORTLAND	Owner Address: 389 CONGRESS ST	Phone:
Business Name:	Contractor Name: Dan Bolduc	Contractor Address: 147 Fore St Portland	Phone (207) 420-0413
Lessee/Buyer's Name Our Tickets, Tours and Events	Phone: 2074200413	Permit Type: Tents	

12 Tents shall have an approved fire resistant rating and maintain 10' between stake lines. No smoking or open flame allowed within 10'. Provide at least one 2A:10 BC fire extinguisher.