FINISH SCHEDULE

ROOM No.	ROOM NAME	FLOORING	BASE	WALLS				CEILING	REMARKS
				NORTH	SOUTH	EAST	WEST		
		1 CERAMIC TILE - CT-1 2 VNTL TILE 3 EXPOSED CONCRETE W/ SEALER 4 CARPET 5 COMPOSITE DECK 6 -- 7 --	8 VNTL WALL BASE - LIGHT GREY 9 CERAMIC BASE - CB-1 10 WOOD BASE 11 --	12 CERAMIC TILE - CT-1 OVER GREEN BOARD 13 GYPSUM BOARD 14 METAL PANEL 15 STUCCO 16 PAINT 17 EXPOSED BLOCK 18 PLASTER ON STRUCT. STEEL LATH (P91) 19 SIDING 20 CURTAIN WALL 21 -- 22 -- 23 -- 24 -- 25 --	27 CERAMIC TILE - CT-1 OVER GREEN BOARD 28 GYPSUM BOARD 29 METAL PANEL 30 STUCCO 31 PAINT 32 EXPOSED BLOCK 33 PLASTER ON STRUCT. STEEL LATH (P91) 34 SIDING 35 CURTAIN WALL 36 -- 37 -- 38 -- 39 -- 40 --	42 CERAMIC TILE - CT-1 OVER GREEN BOARD 43 GYPSUM BOARD 44 METAL PANEL 45 STUCCO 46 PAINT 47 EXPOSED BLOCK 48 PLASTER ON STRUCT. STEEL LATH (P91) 49 SIDING 50 CURTAIN WALL 51 -- 53 -- 54 -- 55 --	57 CERAMIC TILE - CT-1 OVER GREEN BOARD 58 GYPSUM BOARD 59 METAL PANEL 60 STUCCO 61 PAINT 62 EXPOSED BLOCK 63 PLASTER ON STRUCT. STEEL LATH (P91) 64 SIDING 65 CURTAIN WALL 66 -- 67 -- 69 -- 70 -- 71 --	72 EXPOSED CONCRETE 73 2' X 2' SUSPENDED ACOUSTICAL CEILING - WHITE AT.1 74 METAL STRUCTURE EXPOSED 75 GYPSUM BOARD 76 PAINT 77 PLASTER ON STRUCT. STEEL LATH 78 SUSPEND LINEAR METAL CEILING WITH INSULATION 79 GLUE-LAM BEAMS HEIGHT	
	FIRST FLOOR								
100	PASSENGER QUEUING	3	10	13	28	43	58	72	VAR.	
101	C.B.P. PRIMARY	3	10	13	28	43	58	72	VAR.	
102	PASSAGE	3	10	13	28	43	58	72	VAR.	
103	C.B.P. SECONDARY	3	10	13	28	43	58	72	VAR.	
104	UNISEX TOILET-1	1	9	12	27	42	57	75	9'-0"	SOFFIT @ 8'-0"
105	OFFICE-1	2	8	13	28	43	63	LF	9'-0"	
106	ADIT/LAB	2	8	13	28	43	63	LF	9'-0"	
107	DETENTION	2	8	18	33	48	58	75	9'-0"	
108	DETENTION	2	8	18	33	48	58	73	9'-0"	
109	UNISEX TOILET-2	1	9	12	27	42	57	73	9'-0"	SOFFIT @ 8'-0"
110	INT/SEARCH	2	8	13	28	43	58	73	9'-0"	
111	LAN	2	8	13	28	43	58	73	9'-0"	
112	BAG STORAGE	2	8	13	28	43	58	73	9'-0"	
113	GEN. STORAGE	2	8	13	28	43	58	73	9'-0"	
114	CORRIDOR	2	8	13	28	43	58	73	9'-0"	
115	SAN. EJECT. PUMP ROOM	3		13	28	43	58	74	VAR.	UNDER STAIRS
116	ELEVATOR MACH. ROOM	3		13	32	43	58	75	9'-0"	
117	SPRINKLER SERVICE ROOM	3		13	32	43	58	75	9'-0"	
118	STAIR No. 1	3		13	28	43	58	75	--	
119	CASHIER	2	8	13	28	43	58	73	75	9'-0"	
120	C.B.P. STORAGE	3		17	32	47	62		VAR.	UNDER STAIRS
121	EXTERIOR PASSENGER QUEUING	3		17				76	12'-0"	
122	OPEN COVERED PASSAGE No. 1	3				47		76	12'-0"	
123	OPEN COVERED PASSAGE No. 2	3		19			62	76	12'-0"	
124	STAIR No. 2	3		17	32	48	63	75	--	
	SECOND FLOOR								
200	TERRACE	5		19			58	65		OPEN
201	LOUNGE	4	10	17	28	50	58	73	10'-6"	
202	OFFICES	4	8	13	28	43	58	73	9'-0"	
203	MEN'S RESTROOM	1	9	13	28	43	58	73	9'-0"	
204	WOMEN'S RESTROOM	1	9	13	28	43	58	73	9'-0"	
205	WAITING AREA	4	10	13	34	50	58	73	VAR.	
206	BOILER ROOM	3		13	28	43	58	75	9'-0"	
207	ELECTRICAL ROOM	3		13	32	43	62	75	9'-0"	
208	STAIR No.1	3		13	28	43	58	75	--	
209	LOBBY	4	10	13	28	43	58	73	10'-6"	
210	J.C/ STORAGE	3		13	28	43	58	73	9'-0"	
211	PASSAGE	3				49		72	12'-0"	
212	ELEVATOR			17	32	47	58		--	
213	CORRIDOR ELEVATOR	4	10	13	28	43	58	75	10'-6"	
214	LOBBY	4	10	13	28		58	73	10'-6"	
215	CORRIDOR WOMEN'S	1	10	13	28	43	58	73	9'-0"	
216	CORRIDOR MEN'S	1	10	13	28	43	58	73	9'-0"	
217	LADDER	3		13	28	43	58	79	--	
218	STAIR No.2	3		17	32	47	62	75	--	
	THIRD FLOOR								
300	MECHANICAL ROOM	3		15 17	28	47	58		VAR.	
301	EXTERIOR CHILLER DECK	3			30	45	60	73	OPEN	

IN ASSOCIATION WITH:
GORRILL-PALMER CONSULTING ENGINEERS
PERATROVICH, NOTTINGHAM, & DRAGE
WINTON SCOTT ARCHITECTS
HALEY & ALDRICH

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION

PROJECT NUMBER 009215.00

PIN
009215.00

LICENSED ARCHITECT
BRUNO E. RAMOS
NO. 2644
STATE OF MAINE

PROJ. MANAGER	PAUL POTTLE	BY	DATE
DESIGN-DETAILED			
CHECKED-REVIEWED			
DESIGN2-DETAILED2			
DESIGN3-DETAILED3			
REVISIONS 1	-	-	-
REVISIONS 2	-	-	-
REVISIONS 3	-	-	-
REVISIONS 4	-	-	-
FIELD CHANGES	-	-	-

SIGNATURE

P. LICENCE NUMBER
ARC 2644

DATE
10/8/2004

CITY OF PORTLAND
OCEAN GATEWAY PHASE 1

FINISH SCHEDULE

A608-T

Filename: \\Server1\projects\02-0818 Maine Int Ferry Terminal\PHASE 1\Architecture\FINAL CONSTRUCTION DOCUMENTS\TERMINAL BUILDING\20343802-T-A608.dwg, Oct 07, 2004 - 6:02pm