## SECTION 02370 - EROSION AND SEDIMENTATION CONTROL

All work and materials shall conform to the Drawings, the MDOT Erosion Control Best Management Practices and the provisions of MDOT SECTION 620 – GEOTEXTILES and SECTION 656 – TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL with the following modifications and additions:

## MODIFICATIONS:

<u>Section 620.01 Description</u>: Add the following: Location and usage of geotextiles as required for erosion control and slope stabilization or as directed by RESIDENT.

Section 656.4.5 Additional Measures/Amendment of SEWPCP: Add the following:

A. <u>Deficiencies</u> in erosion control measures indicated by failures or erosion shall be immediately corrected by CONTRACTOR providing additional measures or different techniques to correct the situation and prevent subsequent erosion.

<u>Section 656.5.2 If No Pay Item</u>: Add the following: The costs associated with preparing, submitting and implementing a Temporary Soil Erosion and Water Pollution Control Plan, including all associated materials, shall be incidental to the Contract.

\*\*\* END OF SECTION \*\*\*