

SECTION 02770 – CURBS

All work and materials shall conform to MDOT SECTION 609 – CURB with the following modifications and additions:

MODIFICATIONS:

Section 609.03 Vertical Stone Curb, Terminal Section and Transition Sections and Portland Cement Concrete Curb, Terminal Sections and Transition Section

- a. Installation - Add the following: Installation of the granite curb to conform to Drawings and in compliance with the manufacturers recommended installation procedures.

Section 712.04 (as referenced in Section 609.02) Stone Curbing and Edging - Add the following: The curb should conform to the standards of American Society for Testing and Materials (ASTM): C 615-03, Granite Dimension Stone.

Section 712.04a Vertical Curb: Replace the fourth paragraph with the following:
Drill holes through the curb are not allowed.

ADDITIONS:

Submittals: The CONTRACTOR shall submit to the RESIDENT:

- A. Certificates: Manufacturer's certification that products meet specification requirements.

END OF SECTION