

SECTION 03600 – GROUTS

All work and materials shall conform to the Drawings and the provisions of MDOT SECTION 535.25 – KEYWAY GROUT with the following modifications:

*MODIFICATIONS:*

Section 535.25 - Delete the first paragraph and replace with the following: Longitudinal keyways between beams shall be filled with Master Builder's Set 45 or Euclid's Eucospeed MP, no alternates will be considered. The grout shall be mixed, placed and cured in accordance with the manufacturer's published recommendations. Keyways shall be prepared as recommended by the grout supplier prior to placing grout. Provide grout submittals and keyway preparation procedure, to the Resident, two weeks prior to placing grout. Gaskets of compressible material are required around duct openings within keyways to prevent blocking of the duct with grout.

\*\*\* END OF SECTION \*\*\*