

City of Portland, Maine - Building or Use Permit Application
 389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

PERMIT ISSUED

Permit No:	05-0444	Issue Date:	11-11-2005	CB#:	013 K028001
------------	---------	-------------	------------	------	-------------

Location of Construction:	117 Sheridan St	Owner Name:	Fort Summer Lic	Owner Address:	12 Simonton St	Phone:	
Business Name:		Contractor Name:	Pine State Plumbing & Heating	Contractor Address:	CITY OF PORTLAND PO Box 6308 Scarborough	Phone:	2073212261
Lessee/Buyer's Name		Phone:		Permit Type:	HVAC	Zone:	R1b

Past Use:	Condo	Proposed Use:	Condo install a Luna Wall hung boiler	Permit Fee:	\$399.00	Cost of Work:	\$41,600.00	CEO District:	1
Proposed Project Description:	Install a Luna Boiler wall hung			FIRE DEPT:	<input type="checkbox"/> Approved <input type="checkbox"/> Denied	INSPECTION:	Use Group: R2	Type:	HMM

Signature:	<i>Use Case</i>	Signature:	<i>DMB 12/14/05</i>
PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.)			
Action:	<input type="checkbox"/> Approved	<input type="checkbox"/> Approved w/Conditions	<input type="checkbox"/> Denied
Signature:		Date:	

Permit Taken By:	dmartin	Date Applied For:	04/21/2005	Zoning Approval			
------------------	---------	-------------------	------------	------------------------	--	--	--

1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal Rules.	<input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan	<input type="checkbox"/> Variance <input type="checkbox"/> Miscellaneous <input type="checkbox"/> Conditional Use <input type="checkbox"/> Interpretation <input type="checkbox"/> Approved <input type="checkbox"/> Denied	<input checked="" type="checkbox"/> Not in District or Landmark <input type="checkbox"/> Does Not Require Review <input type="checkbox"/> Requires Review <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/Conditions <input type="checkbox"/> Denied
2. Building permits do not include plumbing, septic or electrical work.			
3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..			

Special Zone or Reviews	Zoning Appeal	Historic Preservation
Date: <i>DMB 12/14/05</i>	Date:	Date: <i>DMB</i>

CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provision of the code(s) applicable to such permit.

SIGNATURE OF APPLICANT	ADDRESS	DATE	PHONE
------------------------	---------	------	-------

RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE	DATE	PHONE
---	------	-------



FILL IN AND SIGN WITH INK

APPLICATION FOR PERMIT HEATING OR POWER EQUIPMENT

13 14 028

PERMIT ISSUED
JAN - 3 2006

To the INSPECTOR OF BUILDINGS, PORTLAND, ME.

The undersigned hereby applies for a permit to install the following heating, cooking or power equipment in accordance with the Laws of Maine, the Building Code of the City of Portland, and the following specifications:

Location / CBL ID SHERIDAN ST. Use of Building CANDY'S Date 4-14-05

Name and address of owner of appliance EGRET SUMMER LLC

12 SIMONSON ST SO. PORTLAND ME 04106

Installer's name and address PIPE STATE PHT

5 INDUSTRIAL RD SO. PORTLAND ME. Telephone 321-2262

Location of appliance:

- Basement
- Attic
- Floor
- Roof

Type of Fuel:

- Gas
 - Oil
 - Solid
- #9

Appliance Name: LUNA WALLHUNG BOYERS

U.L. Approved Yes No

Will appliance be installed in accordance with the manufacturer's installation instructions? Yes No

IF NO Explain: _____

The Type of License of Installer:

- Master Plumber # _____
- Solid Fuel # _____
- Oil # _____
- Gas # PVT1197
- Other _____

Approved

See attached letter or requirement

Approved with Conditions

Fire: _____

Ele.: _____

Bldg.: pmh

Signature of Installer Terrance J. Davis X 109 Inspector's Signature _____ Date Approved _____

White - Inspection Yellow - File Pink - Applicant's Gold - Assessor's Copy

14 10 03

Type of Chimney:

- Masonry Lined
- Factory built _____

Metal

Factory Built U.L. Listing # _____

Direct Vent

Type _____

Type of Fuel Tank

- Oil
- Gas


Size of Tank N/A

Number of Tanks _____

Distance from Tank to Center of Flame _____ feet

Cost of Work: \$ 41,600.00

Permit Fee: \$ 399.00



Pine State Plumbing & Heating
PO Box 6308
Scarborough, ME 04070-6308
TEL: 207-321-2261
FAX: 207-780-0696 - Contract Sales



Fax


To: JEANNIE From: TERRY

Fax: _____ Pages: 6

Phone: _____ Date: _____

Rec: _____ CC: _____

- Urgent
- For Review
- Please Comment
- Please Reply
- Please Recycle



www.pinstatesuddenservice.com

City of Portland, Maine - Building or Use Permit

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

Permit No:	05-0444	Date Applied For:	04/21/2005	CBL:	013 K028001
------------	---------	-------------------	------------	------	-------------

Location of Construction:	117 Sheridan St	Owner Name:	Fort Summer LLC	Owner Address:	12 Simonton St	Phone:	
Business Name:		Contractor Name:	Pine State Plumbing & Heating	Contractor Address:	PO Box 6308 Scarborough	Phone	(207) 321-2261
Lessee/Buyer's Name		Phone:		Permit Type:	HVAC		

Proposed Use:	Condo install a Luna Wall hung boiler	Proposed Project Description:	Install a Luna Boiler wall hung
---------------	---------------------------------------	-------------------------------	---------------------------------

Dept: Zoning **Status:** Approved **Reviewer:** Jeanine Bourke **Approval Date:** 12/19/2005
Note: **Ok to Issue:**

Dept: Building **Status:** Approved with Conditions **Reviewer:** Jeanine Bourke **Approval Date:** 12/23/2005
Note: **Ok to Issue:**
 1) The installation must comply with the State of Maine Gas Regulations.

Dept: Fire **Status:** Approved with Conditions **Reviewer:** Cpm Greg Cass **Approval Date:** 12/22/2005
Note: **Ok to Issue:**
 1) Install to comply with NFPA 54 or 58 which ever is applicable. Application did not state L/P or Natural gas.

Comments:

05/02/2005-dmartin: Talked to Terry said he'd send the specs for hanging unit. Left VM that we still have not gotten them. Pine State Plumbing called 4/25 said they were going to send them, today 5/2 they still have not come in, putting permit on hold in the "hold filing cabinet"
 12/19/2005-jimb: Reviewing permits for CO's, did not receive the info requested, left vm w/Terry to send specs.

BAXXI

LUNNA 310 Fi


High efficiency gas fired wall mounted combination boiler

Chaudière murale à gaz à rendement élevé

Installation and servicing instructions
Notice d'installation et d'entretien



BAXXI s.p.a., one of the leading European enterprises to produce central heating and hot water devices for domestic use (wall-mounted gas-operated boilers, floor-standing boilers, electrical water-heaters and steel heating plates) has obtained the QSC certificate of conformity to the UNI EN ISO 9001 norms. This certificate guarantees that the Quality System applied at the **BAXXI s.p.a.** factory in Bassano del Grappa, where your boiler was produced, meets the standards of the UNI EN ISO 9001 norm, which is the strictest and concerns all organization stages and operating personnel involved in the production and distribution processes.



BAXXI s.p.a., l'une des entreprises leader en Europe dans la production d'appareils de chauffage et sanitaires à usage domestique, (chaudières murales à gaz, chaudières au sol, chauffe-eau électriques, plaques de chauffe en acier), a obtenu la certification QSC de conformité aux normes UNI EN ISO 9001. Ce certificat assure que le Système de Qualité en usage aux usines **BAXXI s.p.a.** de Bassano del Grappa, où l'on a produit cette chaudière, satisfait la plus sévère des normes - c'est-à-dire la UNI EN ISO 9001 - qui concerne tous les stades d'organisation et le personnel intervenant du procès de production et distribution.

2. Technical data

2.1 PERFORMANCE

Central Heating		MAX	MIN
		0-2000 Ft/2000-4500 Ft 0-610 m 610-1370 m	
Heat Input (Gross)	Btu/h kW	126 249 37	45 040 13.2
Heat Output (modulating)	Btu/h kW	105 776 31	35 486 10.4
Burner Pressure Setting natural gas (A)	p.s.i. mbar	0.203 14.0	0.0261 1.8
Gas Rate natural gas (A)	m ³ /h ft ³ /h	3.52 124.2	1.26 44.5
Burner Pressure Setting LP gas (E)	p.s.i. mbar	0.3541 24.4	0.0479 3.3
Gas Rate LP gas (E)	ft ³ /h m ³ /h	49.0 1.39	17.29 0.49
CH Water Temp. (Approx.)	°F °C	185 85	

2.1 PERFORMANCE

Chauffage central		MAX	MIN
		0-2000 Ft/2000-4500 Ft 0-610 m 610-1370 m	
Débit calorifique (gross)	Btu/h kW	126 249 37	45 040 13.2
Puissance utile (module)	Btu/h kW	105 776 31	35 486 10.4
Valeurs de pression au brûleur Gaz naturel (A)	p.s.i. mbar	0.203 14.0	0.0261 1.8
Débit de gaz Gaz naturel (A)	m ³ /h ft ³ /h	3.52 124.2	1.26 44.5
Valeurs de pression au brûleur Gaz LP (E)	p.s.i. mbar	0.3541 24.4	0.0479 3.3
Débit de gaz Gaz LP (E)	ft ³ /h m ³ /h	49.0 1.39	17.29 0.49
Temp. de l'eau circuit chauffage (approx.)	°F °C	185 85	

2. Données Techniques

Domestic Hot Water		MAX	MIN
		0-2000 Ft/2000-4500 Ft 0-610 m 610-1370 m	
Heat Input (Gross)	Btu/h kW	126 249 37	45 040 13.2
Heat Output (modulating)	Btu/h kW	105 776 31	35 486 10.4
Burner Pressure Setting natural gas (A)	p.s.i. mbar	0.203 14.0	0.0261 1.8
Gas Rate natural gas (A)	m ³ /h ft ³ /h	3.52 124.2	1.26 44.5
Burner Pressure Setting LP gas (E)	p.s.i. mbar	0.3541 24.4	0.0479 3.3
Gas Rate LP gas (E)	ft ³ /h m ³ /h	49.0 1.39	17.29 0.49
Flow Rate at 63°F/35°C Rise (USA)	(Can) G.P.M. l/min	2.8 3.3 12.7	
Outlet Water Temp. (Approx.)	°F °C	149 65	

Eau chaude sanitaire		MAX	MIN
		0-2000 Ft/2000-4500 Ft 0-610 m 610-1370 m	
Débit calorifique (gross)	Btu/h kW	126 249 37	45 040 13.2
Puissance utile (module)	Btu/h kW	105 776 31	35 486 10.4
Valeurs de pression au brûleur Gaz naturel (A)	p.s.i. mbar	0.203 14.0	0.0261 1.8
Débit de gaz Gaz naturel (A)	m ³ /h ft ³ /h	3.52 124.2	1.26 44.5
Valeurs de pression au brûleur Gaz LP (E)	p.s.i. mbar	0.3541 24.4	0.0479 3.3
Débit de gaz Gaz LP (E)	ft ³ /h m ³ /h	49.0 1.39	17.29 0.49
Débit d'eau avec Δt (Can) 63°F/35°C (USA)	G.P.M. l/min	2.8 3.3 12.7	
Température de l'eau sanitaire (approx.)	°F °C	149 65	

2.2 CIRCUIT

Central Heating (Scaled System)		
Max System Pressure		43 p.s.i./3 bar
Min System Pressure		7.25 p.s.i./0.5 bar
Max System temperature		185°F/85°C
Pressure Relief Valve Setting		43 p.s.i./3 bar
Expansion Vessel Size (pre-charge press.)		2.2 Gal/10 l
Flow Connection		at 11.6 p.s.i./0.8 bar
Return Connection		3/4" / 22.2 mm
Relief Valve Connection		1/2" / 15.9 mm
Recommended System Pressure (cold)		21.7 p.s.i./1.5 bar

Chauffage central (circuit étanché)		
Pression maximale du circuit		43 p.s.i./3 bar
Pression minimale du circuit		7.25 p.s.i./0.5 bar
Température maximale du circuit		185°F/85°C
Tarage soupape de pression		43 p.s.i./3 bar
Dimensions du vase d'expansion (pression avant le remplissage)		à 11.6 p.s.i./0.8 bar
Connexion départ		3/4" / 22.2 mm
Connexion retour		3/4" / 22.2 mm
Connexion soupape de pression		1/2" / 15.9 mm
Pression du circuit recommandée (à froid)		21.7 p.s.i./1.5 bar

Domestic Hot Water		
Max Mains Inlet Pressure		116 p.s.i./8 bar
Min Mains Water Pressure		2.9 p.s.i./0.2 bar
Min DHW Flow Rate		(Can) 0.55 GPM/2.5 l/min (USA) 0.66 GPM/2.5 l/min
Mains Inlet Connection		1/2" / 15.9 mm
DHW Outlet Connection		1/2" / 15.9 mm
Max DHW Temperature		149°F/65°C
DHW Water Content		(Can) 0.05 Gal/0.23 l (USA) 0.06 Gal/0.23 l

Eau chaude sanitaire		
Pression maximale d'entrée eau du réseau		116 p.s.i./8 bar
Pression minimale eau du réseau		2.9 p.s.i./0.2 bar
Débit min. ECS		(Can) 0.55 GPM/2.5 l/min (USA) 0.66 GPM/2.5 l/min
Connexion d'entrée du réseau		1/2" / 15.9 mm
Connexion de sortie ECS		1/2" / 15.9 mm
Température max. ECS		149°F/65°C
Contenance ECS		(Can) 0.05 Gal/0.23 l (USA) 0.06 Gal/0.23 l

2.3 COMPONENTS

Burner (15 blade)	Stainless Steel
Main Heat exchanger	Copper
DHW Heat exchanger	Stainless Steel
Injectors natural gas (A)	1.28 mm
Injectors LPG gas (E)	0.90 mm
Pump	Grundfos UPS 15-62/BX AO
Fume - Outer Duct	Epoxy coated
Fume - Inner Duct	Aluminum
Fan	MVL RLG 97/3400 - 3030LH
Gas Valve	SIT 837 TANDEM
Air Pressure Switch	Tidelta
Diverter Valve	Bevi

2.3 PARTIES COMPOSANTES

Brûleur (15 éléments)	acier inoxydable
Echangeur principal de chaleur	cuivre
Echangeur de chaleur ECS	acier inoxydable
Injecteurs gaz naturel (A)	1.28 mm
Injecteurs gaz LPG (E)	0.90 mm
Pompe	Grundfos: UPS 15-62/BX AO
Buse externe fumées	traitée à résine époxyde
Buse interne fumées	aluminium
Ventilateur	MVL RLG 97/3400 - 3030LH
Vanne à gaz	SIT 837 TANDEM
Commutateur pression air	Tidelta
Vanne à deux voies	Bevi

2.4 INSTALLATION

Minimum Clearances for Servicing	
Top	8.66 in / 220 mm
Bottom	9.84 in / 250 mm
Sides	1.77 in / 45 mm
Front	17.71 in / 450 mm
Flue Terminal Size Concentric System	3.93 in / 100 mm
Flue Terminal Size 2-Pipe Flue System	3.14 in / 80 mm
Flue Terminal Protruding	4.52 in / 115 mm
Lift Weight	90 lb / 41 kg

2.4 INSTALLATION

Espaces minimaux pour l'entretien	
en haut	8,66 in / 220 mm
en bas	9,84 in / 250 mm
côtés	1,77 in / 45 mm
devant	17,71 in / 450 mm
Dimensions terminal buse fumées concentrique	3,93 in / 100 mm
Dimensions terminal buse fumées à 2 conduites	3,14 in / 80 mm
Surplomb de terminal buse fumées	4,52 in / 115 mm
Poids de soulèvement	90 lb / 41 kg

2.5 GENERAL

Dimensions	Height	30.04 in / 763 mm
	Width	17.71 in / 450 mm
	Depth	13.58 in / 345 mm
Gas Connection		3/4"
Primary Water Content		(Can) 0.33 Gal / 1.5 l (USA) 0.40 Gal / 1.5 l
Air Duct Diameter		3.93 in / 100 mm
Flue Duct Diameter		2.36 in / 60 mm

2.5 DONNÉES GÉNÉRALES

Dimensions	Hauteur	30,04 in / 763 mm
	Largeur	17,71 in / 450 mm
	Profondeur	13,58 in / 345 mm
Connexion gaz		3/4"
Contenance d'eau primaire		(Can) 0,33 Gal / 1,5 l (USA) 0,40 Gal / 1,5 l
Diamètre conduit d'air		3,93 in / 100 mm
Diamètre buse fumées		2,36 in / 60 mm

2.6 ELECTRICAL

Supply	120 V 60 Hz
Power Consumption	547 Btu/h - 160 W
Internal Fuse	F 3.15 A
Electrode Spark Gap	2.5 to 3.5 mm

2.6 DONNÉES ÉLECTRIQUES

Alimentation	120 V 60 Hz
Consommation de courant	547 Btu/h - 160 W
Fusible interne	F 3,15 A
Ecartement pointes électrodes	de 2,5 à 3,5 mm

Hot Protection Mode

1. The hot protection mode is integrated to the appliance when left in the domestic hot water and central heating position. If the temperature falls below 5° C the boiler will fire on its minimum setting until a flow temperature of 30° C is reached.

Pump Protection

1. With the selector switch in either the central heating and domestic hot water position, the pump will automatically operate for 1 minute in every 24 hours to prevent sticking.

3. General Boiler Information

Protection contre le gel

1. La chaudière incorpore une protection contre le gel qui fonctionne lorsque la chaudière est en mode eau chaude sanitaire et chauffage central. Si la température du circuit descend au-dessous de 5 ° C, la chaudière démarre au ralenti jusqu'à ce que l'eau en circulation atteigne la température de 30 ° C.

Protection du circulateur

1. Lorsque le sélecteur est sur la position de chauffage central ou de chauffage central plus production d'eau chaude, le circulateur se met automatiquement à tourner pendant 1 minute toutes les 24 heures pour éviter les risques de blocage.

3. Données générales sur la chaudière

3.1 ALIMENTATION DU GAZ

La chaudière nécessite d'un débit de gaz de 128,1 ft³/h - 3,63 m³/h. Le compteur et le réseau du gaz doivent être en mesure de délivrer la quantité de gaz demandée par la chaudière en plus de la quantité demandée par tous les autres appareils de la maison. La chaudière nécessite d'au moins 3/4" de tuyauterie du réseau du gaz. Nettoyez et effectuez un essai de toute l'installation, aussi que du compteur au fin de contrôler l'étanchéité au gaz.

3.2 ALIMENTATION ÉLECTRIQUE

La chaudière nécessite de 120 V, 60 Hz. Assurez-vous que le réseau d'alimentation est polarisé.

Installez la chaudière avec mise à la terre.

Installez seulement un sectionneur, assurant la complète isolation électrique à la chaudière et aux autres contrôles externes.

Au moyen d'un câble isolé au PVC 18 AWG X3C 105 °C.

Toutes les connexions électriques doivent être installées selon les dispositions du Code Electrique National ainsi que selon les dispositions de tout autre code local, régional ou national applicable. Tous les câbles doivent être de la Classe 1 du Code Electrique National. La mise à terre de la chaudière est obligatoire comme pourvu par le Code Electrique National ANSINFP/PA nr. 70 (dernière édition).

Au Canada l'installation doit se conformer au Code Electrique Canadien CSA C22.1, Partie 1 et à tout autre code local.

3.2.1 Installation du thermostat d'ambiance

Installez le thermostat d'ambiance sur une paroi interne. Ne l'installez jamais à un endroit où il y a des courants, des conduites d'eau chaude ou froide, des accessoires d'éclairage, un téléviseur, une cheminée ou sous les rayons du soleil puisque tout cela pourrait causer du bruyillage.

3.3 PRISE D'AIR

La chaudière ne nécessite d'aucun évent air à l'endroit où elle est installée, ou lorsqu'elle est installée dans un débarras ou dans une niche.

3.4 CARNEAU

3.4.1 CONDUIT CONCENTRIQUE

Le raccord pour la buse des fumées livré avec la chaudière est de 2,64 ft / 0,75 m de longueur + terminal. En cas de buse horizontale, il est possible d'effectuer une légère déviation par rapport à la direction horizontale, pourvu que la déviation consiste en une courbure en bas vers le terminal de la buse.

Les accessoires disponibles pour la buse des fumées sont les suivants:

3,28 ft / 1 m buse
raccord à 90°

raccord à 45°

terminal à assembler pour buse verticale. Référez-vous à la notice d'installation livrée séparément avec l'équipement.

- 3.3 AIR SUPPLY
The boiler does not require any air vents in the room in which it is installed, or when installed in a cupboard or compartment.
- 3.4 FLUE SYSTEM
- 3.4.1 CONCENTRIC SYSTEM
The flue assembly supplied for the boiler is 2.64 ft / 0.75 m in length + terminal.
For horizontal flues a minor deviation from the horizontal is allowable, provided it results in a downward slope towards the terminal.
Additional flue components are available as follows:
3.28 ft / 1 m flue
90° bend
45° bend
Vertical flue terminal assembly. Refer to the separate installation instructions supplied with the assembly.

Notes: If an extra 90° bend is used, this reduces the maximum flue length by 3.28 ft / 1 m. Each 45° bend used reduces the maximum flue length by 1.64 ft / 0.5 m. Under no circumstances must the flue length (including allowances for extra bends) exceed 4 meters.

1. Locate the flue elbow on the adaptor at the top of the boiler. Set the elbow to the required orientation (rear, right or left).
2. Measure the distance from the outside wall face to the elbow (Fig. 3). This dimension will be known as 'X'.
3. Taking the air duct, mark dimension 'X' as shown (Fig. 4). Measure the length of waste material, and transfer the dimension to the flue duct (Fig. 4).
4. Remove the waste from both ducts. Ensure that the cut ends are square and free from burrs.
5. Remove the flue elbow from the adaptor.

IMPORTANT: Check all measurements before cutting.

Remarque:
Si l'on emploie un raccord additionnel de 90°, la longueur maximale de la buse des fumées sera réduite de 3.28 ft / 1 m. Tous raccords de 45° ajoutés réduisent la longueur maximale de la buse de 1.64 ft / 0.5 m. En aucun cas la longueur de la buse (les longueurs des raccords additionnels inclus) ne doit pas dépasser les 4 mètres.

1. Placer le coude d'évacuation des fumées sur l'adaptateur en haut de la chaudière. Orienter le coude selon les besoins de l'installation (en arrière, à droite ou à gauche).
2. Mesurer la distance entre le bord extérieur du mur et le coude (Fig. 3). Cette cote sera indiquée par la lettre 'X'.
3. En prenant le conduit d'air, marquer la cote 'X' (voir Fig. 4). Mesurer la longueur de la chute et la transférer sur le conduit des fumées (Fig. 4).
4. Couper les chutes des deux conduits en s'assurant que les coupes sont bien à l'équerre et sans bavures.
5. Sortir le coude de l'adaptateur.

IMPORTANT : Contrôler toutes les cotes avant de couper.





Fig. 3

13 K028

DEAN & ALLYN, INC.

FIRE PROTECTION • SPECIAL HAZARD

32 LEWISTON ROAD • BLDG. 1C
P.O. BOX 709 • GRAY, ME 04039
TEL 207/657-5646 FAX 207/657-5647

January 3, 2006

Portland Fire Department
Attn: Chief Cass

Re: Summer Court
117 Sheridan Street
Portland, ME


Dear Chief Cass,

Please be advised that the system for the above referenced location has been designed, installed and tested per the requirements of NFPA#13R and the State of Maine.

Sincerely,

Sean Carnic (JM)

Sean Carnic
Sales Representative



DEAN & ALLYN, INC.

FIRE PROTECTION * SPECIAL HAZARD

TO: *Chief Cass*

FROM: *Stan Camic*

COMPANY: *Portland Fire Dept.*

DATE: *1/3/06*

FAX NUMBER: *874-8716*

TOTAL NO. OF PAGES INCLUDING COVER: *3*

PHONE NUMBER: _____ SENDER'S REFERENCE NUMBER: _____

RE: *Summer Court*

YOUR REFERENCE NUMBER: _____

URGENT FOR REVIEW PLEASE COMMENT PLEASE REPLY PLEASE RECYCLE

NOTES/COMMENTS:

32 LEWISTON RD. RIDG. 1C* P.O. BOX 709 GRAY, ME 04039
TEL. 207/657-5646 * FAX 207/657-5647

Contractor's Material and Test Certificate for

Aboveground Piping

A. Procedure (Conforms to NFPA 13-1994)
 Upon completion of work, inspection and tests shall be made by the contractor's representative and witnessed by an owner's representative. All defects shall be corrected and system left in service before contractor's personnel finally leave the job. A certificate shall be filled out and signed by both representatives. Copies shall be prepared for approving authorities, owners and contractor. It is understood the owner's representative's signature in no way prejudices any claim against contractor for faulty material, poor workmanship, or failure to comply with approving authority's requirements or local ordinances. All "No" answers shall be explained in the Comments portion of this form.

Property Name: Summer Court Date: 8/12/05
 Property Address: 117 Sheridan St.

- B. Plans**
- Accepted by Approving Authorities (Names): Fire Marshall
 - Address: _____ Yes No
 - Installation conforms to accepted plans Yes No
 - Equipment used is approved Yes No

- C. Instructions**
- Has person in charge of fire equipment been instructed as to location of control valves and care and maintenance of this new equipment? Yes No
 - Have copies of the following been left on the premises:
 - System components instructions Yes No
 - Care and maintenance instructions Yes No
 - NFPA 25 Yes No

D. Location of system - Supplies building: Entrance

E. Sprinklers

Type	Model	Year Made	Orifice	Quantity	Temperature
<u>Type</u>	<u>LF11</u>	<u>2005</u>	<u>1/2</u>	<u>130</u>	<u>155° F</u>
<u>Type</u>	<u>LF11</u>	<u>2005</u>	<u>1/2</u>	<u>10</u>	<u>155° SW</u>
<u>Type</u>	<u>LF11</u>	<u>2005</u>	<u>1/2</u>	<u>8</u>	<u>175° P</u>
<u>Type</u>	<u>LF11</u>	<u>2005</u>	<u>1/2</u>	<u>8</u>	<u>286° P</u>

F. Pipe and Fittings

- Type of Pipe: Black Iron/CPVC
- Type of Fittings: Cast Iron/CPVC

G. Alarm Valve or Flow Indicator

Type	Make	Model	Max. Time to Operate Through Insp. Test
<u>Flow</u>	<u>Retter</u>	<u>V5FR</u>	<u>0-5 Sec</u>

H. Dry-Pipe Valve

- Make and Model: N/A
- Serial Number: _____
- Quick Opening Device (Q.O.D.)

I. Dry-Pipe System Operating Test Without Q.O.D.

- Time to trip through test connection: _____
- Water pressure _____ psi. Air pressure _____ psi.
- Trip point air pressure _____ psi.
- Time water reached test outlet: _____ psi.
- Alarm operated properly Yes No

K. Dry-Pipe System Operating Test With Q.O.D.

- Time to trip through test connection: _____
- Water pressure _____ psi. Air pressure _____ psi.
- Trip point air pressure _____ psi.
- Time water reached test outlet: _____
- Alarm operated properly Yes No

L. Deluge and Preaction Valves

- Make and Model: _____ Pneumatic Electric Hydraulic
- Operation: Operating normally supervised Yes No
- Piping and detecting media supervised Yes No
- Does valve operate from manual trip and/or remote control stations Yes No
- Is there an accessible facility in each circuit for testing Yes No
- Does each circuit operate supervision loss alarm Yes No
- Does each circuit operate valve release Yes No
- Maximum time to operate release: _____ Yes No

M. Pressure Reducing Valve

- Location and Floor: _____
- Make and Model: _____
- Setting: _____
- Static Pressure: Inlet _____ psi. Outlet _____ psi
- Residual Pressure (Flowing): Inlet _____ psi. Outlet _____ psi
- Flow Rate: _____ gpm

N. Test Description

Hydrostatic: Hydrostatic tests shall be made at not less than 200 psi (13.6 bars) for two hours or 50 psi (3.4 bars) above static pressure in excess of 150 psi (10.3 bars) for two hours. Differential dry-pipe valve leakage shall be left open during test to prevent damage. All aboveground piping leakage shall be stopped.

Pneumatic: Establish 40 psi (2.7 bars) air pressure and measure drop, which shall not exceed 1.5 psi (0.1 bars) in 24 hrs. Test pressure tanks at normal water level and air pressure and measure air pressure drop, which shall not exceed 1.5 psi (0.1 bars) in 24 hrs.

- O. Tests**
- All piping hydrostatically tested at 200 psi for 2 hours Yes No
 - Dry piping pneumatically tested N/A Yes No
 - Equipment operates properly Yes No
 - Do you certify as the sprinkler contractor that additives and corrosive chemicals, sodium silicate or derivatives of sodium silicate, brine, or other corrosive chemicals were not used for testing systems or stopping leaks? Yes No
 - Drain Test:
 - Static pressure reading of gage located near water supply connection _____ psi.
 - Residual pressure with valve in test connection open wide _____ psi.
 - Underground mains and lead in connections to risers flushed before connection made to sprinkler piping and verified by copy of form No. 13-U Yes No
 - Flushed by installer of underground piping Yes No
 - If powder driven fasteners are used in concrete, has representative sample testing been satisfactorily completed? Yes No

P. Blank Testing Gaskets

- Number used: 0 Yes No
- Locations: _____
- Number removed: 0 Yes No

Q. Welded Piping - If welded piping was used in the system, complete the following:

- Do you certify as the sprinkler contractor that welding procedures comply with the requirements of at least AWS D10.9, Level AR-3 Yes No
- Do you certify that the welding was performed by welders qualified in compliance with the requirements of at least AWS D10.9, Level AR-3 Yes No
- Do you certify that welding was carried out in compliance with a documented quality control procedure to insure that all discs are retrieved, openings in the pipe are smooth, slag and other welding residue are removed, and the internal diameters of piping are not penetrated Yes No

R. Cutouts (Disks)

Do you certify that you have a control feature to ensure that all cutouts (disks) are retrieved? Yes No

S. Hydraulic Data Nameplate Provided Yes No

T. Date left in service (with all control valves open): _____

U. Signatures

1. Name of sprinkler contractor: DEAN & ALLYN

2. Tests witnessed by: _____

Title: Owner Date: 8/12/05

For sprinkler contractor (Signed): Dean & Allyn Date: 8/12/05

V. Comments (This section is for additional explanation and notes. All "No" answers must be explained here.)

13 R wet System 4th Floor
on an anti-freeze loop

Check here if comments continue on reverse side of this form

67995 National Fire Sprinkler Association, P.O. Box 1000, Patterson, NY 12563, (845) 878-4200 Form 13-A Page 1 of 1
 TOTAL P.03