



September 25, 2003

Maine Medical Center  
19 Bramhall  
Portland, ME 04102

RE: Renovations to 6 Mechanical rooms @ 420 Cumberland Ave. Portland,  
ME

Scope of Work: Expand 6 Mechanical rooms to accommodate future additional HVAC units. Doors shall be moved or replaced as necessary. Non load bearing wall shall be moved as necessary. Mechanical Room 7 shall have fire rated doors and walls. Renovations shall be made per plans by Allied engineering.

PO Box 2564  
South Portland, ME 04116  
207.774.2800 (Phone/Fax)  
www.northshoreconst.com

22 Bramhall  
57

053 Door

Ex. Clgn. Repair at NEW WALLS

3 5/8" Steel Studs

2x4 WOOD @ Door HDR + JAMB

5/8" GNB Typ

FIRE CODE Dayway @ Mech. Room #7

R-11 Fiberglass INSULATION

Seal all GAPS @ WAY + @ Bottom

of Floor ABOVE where NECESSARY  
(PER Plenum)

Doors at Mech Room #7 SHALL HAVE

90 MIN. FIRE RATING

8'0" ±  
(VARIES)

Existing Floor

Section @

NEW WALL Construction

SCALE 1" = 1'-0"

Date 7/15/03