

DIVISION 16

PAGE INTENTIONALLY BLANK

NATIONAL ACCOUNTS

The following is a list of specification sections within this Division stipulating National Accounts the Owner has entered into with the specified manufacturer(s).

1. Section 16442 – PANELBOARDS: Electrical Switchgear.
2. Section 16511 – INTERIOR LIGHTING: Interior Lighting.
3. Section 16521 – EXTERIOR LIGHTING: Exterior Lighting.
4. Section 16700 – ELECTRONIC DETECTION SYSTEM: EAS and POS security system.
5. Section 16710 – BURGLAR ALARM SYSTEM.
6. Section 16729 – PUBLIC ADDRESS AND MUSIC SYSTEM
7. Section 16740 – COMMUNICATIONS EQUIPMENT
8. Section 16750 – ENERGY MANAGEMENT SYSTEM.

PAGE INTENTIONALLY BLANK

SECTION 16050 - BASIC ELECTRICAL MATERIALS AND METHODS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Supporting devices for electrical components.
 - 2. Electrical identification.
 - 3. Electricity-metering components.
 - 4. Concrete equipment bases.
 - 5. Cutting and patching for electrical construction.
 - 6. Touchup painting.

1.3 DEFINITIONS

- A. EMT: Electrical metallic tubing.
- B. FMC: Flexible metal conduit.
- C. IMC: Intermediate metal conduit.
- D. LFMC: Liquidtight flexible metal conduit.
- E. RNC: Rigid nonmetallic conduit.

1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70.

1.5 COORDINATION

- A. Coordinate chases, slots, inserts, sleeves, and openings with general construction work and arrange in building structure during progress of construction to facilitate the electrical installations that follow.

1. Set inserts and sleeves in poured-in-place concrete, masonry work, and other structural components as they are constructed.
- B. Sequence, coordinate, and integrate installing electrical materials and equipment for efficient flow of the Work. Coordinate installing large equipment requiring positioning before closing in the building.
- C. Coordinate electrical service connections to components furnished by utility companies.
 1. Coordinate installation and connection of exterior underground and overhead utilities and services, including provision for electricity-metering components.
 2. Comply with requirements of authorities having jurisdiction and of utility company providing electrical power and other services.
- D. Coordinate location of access panels and doors for electrical items that are concealed by finished surfaces. Access doors and panels are specified in Division 8 Section "Access Doors."
- E. Where electrical identification devices are applied to field-finished surfaces, coordinate installation of identification devices with completion of finished surface.
- F. Where electrical identification markings and devices will be concealed by acoustical ceilings and similar finishes, coordinate installation of these items before ceiling installation.

PART 2 - PRODUCTS

2.1 SUPPORTING DEVICES

- A. Material: Cold-formed steel, with corrosion-resistant coating acceptable to authorities having jurisdiction.
- B. Metal Items for Use Outdoors or in Damp Locations: Hot-dip galvanized steel.
- C. Slotted-Steel Channel Supports: Comply with Division 5 Section "Metal Fabrications" for slotted channel framing.
 1. Channel Thickness: Selected to suit structural loading.
 2. Fittings and Accessories: Products of the same manufacturer as channel supports.

2.2 ELECTRICAL IDENTIFICATION

- A. Identification Devices: A single type of identification product for each application category. Use colors prescribed by ANSI A13.1, NFPA 70, and these Specifications.
- B. Raceway and Cable Labels: Comply with ANSI A13.1, Table 3, for minimum size of letters for legend and minimum length of color field for each raceway and cable size.

1. Type: Pretensioned, wraparound plastic sleeves. Flexible, preprinted, color-coded, acrylic band sized to suit the diameter of the item it identifies.
 2. Type: Preprinted, flexible, self-adhesive, vinyl. Legend is overlaminated with a clear, weather- and chemical-resistant coating.
 3. Color: Black letters on orange background.
 4. Legend: Indicates voltage.
- C. Colored Adhesive Marking Tape for Raceways, Wires, and Cables: Self-adhesive vinyl tape, not less than 1 inch wide by 3 mils thick.
- D. Underground Warning Tape: Permanent, bright-colored, continuous-printed, vinyl tape with the following features:
1. Not less than 6 inches wide by 4 mils thick.
 2. Compounded for permanent direct-burial service.
 3. Embedded continuous metallic strip or core.
 4. Printed legend that indicates type of underground line.
- E. Tape Markers for Wire: Vinyl or vinyl-cloth, self-adhesive, wraparound type with preprinted numbers and letters.
- F. Color-Coding Cable Ties: Type 6/6 nylon, self-locking type. Colors to suit coding scheme.
- G. Engraved-Plastic Labels, Signs, and Instruction Plates: Engraving stock, melamine plastic laminate punched or drilled for mechanical fasteners 1/16-inch minimum thickness for signs up to 20 sq. in. and 1/8-inch minimum thickness for larger sizes. Engraved legend in black letters on white background.
- H. Interior Warning and Caution Signs: Comply with 29 CFR, Chapter XVII, Part 1910.145. Preprinted, aluminum, baked-enamel-finish signs, punched or drilled for mechanical fasteners, with colors, legend, and size appropriate to the application.
- I. Exterior Warning and Caution Signs: Comply with 29 CFR, Chapter XVII, Part 1910.145. Weather-resistant, nonfading, preprinted, cellulose-acetate butyrate signs with 0.0396-inch, galvanized-steel backing, with colors, legend, and size appropriate to the application. 1/4-inch grommets in corners for mounting.
- J. Fasteners for Nameplates and Signs: Self-tapping, stainless-steel screws or No. 10/32 stainless-steel machine screws with nuts and flat and lock washers.
- 2.3 EQUIPMENT FOR UTILITY COMPANY'S ELECTRICITY METERING
- A. Current-Transformer Cabinets: Comply with requirements of electrical power utility company.
- B. Meter Sockets: Comply with requirements of electrical power utility company.

2.4 CONCRETE BASES

- A. Concrete Forms and Reinforcement Materials: As specified in Division 3 Section "Cast-in-Place Concrete."

2.5 TOUCHUP PAINT

- A. For Equipment: Equipment manufacturer's paint selected to match installed equipment finish.
- B. Galvanized Surfaces: Zinc-rich paint recommended by item manufacturer.

PART 3 - EXECUTION

3.1 ELECTRICAL EQUIPMENT INSTALLATION

- A. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide the maximum possible headroom.
- B. Materials and Components: Install level, plumb, and parallel and perpendicular to other building systems and components, unless otherwise indicated.
- C. Equipment: Install to facilitate service, maintenance, and repair or replacement of components. Connect for ease of disconnecting, with minimum interference with other installations.
- D. Right of Way: Give to raceways and piping systems installed at a required slope.

3.2 ELECTRICAL SUPPORTING DEVICE APPLICATION

- A. Damp Locations and Outdoors: Hot-dip galvanized materials or nonmetallic, U-channel system components.
- B. Dry Locations: Steel materials.
- C. Support Clamps for PVC Raceways: Click-type clamp system.
- D. Selection of Supports: Comply with manufacturer's written instructions.
- E. Strength of Supports: Adequate to carry present and future loads, times a safety factor of at least four; minimum of 200-lb design load.

3.3 SUPPORT INSTALLATION

- A. Install support devices to securely and permanently fasten and support electrical components.

- B. Install individual and multiple raceway hangers and riser clamps to support raceways. Provide U-bolts, clamps, attachments, and other hardware necessary for hanger assemblies and for securing hanger rods and conduits.
- C. Support parallel runs of horizontal raceways together on trapeze- or bracket-type hangers.
- D. Size supports for multiple raceway installations so capacity can be increased by a 25 percent minimum in the future.
- E. Support individual horizontal raceways with separate, malleable-iron pipe hangers or clamps.
- F. Arrange supports in vertical runs so the weight of raceways and enclosed conductors is carried entirely by raceway supports, with no weight load on raceway terminals.
- G. Simultaneously install vertical conductor supports with conductors.
- H. Separately support cast boxes that are threaded to raceways and used for fixture support. Support sheet-metal boxes directly from the building structure or by bar hangers. If bar hangers are used, attach bar to raceways on opposite sides of the box and support the raceway with an approved fastener not more than 24 inches from the box.
- I. Install metal channel racks for mounting cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices unless components are mounted directly to structural elements of adequate strength.
- J. Install sleeves for cable and raceway penetrations of concrete slabs and walls unless core-drilled holes are used. Install sleeves for cable and raceway penetrations of masonry and fire-rated gypsum walls and of all other fire-rated floor and wall assemblies. Install sleeves during erection of concrete and masonry walls.
- K. Securely fasten electrical items and their supports to the building structure, unless otherwise indicated. Perform fastening according to the following unless other fastening methods are indicated:
 - 1. Wood: Fasten with wood screws or screw-type nails.
 - 2. Masonry: Toggle bolts on hollow masonry units and expansion bolts on solid masonry units.
 - 3. New Concrete: Concrete inserts with machine screws and bolts.
 - 4. Existing Concrete: Expansion bolts.
 - 5. Steel: Welded threaded studs or spring-tension clamps on steel.
 - a. Field Welding: Comply with AWS D1.1.
 - 6. Welding to steel structure may be used only for threaded studs, not for conduits, pipe straps, or other items.
 - 7. Light Steel: Sheet-metal screws.
 - 8. Fasteners: Select so the load applied to each fastener does not exceed 25 percent of its proof-test load.

3.4 IDENTIFICATION MATERIALS AND DEVICES

- A. Install at locations for most convenient viewing without interference with operation and maintenance of equipment.
- B. Coordinate names, abbreviations, colors, and other designations used for electrical identification with corresponding designations indicated in the Contract Documents or required by codes and standards. Use consistent designations throughout Project.
- C. Identify raceways and cables with color banding as follows:
 - 1. Colors: As follows:
 - a. Fire Alarm System: Red.
 - b. Security System: Blue and yellow.
 - c. Telecommunication System: Green and yellow.
- D. Tag and label circuits designated to be extended in the future. Identify source and circuit numbers in each cabinet, pull and junction box, and outlet box. Color-coding may be used for voltage and phase identification.
- E. Install continuous underground plastic markers during trench backfilling, for exterior underground power, control, signal, and communication lines located directly above power and communication lines. Locate 6 to 8 inches below finished grade. If width of multiple lines installed in a common trench or concrete envelope does not exceed 16 inches, overall, use a single line marker.
- F. Color-code 208/120-V system service, feeder, and branch-circuit conductors throughout the secondary electrical system as follows:
 - 1. Phase A: Black.
 - 2. Phase B: Red.
 - 3. Phase C: Blue.
 - 4. Neutral: White.
 - 5. Ground: Green.

3.5 UTILITY COMPANY ELECTRICITY-METERING EQUIPMENT

- A. Install equipment according to utility company's written requirements. Provide grounding and empty conduits as required by utility company.

3.6 FIRESTOPPING

- A. Apply firestopping to cable and raceway penetrations of fire-rated floor and wall assemblies to achieve fire-resistance rating of the assembly. Firestopping materials and installation requirements are specified in Division 7 Section "Firestopping."

3.7 CONCRETE BASES

- A. Construct concrete bases of dimensions indicated, but not less than 4 inches larger, in both directions, than supported unit. Follow supported equipment manufacturer's anchorage recommendations and setting templates for anchor-bolt and tie locations, unless otherwise indicated. Use 3000-psi, 28-day compressive-strength concrete and reinforcement as specified in Division 3 Section "Cast-in-Place Concrete."

3.8 CUTTING AND PATCHING

- A. Cut, channel, chase, and drill floors, walls, partitions, ceilings, and other surfaces required to permit electrical installations. Perform cutting by skilled mechanics of trades involved.
- B. Repair and refinish disturbed finish materials and other surfaces to match adjacent undisturbed surfaces. Install new fireproofing where existing firestopping has been disturbed. Repair and refinish materials and other surfaces by skilled mechanics of trades involved.

3.9 FIELD QUALITY CONTROL

- A. Inspect installed components for damage and faulty work, including the following:
 - 1. Raceways.
 - 2. Building wire and connectors.
 - 3. Supporting devices for electrical components.
 - 4. Electrical identification.
 - 5. Concrete bases.
 - 6. Cutting and patching for electrical construction.
 - 7. Touchup painting.

3.10 REFINISHING AND TOUCHUP PAINTING

- A. Refinish and touch up paint. Paint materials and application requirements are specified in Division 9 Section "Painting."

3.11 CLEANING AND PROTECTION

- A. On completion of installation, including outlets, fittings, and devices, inspect exposed finish. Remove burrs, dirt, paint spots, and construction debris.
- B. Protect equipment and installations and maintain conditions to ensure that coatings, finishes, and cabinets are without damage or deterioration at time of Substantial Completion.

END OF SECTION 16050

SECTION 16060 - GROUNDING AND BONDING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes grounding of electrical systems and equipment. Grounding requirements specified in this Section may be supplemented by special requirements of systems described in other Sections.

1.3 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Testing agency as defined by OSHA in 29 CFR 1910.7 or a member company of the InterNational Electrical Testing Association and that is acceptable to authorities having jurisdiction.
 - 1. Testing Agency's Field Supervisor: Person currently certified by the InterNational Electrical Testing Association to supervise on-site testing specified in Part 3.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
 - 1. Comply with UL 467.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Grounding Conductors, Cables, Connectors, and Rods:
 - a. Apache Grounding/Erico Inc.
 - b. Boggs, Inc.
 - c. Chance/Hubbell.
 - d. Copperweld Corp.
 - e. Dossert Corp.
 - f. Erico Inc.; Electrical Products Group.

- g. Framatome Connectors/Burndy Electrical.
- h. Galvan Industries, Inc.
- i. Harger Lightning Protection, Inc.
- j. Hastings Fiber Glass Products, Inc.
- k. Heary Brothers Lightning Protection Co.
- l. Ideal Industries, Inc.
- m. ILSCO.
- n. Kearney/Cooper Power Systems.
- o. Korns: C. C. Korns Co.; Division of Robroy Industries.
- p. Lightning Master Corp.
- q. Lyncole XIT Grounding.
- r. O-Z/Gedney Co.; a business of the EGS Electrical Group.
- s. Raco, Inc.; Division of Hubbell.
- t. Robbins Lightning, Inc.
- u. Salisbury: W. H. Salisbury & Co.
- v. Superior Grounding Systems, Inc.
- w. Thomas & Betts, Electrical.

2.2 GROUNDING CONDUCTORS

- A. For insulated conductors, comply with Division 16 Section "Conductors and Cables."
- B. Material: Copper.
- C. Equipment Grounding Conductors: Insulated with green-colored insulation.
- D. Isolated Ground Conductors: Insulated with green-colored insulation with yellow stripe. On feeders with isolated ground, use colored tape, alternating bands of green and yellow tape to provide a minimum of three bands of green and two bands of yellow.
- E. Grounding Electrode Conductors: Stranded cable.
- F. Underground Conductors: Bare, tinned, stranded, unless otherwise indicated.
- G. Bare Copper Conductors: Comply with the following:
 - 1. Solid Conductors: ASTM B 3.
 - 2. Assembly of Stranded Conductors: ASTM B 8.
 - 3. Tinned Conductors: ASTM B 33.
- H. Copper Bonding Conductors: As follows:
 - 1. Bonding Cable: 28 kcmil, 14 strands of No. 17 AWG copper conductor, 1/4 inch in diameter.
 - 2. Bonding Conductor: No. 4 or No. 6 AWG, stranded copper conductor.
 - 3. Bonding Jumper: Bare copper tape, braided bare copper conductors, terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.
 - 4. Tinned Bonding Jumper: Tinned-copper tape, braided copper conductors, terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.

- I. Grounding Bus: Bare, annealed copper bars of rectangular cross section, with insulators.

2.3 CONNECTOR PRODUCTS

- A. Comply with IEEE 837 and UL 467; listed for use for specific types, sizes, and combinations of conductors and connected items.
- B. Bolted Connectors: Bolted-pressure-type connectors, or compression type.
- C. Welded Connectors: Exothermic-welded type, in kit form, and selected per manufacturer's written instructions.

2.4 GROUNDING ELECTRODES

- A. Ground Rods: Copper-clad steel.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Use only copper conductors for both insulated and bare grounding conductors in direct contact with earth, concrete, masonry, crushed stone, and similar materials.
- B. In raceways, use insulated equipment grounding conductors.
- C. Exothermic-Welded Connections: Use for connections to structural steel and for underground connections, except those at test wells.
- D. Equipment Grounding Conductor Terminations: Use bolted pressure clamps.
- E. Ground Rod Clamps at Test Wells: Use bolted pressure clamps with at least two bolts.

3.2 EQUIPMENT GROUNDING CONDUCTORS

- A. Comply with NFPA 70, Article 250, for types, sizes, and quantities of equipment grounding conductors, unless specific types, larger sizes, or more conductors than required by NFPA 70 are indicated.
- B. Install equipment grounding conductors in all feeders and circuits.
- C. Computer Outlet Circuits: Install insulated equipment grounding conductor in branch-circuit runs from computer-area power panels or power-distribution units.
- D. Isolated Grounding Receptacle Circuits: Install an insulated equipment grounding conductor connected to the receptacle grounding terminal. Isolate grounding conductor from raceway and from panelboard grounding terminals. Terminate at

equipment grounding conductor terminal of the applicable derived system or service, unless otherwise indicated.

- E. Isolated Equipment Enclosure Circuits: For designated equipment supplied by a branch circuit or feeder, isolate equipment enclosure from supply raceway with a nonmetallic raceway fitting listed for the purpose. Install fitting where raceway enters enclosure, and install a separate equipment grounding conductor. Isolate equipment grounding conductor from raceway and from panelboard grounding terminals. Terminate at equipment grounding conductor terminal of the applicable derived system or service, unless otherwise indicated.
- F. Nonmetallic Raceways: Install an equipment grounding conductor in nonmetallic raceways unless they are designated for telephone or data cables.
- G. Signal and Communication Systems: For telephone, alarm, voice and data, and other communication systems, provide No. 4 AWG minimum insulated grounding conductor in raceway from grounding electrode system to each service location, terminal cabinet, wiring closet, and central equipment location.
 - 1. Service and Central Equipment Locations and Wiring Closets: Terminate grounding conductor on a 1/4-by-2-by-12-inch grounding bus.
 - 2. Terminal Cabinets: Terminate grounding conductor on cabinet grounding terminal.
- H. Metal Poles Supporting Outdoor Lighting Fixtures: Provide a grounding electrode in addition to installing a separate equipment grounding conductor with supply branch-circuit conductors.

3.3 INSTALLATION

- A. Ground Rods: Install at least three rods spaced at least one-rod length from each other and located at least the same distance from other grounding electrodes.
 - 1. Drive ground rods until tops are 2 inches below finished floor or final grade, unless otherwise indicated.
 - 2. Interconnect ground rods with grounding electrode conductors. Use exothermic welds, except at test wells and as otherwise indicated. Make connections without exposing steel or damaging copper coating.
- B. Grounding Conductors: Route along shortest and straightest paths possible, unless otherwise indicated. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.
- C. Bonding Straps and Jumpers: Install so vibration by equipment mounted on vibration isolation hangers and supports is not transmitted to rigidly mounted equipment. Use exothermic-welded connectors for outdoor locations, unless a disconnect-type connection is required; then, use a bolted clamp. Bond straps directly to the basic structure taking care not to penetrate any adjacent parts. Install straps only in locations accessible for maintenance.

- D. Metal Water Service Pipe: Provide insulated copper grounding conductors, in conduit, from building's main service equipment, or grounding bus, to main metal water service entrances to building. Connect grounding conductors to main metal water service pipes by grounding clamp connectors. Where a dielectric main water fitting is installed, connect grounding conductor to street side of fitting. Bond metal grounding conductor conduit or sleeve to conductor at each end.
- E. Water Meter Piping: Use braided-type bonding jumpers to electrically bypass water meters. Connect to pipe with grounding clamp connectors.

3.4 CONNECTIONS

- A. General: Make connections so galvanic action or electrolysis possibility is minimized. Select connectors, connection hardware, conductors, and connection methods so metals in direct contact will be galvanically compatible.
 - 1. Use electroplated or hot-tin-coated materials to ensure high conductivity and to make contact points closer to order of galvanic series.
 - 2. Make connections with clean, bare metal at points of contact.
 - 3. Make aluminum-to-steel connections with stainless-steel separators and mechanical clamps.
 - 4. Make aluminum-to-galvanized steel connections with tin-plated copper jumpers and mechanical clamps.
 - 5. Coat and seal connections having dissimilar metals with inert material to prevent future penetration of moisture to contact surfaces.
- B. Exothermic-Welded Connections: Comply with manufacturer's written instructions. Welds that are puffed up or that show convex surfaces indicating improper cleaning are not acceptable.
- C. Equipment Grounding Conductor Terminations: For No. 8 AWG and larger, use pressure-type grounding lugs. No. 10 AWG and smaller grounding conductors may be terminated with winged pressure-type connectors.
- D. Noncontact Metal Raceway Terminations: If metallic raceways terminate at metal housings without mechanical and electrical connection to housing, terminate each conduit with a grounding bushing. Connect grounding bushings with a bare grounding conductor to grounding bus or terminal in housing. Bond electrically noncontinuous conduits at entrances and exits with grounding bushings and bare grounding conductors, unless otherwise indicated.

3.5 UNDERGROUND DISTRIBUTION SYSTEM GROUNDING

- A. Pad-Mounted Transformers and Switches: Install two ground rods and counterpoise circling pad. Ground pad-mounted equipment and noncurrent-carrying metal items associated with substations by connecting them to underground cable and grounding electrodes. Use tinned-copper conductor not less than No. 2 AWG for counterpoise and for taps to equipment ground pad. Bury counterpoise not less than 18 inches below grade and 6 inches from the foundation.

3.6 FIELD QUALITY CONTROL

A. Testing: Perform the following field quality-control testing:

1. After installing grounding system but before permanent electrical circuitry has been energized, test for compliance with requirements.
2. Test completed grounding system at each location where a maximum ground-resistance level is specified, at service disconnect enclosure grounding terminal, and at ground test wells. Measure ground resistance not less than two full days after the last trace of precipitation, and without the soil being moistened by any means other than natural drainage or seepage and without chemical treatment or other artificial means of reducing natural ground resistance. Perform tests, by the fall-of-potential method according to IEEE 81.
3. Excessive Ground Resistance: If resistance to ground exceeds specified values, notify Architect promptly and include recommendations to reduce ground resistance.

END OF SECTION 16060

SECTION 16071 - SEISMIC CONTROLS FOR ELECTRICAL WORK

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes seismic restraints and other earthquake-damage-reduction measures for electrical components. It applies to and complements optional seismic-restraint requirements in the various electrical component Sections of these Specifications.

1.2 DEFINITIONS

- A. Seismic Restraint: A fixed device (a seismic brace, an anchor bolt or stud, or a fastening assembly) used to prevent vertical or horizontal movement, or both vertical and horizontal movement, of an electrical system component during an earthquake.
- B. Mobile Structural Element: A part of the building structure such as a slab, floor structure, roof structure, or wall that may move independently of other structural elements during an earthquake.

1.3 QUALITY ASSURANCE

- A. Comply with seismic-restraint requirements in BOCA, SBC, UBC, unless requirements in this Section are more stringent.
- B. Testing Agency Qualifications: An independent testing and inspection agency, acceptable to authorities having jurisdiction, with the experience and capability to conduct the inspection indicated.

1.4 PROJECT CONDITIONS

- A. Project Seismic Zone and Zone Factor as Defined in UBC: 2a and 0.15
- B. Occupancy Category as Defined in UBC: M (Mercantile)
- C. Acceleration Factor as Defined in UBC, BOCA, or SBC: .12g
- D. Project Seismic Hazard Exposure Group as Defined in BOCA or SBC: Group I

1.5 COORDINATION

- A. Coordinate layout and installation of seismic bracing with building structure, architectural features, and mechanical, fire-protection, electrical, and other building systems.

- B. Coordinate concrete bases with building structural system.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. B-Line Systems, Inc.
 2. Powerstrut.
 3. Thomas & Betts Corp.
 4. Unistrut Corporation.

2.2 MATERIALS

- A. Use the following materials for restraints:
 1. Indoor Dry Locations: Steel, zinc plated.
 2. Outdoors and Damp Locations: Galvanized steel.
 3. Corrosive Locations: Stainless steel.

2.3 ANCHORAGE AND STRUCTURAL ATTACHMENT COMPONENTS

- A. Strength: Defined in reports by ICBO Evaluation Service or another agency acceptable to authorities having jurisdiction.
 1. Structural Safety Factor: Strength in tension and shear of components shall be at least twice the maximum seismic forces for which they are required to be designed.
- B. Concrete and Masonry Anchor Bolts and Studs: Steel-expansion wedge type.
- C. Concrete Inserts: Steel-channel type.
- D. Through Bolts: Structural type, hex head, high strength. Comply with ASTM A 325.
- E. Welding Lugs: Comply with MSS SP-69, Type 57.
- F. Beam Clamps for Steel Beams and Joists: Double sided. Single-sided type is not acceptable.
- G. Bushings for Floor-Mounted Equipment Anchors: Neoprene units designed for seismically rated rigid equipment mountings, and matched to the type and size of anchor bolts and studs used.

- H. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for seismically rated rigid equipment mountings, and matched to the type and size of attachment devices used.

2.4 SEISMIC-BRACING COMPONENTS

- A. Slotted Steel Channel: 1-5/8-by-1-5/8-inch cross section, formed from 0.1046-inch-thick steel, with 9/16-by-7/8-inch slots at a maximum of 2 inches o.c. in webs, and flange edges turned toward web.
1. Materials for Channel: ASTM A 570, GR 33.
 2. Materials for Fittings and Accessories: ASTM A 575, ASTM A 576, or ASTM A 36.
 3. Fittings and Accessories: Products of the same manufacturer as channels and designed for use with that product.
 4. Finish: Baked, rust-inhibiting, acrylic-enamel paint applied after cleaning and phosphate treatment, unless otherwise indicated.
- B. Channel-Type Bracing Assemblies: Slotted steel channel, with adjustable hinged steel brackets and bolts.
- C. Hanger Rod Stiffeners: Slotted steel channels, installed vertically, with internally bolted connections to hanger rod.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install seismic restraints according to applicable codes and regulations and as approved by authorities having jurisdiction, unless more stringent requirements are indicated.
- B. Install structural attachments as follows:
1. Use bolted connections with steel brackets, slotted channel, and slotted-channel fittings to spread structural loads and reduce stresses.
 2. Attachments to New Concrete: Bolt to channel-type concrete inserts or use expansion anchors.
 3. Attachments to Existing Concrete: Use expansion anchors.
 4. Holes for Expansion Anchors in Concrete: Drill at locations and to depths that avoid reinforcing bars.
 5. Attachments to Solid Concrete Masonry Unit Walls: Use expansion anchors.
 6. Attachments to Hollow Walls: Bolt to slotted steel channels fastened to wall with expansion anchors.
 7. Attachments to Wood Structural Members: Install bolts through members.
 8. Attachments to Steel: Bolt to clamps on flanges of beams or on upper truss chords of bar joists.

C. Install electrical equipment anchorage as follows:

1. Anchor panelboards, motor-control centers, motor controls, switchboards, switchgear, transformers, unit substations, fused power-circuit devices, transfer switches, busway, battery racks, static uninterruptible power units, power conditioners, capacitor units, communication system components, and electronic signal processing, control, and distribution units as follows:
 - a. Anchor equipment rigidly to a single mobile structural element or to a concrete base that is structurally tied to a single mobile structural element.
 - b. Size concrete bases so expansion anchors will be a minimum of 10 bolt diameters from the edge of the concrete base.
 - c. Concrete Bases for Floor-Mounted Equipment: Use female expansion anchors and install studs and nuts after equipment is positioned.
 - d. Bushings for Floor-Mounted Equipment Anchors: Install to allow for resilient media between anchor bolt or stud and mounting hole in concrete.
 - e. Anchor Bolt Bushing Assemblies for Wall-Mounted Equipment: Install to allow for resilient media where equipment or equipment-mounting channels are attached to wall.
 - f. Torque bolts and nuts on studs to values recommended by equipment manufacturer.

D. Install seismic bracing as follows:

1. Install bracing according to spacings and strengths indicated by approved analysis.
2. Expansion and Contraction: Install to allow for thermal movement of braced components.
3. Attachment to Structure: If specific attachment is not indicated, anchor bracing to the structure at flanges of beams, upper truss chords of bar joists, or at concrete members.

- E. Accommodation of Differential Seismic Motion: Make flexible connections in raceways, cables, wireway, cable trays, and busway where they cross expansion- and seismic-control joints, where adjacent sections or branches are supported by different structural elements, and where they terminate at electrical equipment anchored to a different mobile structural element from the one supporting them.

3.2 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing and inspection agency to inspect seismic-control installation for compliance with indicated requirements.
- B. Reinspection: Correct deficiencies and verify by reinspection that work complies with requirements.
- C. Provide written report of tests and inspections.

END OF SECTION 16071

SECTION 16120 - CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes building wires and cables and associated connectors, splices, and terminations for wiring systems rated 600 V and less.

1.3 QUALITY ASSURANCE

- A. Listing and Labeling: Provide wires and cables specified in this Section that are listed and labeled.
 - 1. The Terms "Listed" and "Labeled": As defined in NFPA 70, Article 100.
 - 2. Listing and Labeling Agency Qualifications: A "Nationally Recognized Testing Laboratory" as defined in OSHA Regulation 1910.7.

- B. Comply with NFPA 70.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Deliver wires and cables according to NEMA WC 26.

1.5 COORDINATION

- A. Coordinate layout and installation of cables with other installations.
- B. Revise locations and elevations from those indicated, as required to suit field conditions and as approved by Architect.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Wires and Cables:
 - a. Alcan Aluminum Corporation; Alcan Cable Div.
 - b. American Insulated Wire Corp.; Leviton Manufacturing Co.
 - c. BICC Brand-Rex Company.
 - d. Carol Cable Co., Inc.
 - e. Senator Wire & Cable Company.
 - f. Southwire Company.
2. Connectors for Wires and Cables:
 - a. AMP Incorporated.
 - b. General Signal; O-Z/Gedney Unit.
 - c. Monogram Co.; AFC.
 - d. Square D Co.; Anderson.
 - e. 3M Company; Electrical Products Division.

2.2 BUILDING WIRES AND CABLES

- A. UL-listed building wires and cables with conductor material, insulation type, cable construction, and rating as specified in Part 3 "Wire and Insulation Applications" Article.
- B. Rubber Insulation Material: Comply with NEMA WC 3.
- C. Thermoplastic Insulation Material: Comply with NEMA WC 5.
- D. Cross-Linked Polyethylene Insulation Material: Comply with NEMA WC 7.
- E. Ethylene Propylene Rubber Insulation Material: Comply with NEMA WC 8.
- F. Conductor Material: Copper.
- G. Stranding: Solid conductor for No. 10 AWG and smaller; stranded conductor for larger than No. 10 AWG.

2.3 CONNECTORS AND SPLICES

- A. UL-listed, factory-fabricated wiring connectors of size, ampacity rating, material, type, and class for application and service indicated. Comply with Project's installation requirements and as specified in Part 3 "Wire and Insulation Applications" Article.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine raceways and building finishes to receive wires and cables for compliance with requirements for installation tolerances and other conditions affecting performance

of wires and cables. Do not proceed with installation until unsatisfactory conditions have been corrected.

3.2 WIRE AND INSULATION APPLICATIONS

- A. Service Entrance: Type RHW or THWN, in raceway.
- B. Feeders: Type THHN/THWN, in raceway.
- C. Fire-Pump Feeder: Type MI, 3-conductor.
- D. Branch Circuits: Type THHN/THWN, in raceway.
- E. Fire Alarm Circuits: Power-limited, fire-protective, signaling circuit cable.
- F. Class 2 Control Circuits: Power-limited tray cable, in cable tray.

3.3 INSTALLATION

- A. Install wires and cables as indicated, according to manufacturer's written instructions and NECA's "Standard of Installation."
- B. Pull Conductors: Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- C. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- D. Install exposed cables, parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- E. Support cables according to Division 16 Section "Basic Electrical Materials and Methods."
- F. Seal around cables penetrating fire-rated elements according to Division 7 Section "Firestopping."
- G. Identify wires and cables according to Division 16 Section "Basic Electrical Materials and Methods."

3.4 CONNECTIONS

- A. Conductor Splices: Keep to minimum.
- B. Install splices and tapes that possess equivalent or better mechanical strength and insulation ratings than conductors being spliced.

- C. Use splice and tap connectors compatible with conductor material.
- D. Use oxide inhibitor in each splice and tap connector for aluminum conductors.
- E. Wiring at Outlets: Install conductor at each outlet, with at least 12 inches of slack.
- F. Connect outlets and components to wiring and to ground as indicated and instructed by manufacturer.
- G. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified independent testing agency to perform field quality-control testing.
- B. Testing: On installation of wires and cables and before electrical circuitry has been energized, demonstrate product capability and compliance with requirements.
 - 1. Procedures: Perform each visual and mechanical inspection and electrical test stated in NETA ATS, Section 7.3.1. Certify compliance with test parameters.
- C. Correct malfunctioning conductors and cables at Project site, where possible, and retest to demonstrate compliance; otherwise, remove and replace with new units and retest.

END OF SECTION 16120

- h. Electri-Flex Co.
 - i. George-Ingraham Corp.
 - j. Hubbell, Inc.; Raco, Inc.
 - k. Lamson & Sessions; Carlon Electrical Products.
 - l. R&G Sloan Manufacturing Co., Inc.
 - m. Spiraduct, Inc.
 - n. Thomas & Betts Corp.
3. Conduit Bodies and Fittings:
- a. American Electric; Construction Materials Group.
 - b. Crouse-Hinds; Div. of Cooper Industries.
 - c. Emerson Electric Co.; Appleton Electric Co.
 - d. Hubbell, Inc.; Killark Electric Manufacturing Co.
 - e. Lamson & Sessions; Carlon Electrical Products.
 - f. O-Z/Gedney; Unit of General Signal.
 - g. Scott Fetzer Co.; Adalet-PLM.
 - h. Spring City Electrical Manufacturing Co.
4. Metal Wireways:
- a. Hoffman Engineering Co.
 - b. Keystone/Rees, Inc.
 - c. Square D Co.
5. Surface Metal Raceways:
- a. Airey-Thompson Co., Inc.; A-T Power Systems.
 - b. American Electric; Construction Materials Group.
 - c. Butler Manufacturing Co.; Walker Division.
 - d. Wiremold Co. (The); Electrical Sales Division.
6. Surface Nonmetallic Raceways:
- a. Anixter Brothers, Inc.
 - b. Butler Manufacturing Co.; Walker Division.
 - c. Hubbell, Inc.; Wiring Device Division.
 - d. JBC Enterprises, Inc.; Enduro Fiberglass Systems.
 - e. Lamson & Sessions; Carlon Electrical Products.
 - f. Panduit Corp.
 - g. Thermotools Co.
 - h. United Telecom; Premier Telecom Products, Inc.
 - i. Wiremold Co. (The); Electrical Sales Division.
7. Boxes, Enclosures, and Cabinets:
- a. American Electric; FL Industries.
 - b. Butler Manufacturing Co.; Walker Division.
 - c. Crouse-Hinds; Div. of Cooper Industries.
 - d. Electric Panelboard Co., Inc.
 - e. Erickson Electrical Equipment Co.

- f. Hoffman Engineering Co.; Federal-Hoffman, Inc.
- g. Hubbell Inc.; Killark Electric Manufacturing Co.
- h. Hubbell Inc.; Raco, Inc.
- i. Lamson & Sessions; Carlon Electrical Products.
- j. O-Z/Gedney; Unit of General Signal.
- k. Parker Electrical Manufacturing Co.
- l. Robroy Industries, Inc.; Electrical Division.
- m. Scott Fetzer Co.; Adalet-PLM.
- n. Spring City Electrical Manufacturing Co.
- o. Thomas & Betts Corp.
- p. Woodhead Industries, Inc.; Daniel Woodhead Co.

2.2 METAL CONDUIT AND TUBING

- A. Rigid Steel Conduit: ANSI C80.1.
- B. Rigid Aluminum Conduit: ANSI C80.5.
- C. IMC: ANSI C80.6.
- D. Plastic-Coated Steel Conduit and Fittings: NEMA RN 1.
- E. Plastic-Coated IMC and Fittings: NEMA RN 1.
- F. EMT and Fittings: ANSI C80.3.
 - 1. Fittings: Set-screw or compression type.
- G. FMC: Zinc-coated steel.
- H. Fittings: NEMA FB 1; compatible with conduit/tubing materials.

2.3 METAL WIREWAYS

- A. Material: Sheet metal sized and shaped as indicated.
- B. Fittings and Accessories: Include couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.
- C. Select features, unless otherwise indicated, as required to complete wiring system and to comply with NFPA 70.
- D. Wireway Covers: Screw-cover type.
- E. Finish: Manufacturer's standard enamel finish.

2.4 SURFACE RACEWAYS

- A. Surface Metal Raceways: Galvanized steel with snap-on covers. Finish with manufacturer's standard prime coating.
- B. Types, sizes, and channels as indicated and required for each application, with fittings that match and mate with raceways.

2.5 OUTLET AND DEVICE BOXES

- A. Sheet Metal Boxes: NEMA OS 1.
- B. Cast-Metal Boxes: NEMA FB 1, Type FD, cast box with gasketed cover.

2.6 FLOOR BOXES

- A. Floor Boxes: Cast metal, fully adjustable, rectangular.

2.7 PULL AND JUNCTION BOXES

- A. Small Sheet Metal Boxes: NEMA OS 1.
- B. Cast-Metal Boxes: NEMA FB 1, cast aluminum with gasketed cover.

2.8 ENCLOSURES AND CABINETS

- A. Hinged-Cover Enclosures: NEMA 250, Type 1, with continuous hinge cover and flush latch.
 - 1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
- B. Cabinets: NEMA 250, Type 1, galvanized steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel. Hinged door in front cover with flush latch and concealed hinge. Key latch to match panelboards. Include metal barriers to separate wiring of different systems and voltage, and include accessory feet where required for freestanding equipment.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine surfaces to receive raceways, boxes, enclosures, and cabinets for compliance with installation tolerances and other conditions affecting performance of raceway installation. Do not proceed with installation until unsatisfactory conditions have been corrected.

3.2 WIRING METHODS

A. Outdoors: Use the following wiring methods:

1. Exposed: Rigid steel or IMC.
2. Concealed: Rigid steel or IMC.
3. Underground, Single Run: RNC.
4. Underground, Grouped: RNC.
5. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.
6. Boxes and Enclosures: NEMA 250, Type 3R or Type 4.

B. Indoors: Use the following wiring methods:

1. Exposed: EMT.
2. Concealed: EMT.
3. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC; except in wet or damp locations, use LFMC.
4. Damp or Wet Locations: Rigid steel conduit.
5. Boxes and Enclosures: NEMA 250, Type 1, except as follows:
 - a. Damp or Wet Locations: NEMA 250, Type 4, stainless steel.

3.3 INSTALLATION

- A. Minimum Raceway Size: $\frac{3}{4}$ -inch trade size (DN21)
- B. Conceal conduit and EMT, unless otherwise indicated, within finished walls, ceilings, and floors.
- C. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.
- D. Install raceways level and square and at proper elevations. Provide adequate headroom.
- E. Complete raceway installation before starting conductor installation.
- F. Support raceways as specified in Division 16 Section "Basic Electrical Materials and Methods."
- G. Use temporary closures to prevent foreign matter from entering raceways.
- H. Protect stub-ups from damage where conduits rise through floor slabs. Arrange so curved portion of bends is not visible above the finished slab.
- I. Make bends and offsets so ID is not reduced. Keep legs of bends in the same plane and straight legs of offsets parallel, unless otherwise indicated.

SECTION 16140 - WIRING DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes receptacles, connectors, switches, and finish plates.

1.3 DEFINITIONS

- A. GFCI: Ground-fault circuit interrupter.

1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction.
- B. Comply with NEMA WD 1.
- C. Comply with NFPA 70.

1.5 COORDINATION

- A. Receptacles for Owner-Furnished Equipment: Match plug configurations.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Wiring Devices:
 - a. Bryant Electric, Inc.
 - b. Eagle Electric Manufacturing Co., Inc.
 - c. GE Company; GE Wiring Devices.
 - d. Hubbell, Inc.; Wiring Devices Div.

- e. Killark Electric Manufacturing Co.
 - f. Leviton Manufacturing Co., Inc.
 - g. Pass & Seymour/Legrand; Wiring Devices Div.
 - h. Pyle-National, Inc.; an Amphenol Co.
2. Multioutlet Assemblies:
- a. Airey-Thompson Co.
 - b. Wiremold.
3. Poke-through, Floor Service Outlets and Telephone/Power Poles:
- a. American Electric.
 - b. Hubbell, Inc.; Wiring Devices Div.
 - c. Pass & Seymour/Legrand; Wiring Devices Div.
 - d. Square D Co.
 - e. Wiremold.

2.2 RECEPTACLES

- A. Straight-Blade Receptacles: Specification grade.
- B. GFCI Receptacles: Feed-through type, with integral NEMA WD 6, Configuration 5-20R duplex receptacle arranged to protect connected downstream receptacles on same circuit. Design units for installation in a 2-3/4-inch- deep outlet box without an adapter.
- C. Isolated-Ground Receptacles: Equipment grounding contacts connected only to the green grounding screw terminal of the device with inherent electrical isolation from mounting strap.
1. Devices: Listed and labeled as isolated-ground receptacles.
 2. Isolation Method: Integral to receptacle construction and not dependent on removable parts.

2.3 SWITCHES

- A. Snap Switches: General-duty, quiet type.

2.4 WALL PLATES

- A. Single and combination types match corresponding wiring devices.
1. Plate-Securing Screws: Metal with head color to match plate finish.
 2. Material for Finished Spaces: 0.04-inch- thick, Type 302, satin-finished stainless steel.
 3. Material for Unfinished Spaces: Smooth plastic.

2.5 FLOOR SERVICE FITTINGS

- A. Type: Modular, flush-type, dual-service units suitable for wiring method used.
- B. Type: Modular, pop-up, dual-service units suitable for wiring method used.
- C. Type: Modular, above-floor, dual-service units suitable for wiring method used.
- D. Compartmentation: Barrier separates power and signal compartments.
- E. Housing Material: Die-cast aluminum, satin finished.
- F. Power Receptacle: NEMA WD 6, Configuration 5-20R, gray finish, unless otherwise indicated.
- G. Signal Outlet: Blank cover with bushed cable opening, unless otherwise indicated.

2.6 MULTIOUTLET ASSEMBLIES

- A. Components of Assemblies: Products from a single manufacturer designed for use as a complete, matching assembly of raceways and receptacles.
- B. Raceway Material: Metal, with manufacturer's standard finish.
- C. Wire: No. 12 AWG.

2.7 FINISHES

- A. Color: White, unless otherwise indicated or required by Code.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install devices and assemblies plumb and secure.
- B. Install wall plates when painting is complete.
- C. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical, and grounding terminal of receptacles on top. Group adjacent switches under single, multigang wall plates.
- D. Protect devices and assemblies during painting.
- E. Adjust locations at which floor service outlets and telephone/power service poles are installed to suit arrangement of partitions and furnishings.

3.2 IDENTIFICATION

- A. Comply with Division 16 Section "Basic Electrical Materials and Methods."
 - 1. Switches: Where three or more switches are ganged, and elsewhere as indicated, identify each switch with approved legend engraved on wall plate.
 - 2. Receptacles: Identify panelboard and circuit number from which served. Use machine-printed, pressure-sensitive, abrasion-resistant label tape on face of plate and durable wire markers or tags within outlet boxes.

3.3 CONNECTIONS

- A. Connect wiring device grounding terminal to branch-circuit equipment grounding conductor.
- B. Isolated-Ground Receptacles: Connect to isolated-ground conductor routed to designated isolated equipment ground terminal of electrical system.
- C. Tighten electrical connectors and terminals according to manufacturers published torque-tightening values. If manufacturers torque values are not indicated, use those specified in UL 486A and UL 486B.

3.4 FIELD QUALITY CONTROL

- A. Test wiring devices for proper polarity and ground continuity. Operate each device at least six times.
- B. Test GFCI operation with both local and remote fault simulations according to manufacturer's written instructions.
- C. Replace damaged or defective components.

3.5 CLEANING

- A. Internally clean devices, device outlet boxes, and enclosures. Replace stained or improperly painted wall plates or devices.

END OF SECTION 16140

SECTION 16410 - ENCLOSED SWITCHES AND CIRCUIT BREAKERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes individually mounted enclosed switches and circuit breakers used for the following:
 - 1. Service disconnecting means.
 - 2. Feeder and branch-circuit protection.
 - 3. Motor and equipment disconnecting means.

1.3 DEFINITIONS

- A. GFCI: Ground-fault circuit interrupter.
- B. RMS: Root mean square.
- C. SPDT: Single pole, double throw.

1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NEMA AB 1 and NEMA KS 1.
- C. Comply with NFPA 70.

1.5 COORDINATION

- A. Coordinate layout and installation of switches, circuit breakers, and components with other construction, including conduit, piping, equipment, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Fusible Switches:
 - a. Eaton Corp.; Cutler-Hammer Products.
 - b. General Electric Co.; Electrical Distribution & Control Division.
 - c. Siemens Energy & Automation, Inc.
 - d. Square D Co.
 2. Molded-Case Circuit Breakers:
 - a. Eaton Corp.; Cutler-Hammer Products.
 - b. General Electric Co.; Electrical Distribution & Control Division.
 - c. Klockner-Moeller.
 - d. Siemens Energy & Automation, Inc.
 - e. Square D Co.

2.2 ENCLOSED SWITCHES

- A. Enclosed, Nonfusible Switch: NEMA KS 1, Type HD, with lockable handle.
- B. Enclosed, Fusible Switch, 800 A and Smaller: NEMA KS 1, Type HD, with clips to accommodate specified fuses, lockable handle with two padlocks, and interlocked with cover in closed position.

2.3 ENCLOSED CIRCUIT BREAKERS

- A. Molded-Case Circuit Breaker: NEMA AB 1, with interrupting capacity to meet available fault currents.
1. Thermal-Magnetic Circuit Breakers: Inverse time-current element for low-level overloads, and instantaneous magnetic trip element for short circuits. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
 2. Adjustable Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
 3. Electronic Trip Unit Circuit Breakers: RMS sensing; field-replaceable rating plug; with the following field-adjustable settings:
 - a. Instantaneous trip.
 - b. Long- and short-time pickup levels.
 - c. Long- and short-time time adjustments.
 - d. Ground-fault pickup level, time delay, and I^2t response.

- B. Molded-Case Circuit-Breaker Features and Accessories: Standard frame sizes, trip ratings, and number of poles.
 - 1. Lugs: Mechanical style suitable for number, size, trip ratings, and material of conductors.
 - 2. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HACR for heating, air-conditioning, and refrigerating equipment.

2.4 ENCLOSURES

- A. NEMA AB 1 and NEMA KS 1 to meet environmental conditions of installed location.
 - 1. Outdoor Locations: NEMA 250, Type 3R.
 - 2. Other Wet or Damp Indoor Locations: NEMA 250, Type 4.

2.5 FACTORY FINISHES

- A. Manufacturer's standard prime-coat finish ready for field painting.
- B. Finish: Manufacturer's standard grey paint applied to factory-assembled and -tested enclosures before shipping.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine elements and surfaces to receive enclosed switches and circuit breakers for compliance with installation tolerances and other conditions affecting performance.
 - 1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with mounting and anchoring requirements specified in Division 16 Section "Seismic Controls for Electrical Work."
- B. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from enclosures and components.

3.3 IDENTIFICATION

- A. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs as specified in Division 16 Section "Basic Electrical Materials and Methods."

- B. Enclosure Nameplates: Label each enclosure with engraved metal or laminated-plastic nameplate mounted with corrosion-resistant screws.

3.4 CONNECTIONS

- A. Install equipment grounding connections for switches and circuit breakers with ground continuity to main electrical ground bus.
- B. Install power wiring. Install wiring between switches and circuit breakers, and control and indication devices.
- C. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.5 FIELD QUALITY CONTROL

- A. Prepare for acceptance tests as follows:
 - 1. Test insulation resistance for each enclosed switch, circuit breaker, component, and control circuit.
 - 2. Test continuity of each line- and load-side circuit.
- B. Testing: After installing enclosed switches and circuit breakers and after electrical circuitry has been energized, demonstrate product capability and compliance with requirements.
 - 1. Procedures: Perform each visual and mechanical inspection and electrical test indicated in NETA ATS, Section 7.5 for switches and Section 7.6 for molded-case circuit breakers. Certify compliance with test parameters.
 - 2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.

3.6 ADJUSTING

- A. Set field-adjustable switches and circuit-breaker trip ranges.

3.7 CLEANING

- A. On completion of installation, inspect interior and exterior of enclosures. Remove paint splatters and other spots. Vacuum dirt and debris; do not use compressed air to assist in cleaning. Repair exposed surfaces to match original finish.

END OF SECTION 16410

SECTION 16442 - PANELBOARDS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes panelboards, overcurrent protective devices, and associated auxiliary equipment rated 600 V and less for the following types:
 - 1. Lighting and appliance branch-circuit panelboards.
 - 2. Distribution panelboards.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with NESCO Inc. for furnishing the electrical switchgear specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders, and further information, call NESCO, Inc. at (800) 244-6980.

1.4 DEFINITIONS

- A. EMI: Electromagnetic interference.
- B. GFCI: Ground-fault circuit interrupter.
- C. RFI: Radio-frequency interference.
- D. RMS: Root mean square.
- E. SPDT: Single pole, double throw.

1.5 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NEMA PB 1.
- C. Comply with NFPA 70.

1.6 COORDINATION

- A. Coordinate layout and installation of panelboards and components with other construction that penetrates walls or is supported by them, including electrical and other types of equipment, raceways, piping, and encumbrances to workspace clearance requirements.

1.7 EXTRA MATERIALS

- A. Keys: Six spares of each type of panelboard cabinet lock.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Panelboards, Overcurrent Protective Devices, Controllers, Contactors, and Accessories:
 - a. General Electric Co.; Electrical Distribution & Control Div.

2.2 FABRICATION AND FEATURES

- A. Enclosures: Surface-mounted cabinets. NEMA PB 1, Type 1, to meet environmental conditions at installed location.
- B. Hinged Front Cover: Entire front trim hinged to box and with standard door within hinged trim cover.
- C. Finish: Manufacturer's standard enamel finish over corrosion-resistant treatment or primer coat.
- D. Directory Card: With transparent protective cover, mounted inside metal frame, inside panelboard door.
- E. Bus: Tin-plated aluminum.
- F. Main and Neutral Lugs: Mechanical type suitable for use with conductor material.
- G. Equipment Ground Bus: Adequate for feeder and branch-circuit equipment ground conductors; bonded to box.

- H. Isolated Equipment Ground Bus: Adequate for branch-circuit equipment ground conductors; insulated from box.
- I. Feed-through Lugs: Mechanical type suitable for use with conductor material. Locate at opposite end of bus from incoming lugs or main device.

2.3 PANELBOARD SHORT-CIRCUIT RATING

- A. MDP fully rated to interrupt symmetrical short-circuit current available at terminals.
- B. Branch panelboards to be series rated.

2.4 LIGHTING AND APPLIANCE BRANCH-CIRCUIT PANELBOARDS

- A. Branch Overcurrent Protective Devices: Bolt-on circuit breakers, replaceable without disturbing adjacent units.
- B. Doors: Front mounted with concealed hinges; secured with flush latch with tumbler lock; keyed alike.

2.5 DISTRIBUTION PANELBOARDS

- A. Doors: Front mounted, except omit in fused-switch panelboards; secured with vault-type latch with tumbler lock; keyed alike.
- B. Main Overcurrent Protective Devices: Circuit breaker.
- C. Branch overcurrent protective devices shall be one of the following:
 - 1. For Circuit-Breaker Frame Sizes 125 A and Smaller: Bolt-on circuit breakers.
 - 2. For Circuit-Breaker Frame Sizes Larger Than 125 A: Bolt-on circuit breakers.

2.6 OVERCURRENT PROTECTIVE DEVICES

- A. Molded-Case Circuit Breaker: NEMA AB 1, with interrupting capacity to meet available fault currents.
 - 1. Thermal-Magnetic Circuit Breakers: Inverse time-current element for low-level overloads, and instantaneous magnetic trip element for short circuits. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
 - 2. Electronic Trip Unit Circuit Breakers: RMS sensing; field-replaceable rating plug; with the following field-adjustable settings:
 - a. Instantaneous trip.
 - b. Long- and short-time pickup levels.
 - c. Long- and short-time time adjustments.
 - d. Ground-fault pickup level, time delay, and I^2t response.

- B. Molded-Case Circuit-Breaker Features and Accessories. Standard frame sizes, trip ratings, and number of poles.
 - 1. Lugs: Mechanical style, suitable for number, size, trip ratings, and material of conductors.
 - 2. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HACR for heating, air-conditioning, and refrigerating equipment.

2.7 CONTROLLERS

- A. Motor Controllers: NEMA ICS 2, Class A combination controller equipped for panelboard mounting and including the following accessories:
 - 1. Melting-alloy overload relay.
 - 2. Indicating lights.
 - 3. Seal-in contact.
 - 4. Two (2) convertible auxiliary contacts.
 - 5. Push buttons.
- B. Contactors: NEMA ICS 2, Class A combination controller equipped for panelboard mounting and including the following accessories:
 - 1. Individual control-power transformers.
 - 2. Fuses for control-power transformers.
 - 3. Indicating lights.
 - 4. Seal-in contact.
 - 5. Four (4) convertible auxiliary contacts.
 - 6. Push buttons.
 - 7. Selector switches.
- C. Controller Disconnect Switches: Fused switch and interlocked with controller.
 - 1. Auxiliary Contacts: Integral with disconnect switches to de-energize external control-power source.

2.8 ACCESSORY COMPONENTS AND FEATURES

- A. Accessory Set: Tools and miscellaneous items required for overcurrent protective device test, inspection, maintenance, and operation.
- B. Portable Test Set: To test functions of solid-state trip devices without removal from panelboard.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install panelboards and accessories according to NEMA PB 1.1.
- B. Mounting Heights: Top of trim 74 inches above finished floor, unless otherwise indicated.
- C. Mounting: Plumb and rigid without distortion of box. Mount recessed panelboards with fronts uniformly flush with wall finish.
- D. Circuit Directory: Create a directory to indicate installed circuit loads after balancing panelboard loads. Obtain approval before installing. Use a computer or typewriter to create directory; handwritten directories are not acceptable.
- E. Install filler plates in unused spaces.
- F. Provision for Future Circuits at Flush Panelboards: Stub four 1-inch empty conduits from panelboard into accessible ceiling space or space designated to be ceiling space in the future. Stub four 1-inch empty conduits into raised floor space or below slab not on grade.
- G. Wiring in Panelboard Gutters: Arrange conductors into groups and bundle and wrap with wire ties after completing load balancing.

3.2 IDENTIFICATION

- A. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs as specified in Division 16 Section "Basic Electrical Materials and Methods."
- B. Panelboard Nameplates: Label each panelboard with engraved metal or laminated-plastic nameplate mounted with corrosion-resistant screws.

3.3 CONNECTIONS

- A. Install equipment grounding connections for panelboards with ground continuity to main electrical ground bus.
- B. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.4 FIELD QUALITY CONTROL

- A. Prepare for acceptance tests as follows:

1. Test insulation resistance for each panelboard bus, component, connecting supply, feeder, and control circuit.
 2. Test continuity of each circuit.
- B. Testing: After installing panelboards and after electrical circuitry has been energized, demonstrate product capability and compliance with requirements.
1. Procedures: Perform each visual and mechanical inspection and electrical test indicated in NETA ATS, Section 7.5 for switches and Section 7.6 for molded-case circuit breakers. Certify compliance with test parameters.
 2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
- C. Balancing Loads: After Substantial Completion, but not more than 60 days after Final Acceptance, measure load balancing and make circuit changes as follows:
1. Measure as directed during period of normal system loading.
 2. Perform load-balancing circuit changes outside normal occupancy/working schedule of the facility and at time directed. Avoid disrupting critical 24-hour services such as fax machines and on-line data-processing, computing, transmitting, and receiving equipment.
 3. After circuit changes, recheck loads during normal load period. Record all load readings before and after changes and submit test records.
 4. Tolerance: Difference exceeding 20 percent between phase loads, within a panelboard, is not acceptable. Rebalance and recheck as necessary to meet this minimum requirement.

3.5 ADJUSTING

- A. Set field-adjustable switches and circuit-breaker trip ranges.

3.6 CLEANING

- A. On completion of installation, inspect interior and exterior of panelboards. Remove paint splatters and other spots. Vacuum dirt and debris; do not use compressed air to assist in cleaning. Repair exposed surfaces to match original finish.

END OF SECTION 16442

SECTION 16511 - INTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes interior lighting fixtures, lighting fixtures mounted on exterior building surfaces, lamps, ballasts, emergency lighting units, and accessories.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with Wiedenbach – Brown Co., Inc. for furnishing the interior lighting specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders, and further information, call Wiedenbach – Brown Co., Inc @ (888) 230-1569.

1.4 QUALITY ASSURANCE

- A. Fixtures, Emergency Lighting Units, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction.
- B. Comply with NFPA 70.
- C. NFPA 101 Compliance: Comply with visibility and luminance requirements for exit signs.

1.5 COORDINATION

- A. Fixtures, Mounting Hardware, and Trim: Coordinate layout and installation of lighting fixtures with ceiling system and other construction.

1.6 WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.

- B. Special Warranty for Batteries: Written warranty, executed by manufacturer agreeing to replace rechargeable batteries that fail in materials or workmanship within specified warranty period.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the products indicated in the Interior Lighting Fixture Schedule at the end of Part 3.
- B. Products: Subject to compliance with requirements, provide one of the products indicated for each designation in the Interior Lighting Fixture Schedule at the end of Part 3.

2.2 FIXTURES AND FIXTURE COMPONENTS, GENERAL

- A. Metal Parts: Free from burrs, sharp corners, and edges.
- B. Sheet Metal Components: Steel, unless otherwise indicated. Form and support to prevent warping and sagging.
- C. Doors, Frames, and Other Internal Access: Smooth operating, free from light leakage under operating conditions, and arranged to permit relamping without use of tools. Arrange doors, frames, lenses, diffusers, and other pieces to prevent accidental falling during relamping and when secured in operating position.
- D. Reflecting Surfaces: Minimum reflectance as follows, unless otherwise indicated:
 - 1. White Surfaces: 85 percent.
 - 2. Specular Surfaces: 83 percent.
 - 3. Diffusing Specular Surfaces: 75 percent.
 - 4. Laminated Silver Metallized Film: 90 percent.
- E. Lenses, Diffusers, Covers, and Globes: 100 percent virgin acrylic plastic or annealed crystal glass, unless otherwise indicated.
 - 1. Plastic: High resistance to yellowing and other changes due to aging, exposure to heat, and ultraviolet radiation.
 - 2. Lens Thickness: 0.125 inch minimum, unless greater thickness is indicated.

2.3 FLUORESCENT LAMP BALLASTS

- A. General Requirements: Unless otherwise indicated, features include the following:
 - 1. Designed for type and quantity of lamps indicated at full light output.
 - 2. Total Harmonic Distortion Rating: Less than 10 percent.

SECTION 16511 - INTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes interior lighting fixtures, lighting fixtures mounted on exterior building surfaces, lamps, ballasts, emergency lighting units, and accessories.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with Wiedenbach – Brown Co., Inc. for furnishing the interior lighting specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders, and further information, call Wiedenbach – Brown Co., Inc @ (888) 230-1569.

1.4 QUALITY ASSURANCE

- A. Fixtures, Emergency Lighting Units, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction.
- B. Comply with NFPA 70.
- C. NFPA 101 Compliance: Comply with visibility and luminance requirements for exit signs.

1.5 COORDINATION

- A. Fixtures, Mounting Hardware, and Trim: Coordinate layout and installation of lighting fixtures with ceiling system and other construction.

1.6 WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.

- B. Special Warranty for Batteries: Written warranty, executed by manufacturer agreeing to replace rechargeable batteries that fail in materials or workmanship within specified warranty period.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the products indicated in the Interior Lighting Fixture Schedule at the end of Part 3.
- B. Products: Subject to compliance with requirements, provide one of the products indicated for each designation in the Interior Lighting Fixture Schedule at the end of Part 3.

2.2 FIXTURES AND FIXTURE COMPONENTS, GENERAL

- A. Metal Parts: Free from burrs, sharp corners, and edges.
- B. Sheet Metal Components: Steel, unless otherwise indicated. Form and support to prevent warping and sagging.
- C. Doors, Frames, and Other Internal Access: Smooth operating, free from light leakage under operating conditions, and arranged to permit relamping without use of tools. Arrange doors, frames, lenses, diffusers, and other pieces to prevent accidental falling during relamping and when secured in operating position.
- D. Reflecting Surfaces: Minimum reflectance as follows, unless otherwise indicated:
 - 1. White Surfaces: 85 percent.
 - 2. Specular Surfaces: 83 percent.
 - 3. Diffusing Specular Surfaces: 75 percent.
 - 4. Laminated Silver Metallized Film: 90 percent.
- E. Lenses, Diffusers, Covers, and Globes: 100 percent virgin acrylic plastic or annealed crystal glass, unless otherwise indicated.
 - 1. Plastic: High resistance to yellowing and other changes due to aging, exposure to heat, and ultraviolet radiation.
 - 2. Lens Thickness: 0.125 inch minimum, unless greater thickness is indicated.

2.3 FLUORESCENT LAMP BALLASTS

- A. General Requirements: Unless otherwise indicated, features include the following:
 - 1. Designed for type and quantity of lamps indicated at full light output.
 - 2. Total Harmonic Distortion Rating: Less than 10 percent.

- C. Noncompact Fluorescent Lamp Life: Rated average is 20,000 hours at 3 hours per start when used on rapid-start circuits.
- D. Metal-Halide Color Temperature and Minimum Color-Rendering Index: 3600 K and 70 CRI, unless otherwise indicated.

2.8 FINISHES

- A. Fixtures: Manufacturer's standard, unless otherwise indicated.
 - 1. Paint Finish: Applied over corrosion-resistant treatment or primer, free of defects.
 - 2. Metallic Finish: Corrosion resistant.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Fixtures: Set level, plumb, and square with ceiling and walls, and secure according to manufacturer's written instructions and approved submittal materials. Install lamps in each fixture.
- B. Support for Fixtures in or on Grid-Type Suspended Ceilings: Use grid for support.
 - 1. Install a minimum of four ceiling support system rods or wires for each fixture. Locate not more than 6 inches from fixture corners.
 - 2. Support Clips: Fasten to fixtures and to ceiling grid members at or near each fixture corner.
 - 3. Fixtures of Sizes Less Than Ceiling Grid: Arrange as indicated on reflected ceiling plans or center in acoustical panel, and support fixtures independently with at least two 3/4-inch metal channels spanning and secured to ceiling tees.
- C. Suspended Fixture Support: As follows:
 - 1. Pendants and Rods: Where longer than 48 inches, brace to limit swinging.
 - 2. Stem-Mounted, Single-Unit Fixtures: Suspend with twin-stem hangers.

3.2 CONNECTIONS

- A. Ground equipment.
 - 1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.3 FIELD QUALITY CONTROL

- A. Inspect each installed fixture for damage. Replace damaged fixtures and components.
- B. Advance Notice: Give dates and times for field tests.
- C. Provide instruments to make and record test results.
- D. Tests: As follows:
 - 1. Verify normal operation of each fixture after installation.
 - 2. Emergency Lighting: Interrupt electrical supply to demonstrate proper operation.
 - 3. Verify normal transfer to battery source and retransfer to normal.
 - 4. Report results in writing.
- E. Malfunctioning Fixtures and Components: Replace or repair, then retest. Repeat procedure until units operate properly.
- F. Corrosive Fixtures: Replace during warranty period.

3.4 CLEANING AND ADJUSTING

- A. Clean fixtures internally and externally after installation. Use methods and materials recommended by manufacturer.
- B. Adjust aimable fixtures to provide required light intensities.

3.5 INTERIOR LIGHTING FIXTURE SCHEDULE

- A. Refer to Drawings.

END OF SECTION 16511

SECTION 16521 - EXTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes exterior lighting units with luminaires, lamps, ballasts, poles/support structures, and accessories.

1.3 NATIONAL ACCOUNTS

- A. CVS Pharmacy has entered into a national account agreement with Wiendenbach-Brown Co., Inc. for furnishing the exterior lighting specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders, and further information, call Wiendenbach-Brown Co., Inc. at (888) 230-1569.

1.4 SITE PHOTOMETRIC

- A. Thru CVS Pharmacy's national account agreement with Wiendenbach-Brown Co., Inc., use the following consultants to prepare the photometric requirements for this section.
 1. Primary Consultant: Hubbell Lighting Inc., contact Arnel Uy at (864) 327-3124.
 2. Secondary Consultant: Cooper Lighting, contact Joe Robertson at (770) 486-4582.

1.5 DEFINITIONS

- A. Lighting Unit: A luminaire or an assembly of luminaires complete with a common support, including pole, post, or other structure, and mounting and support accessories.
- B. Luminaire (Light Fixture): A complete lighting device consisting of lamp(s) and ballast(s), when applicable, together with parts designed to distribute light, to position and protect lamps, and to connect lamps to power supply.

1.6 QUALITY ASSURANCE

- A. Luminaires and Accessories: Listed and labeled as defined in NFPA 70, Article 100, for their indicated use, location, and installation conditions by a testing agency acceptable to authorities having jurisdiction

- B. Comply with ANSI C2.
- C. Comply with NFPA 70.
- D. FM Compliance: Units for hazardous locations shall be listed and labeled for indicated class and division of hazard by FM.

1.7 DELIVERY, STORAGE, AND HANDLING OF POLES

- A. Package aluminum poles for shipping according to ASTM B 660.
- B. Store poles on decay-resistant treated skids at least 12 inches above grade and vegetation. Support poles to prevent distortion and arrange to provide free air circulation.
- C. Handle wood poles so they will not be damaged. Do not use pointed tools that can indent surface more than 1/4 inch deep. Do not apply tools to section of poles below ground-line.
- D. Retain factory-applied pole wrappings on fiberglass poles until just before pole installation. Handle poles with web fabric straps.
- E. Retain factory-applied pole wrappings on metal poles until just before pole installation. For poles with nonmetallic finishes, handle with web fabric straps.

1.8 WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Special Warranty: Written warranty, signed by manufacturer and Installer agreeing to replace external parts of luminaires and poles exhibiting a failure of finish as specified below. This warranty is in addition to, and not a limitation of, other rights and remedies Owner may have under requirements of the Contract Documents.
 - 1. Protection of Metal from Corrosion: Warranty against perforation or erosion of finish due to weathering.
 - 2. Color Retention: Warranty against fading, staining, and chalking due to effects of weather and solar radiation.
 - 3. Warranty Period: Manufacturer's standard, but not less than three years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the products indicated in the Exterior Lighting Unit Schedule at the end of Part 3.
- B. Products: Subject to compliance with requirements, provide one of the products indicated for each designation in the Exterior Lighting Unit Schedule at the end of Part 3.

2.2 LUMINAIRES

- A. Comply with IESNA RP-8 for parameters of lateral light distribution patterns indicated for luminaires.
- B. Metal Parts: Free from burrs, sharp corners, and edges.
- C. Sheet Metal Components: Corrosion-resistant aluminum, unless otherwise indicated. Form and support to prevent warping and sagging.
- D. Housings: Rigidly formed, weather- and light-tight enclosures that will not warp, sag, or deform in use. Provide filter/breather for enclosed luminaires.
- E. Doors, Frames, and Other Internal Access: Smooth operating, free from light leakage under operating conditions, and arranged to permit relamping without use of tools. Arrange doors, frames, lenses, diffusers, and other pieces to prevent accidental falling during relamping and when secured in operating position. Provide for door removal for cleaning or replacing lens. Arrange to disconnect ballast when door opens.
- F. Exposed Hardware Material: Stainless steel.
- G. Plastic Parts: High resistance to yellowing and other changes due to aging, exposure to heat, and ultraviolet radiation.
- H. Reflecting Surfaces: Minimum reflectance as follows, unless otherwise indicated:
 - 1. White Surfaces: 85 percent.
 - 2. Specular Surfaces: 83 percent.
 - 3. Diffusing Specular Surfaces: 75 percent.
- I. Lenses and Refractors: Materials as indicated. Use heat- and aging-resistant, resilient gaskets to seal and cushion lens and refractor in luminaire doors.
- J. Photoelectric Relays: As follows:
 - 1. Contact Relays: Single throw, arranged to fail in the on position and factory set to turn light unit on at 1.5 to 3 fc and off at 4.5 to 10 fc with 15-second minimum time delay.
 - 2. Relay Mounting: In luminaire housing.
- K. High-Intensity-Discharge Ballasts: Comply with ANSI C82.4. Constant wattage autotransformer or regulating high-power-factor type, unless otherwise indicated.

1. Ballast Fuses: One in each ungrounded supply conductor. Voltage and current ratings as recommended by ballast manufacturer.
 2. Single-Lamp Ballasts: Minimum starting temperature of minus 40 deg C.
 3. Open-circuit operation will not reduce average life.
 4. High-Pressure Sodium Ballasts: Equip with a solid-state igniter/starter having an average life in pulsing mode of 10,000 hours at an igniter/starter case temperature of 90 deg C.
 5. Noise: Uniformly quiet operation, with a noise rating of B or better.
 6. Surge Protector: Hard-wired unit external to ballast case, rated for supply circuit line voltage, and encapsulated for circuit and moisture protection. Three-stage surge protection with three suppression modes provides 330-V peak clamping, line to neutral, line to ground, and neutral to ground. Pulse life is 500 3KA-8x20 microsecond impulses, and response time is less than 1 nanosecond. Internal fuse takes device off line on failure and lights a light-emitting diode failure indicator.
- L. Lamps: Comply with the standard of the ANSI C78 series that is applicable to each type of lamp. Provide luminaires with indicated lamps of designated type, characteristics, and wattage. Where a lamp is not indicated for a luminaire, provide medium wattage lamp recommended by manufacturer for luminaire.
1. Metal-Halide Color Temperature and Minimum Color-Rendering Index: 3600 K and 70 CRI, unless otherwise indicated.

2.3 LUMINAIRE SUPPORT COMPONENTS

- A. Description: Comply with AASHTO LTS-3 for pole or other support structures, brackets, arms, appurtenances, base, and anchorage and foundation.
- B. Wind-Load Strength of Total Support Assembly: Adequate to carry support assembly plus luminaires at indicated heights above grade without failure, permanent deflection, or whipping in steady winds of 100 mph with a gust factor of 1.3. Support assembly includes pole or other support structures, brackets, arms, appurtenances, base, and anchorage and foundation.
- C. Finish: Match finish of pole/support structure for arm, bracket, and tenon mount materials.
- D. Mountings, Fasteners, and Appurtenances: Corrosion-resistant items compatible with support components.
1. Materials: Will not cause galvanic action at contact points.
 2. Mountings: Correctly position luminaire to provide indicated light distribution.
 3. Anchor Bolts, Nuts, and Washers: Hot-dip galvanized after fabrication unless stainless-steel items are indicated.
 4. Anchor-Bolt Template: Plywood or steel.
- E. Pole/Support Structure Bases: Anchor type with hold-down or anchor bolts, leveling nuts, and bolt covers.

- F. Pole Bases: Hinged-anchor type with hold-down or anchor bolts, leveling nuts, and bolt covers.
- G. Pole Bases: Embedded type with underground cable entry.
- H. Steel Poles: Tubing complying with ASTM A 500, Grade B, carbon steel with a minimum yield of 46,000 psig; one-piece construction up to 40 feet in length with access handhole in pole wall.
- I. Laminated-Wood Poles: Pressure treat with pentachlorophenol preservative and have a concealed raceway path connected to access handhole.
- J. Metal Pole Brackets: Match pole metal. Provide cantilever brackets without underbrace, in sizes and styles indicated, with straight tubular end section to accommodate luminaire.
- K. Concrete for Pole Foundations: Comply with Division 3 Section "Cast-in-Place Concrete."
 - 1. Design Strength: 3000-psig, 28-day compressive strength.

2.4 FINISHES

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Steel: Grind welds and polish surfaces to a smooth, even finish.
 - 1. Galvanized Finish: Hot-dip galvanize after fabrication to comply with ASTM A 123.
 - 2. Surface Preparation: Clean surfaces to comply with SSPC-SP 1, "Solvent Cleaning," to remove dirt, oil, grease, and other contaminants that could impair paint bond. Remove mill scale and rust, if present, from uncoated steel, complying with SSPC-SP 5/NACE No. 1, "White Metal Blast Cleaning," or SSPC-SP 8, "Pickling."
 - 3. Interior: Apply one coat of bituminous paint on interior of pole, or otherwise treat to prevent corrosion.
 - 4. Polyurethane Enamel: Manufacturer's standard finish consisting of one or more coats of primer and two finish coats of high-gloss, high-build polyurethane enamel.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Concrete Foundations: Construct according to Division 3 Section "Cast-in-Place Concrete."

1. Comply with details for reinforcement and for anchor bolts, nuts, and washers. Verify anchor-bolt templates by comparing with actual pole bases furnished.
 2. Finish for Parts Exposed to View: Trowel and rub smooth. Comply with Division 3 Section "Cast-in-Place Concrete" for exposed finish.
- B. Embedded Poles: Set poles to indicated depth, but not less than one-sixth of pole length below finish grade. Dig holes large enough to permit use of tampers the full depth of hole. Backfill in 6-inch layers and thoroughly tamp each layer so compaction of backfill is equal to or greater than that of undisturbed earth.
- C. Install poles as follows:
1. Use web fabric slings (not chain or cable) to raise and set poles.
 2. Mount pole to foundation with leveling nuts, and tighten top nuts to torque level recommended by pole manufacturer.
 3. Secure poles level, plumb, and square.
 4. Grout void between pole base and foundation. Use nonshrinking or expanding concrete grout firmly packed in entire void space.
 5. Use a short piece of 1/2-inch- diameter pipe to make a drain hole through grout. Arrange to drain condensation from interior of pole.
- D. Luminaire Attachment: Fasten to indicated structural supports.

3.2 CONNECTIONS

A. Ground equipment.

1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.3 FIELD QUALITY CONTROL

- A. Inspect each installed unit for damage. Replace damaged units.
- B. Advance Notice: Give dates and times for field tests.
- C. Provide instruments to make and record test results.
- D. Tests and Observations: Verify normal operation of lighting units after installing luminaires and energizing circuits with normal power source, and as follows:
- E. Prepare a written report of tests, inspections, observations and verifications indicating and interpreting results.
- F. Malfunctioning Fixtures and Components: Replace or repair, then retest. Repeat procedure until units operate properly.

3.4 CLEANING AND ADJUSTING

- A. Clean units after installation. Use methods and materials recommended by manufacturer.

END OF SECTION 16521

SECTION 16700 – ELECTRONIC DETECTION SYSTEM

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes electronic article surveillance (EAS) and point of sale (POS) security system.
- B. System shall detect unscanned merchandise.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with Checkpoint for furnishing the electronic detection system specified in this section. Complete installation shall be by manufacturer. The General Contractor is responsible for contacting the manufacturer for pricing quotations, placing orders, and further information, call Checkpoint at (401) 770-3920.

1.4 QUALITY ASSURANCE

- A. Standards: Comply with applicable industry standards.
- B. Installer: Complete installation shall be by manufacturer.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Protect materials in accordance with manufacturer's instructions and recommendations.

PART 2 - PRODUCTS

2.1 ELECTRONIC DETECTION SYSTEM

- A. Provide system including the following components:
 - 1. Set of two (2) pedestals consisting of one (1) primary pedestal with electronics and light and one (1) secondary pedestal with remote antenna.
 - 2. One (1) deactivator pad per POS register.
 - 3. One (1) deactivator chassis per POS register.

- B. Miscellaneous Materials: Provide as required and as standard with the manufacturer for the Owner for the units required.

PART 3 - EXECUTION

3.1 INSPECTION

- A. Inspect installation areas for a clean and level floor space; and materials for electronic connections. Areas shall be broom clean, free of construction debris.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Complete installation to be performed by the manufacturer.
- B. Coordinate installation with other components of the work.
 - 1. Repair abraded areas of factory applied finishes.

3.3 CLEANING

- A. Clean surfaces promptly after installation. Exercise care to avoid damage to the finish. Remove excess dirt and other substances.

3.4 PROTECTION

- A. Initiate and maintain protection and other precautions required through the remainder of the construction period to ensure that electronic detection system will be free of damage or deterioration at the time of substantial completion.

3.5 DEMONSTRATION

- A. Startup Services: Engage a factory-authorized service representative to perform startup services and to train Owner's maintenance personnel as specified below:
 - 1. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - 2. Train Owner's maintenance personnel on procedures and schedules related to startup and shutdown, troubleshooting, servicing, and preventive maintenance.
 - 3. Review data in maintenance manuals. Refer to Division 1 Section "Closeout Procedures".
 - 4. Schedule training with Owner, through Architect, with at least seven (7) day's advance notice.

SECTION 16700 – ELECTRONIC DETECTION SYSTEM

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes electronic article surveillance (EAS) and point of sale (POS) security system.
- B. System shall detect unscanned merchandise.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with Checkpoint for furnishing the electronic detection system specified in this section. Complete installation shall be by manufacturer. The General Contractor is responsible for contacting the manufacturer for pricing quotations, placing orders, and further information, call Checkpoint at (401) 770-3920.

1.4 QUALITY ASSURANCE

- A. Standards: Comply with applicable industry standards.
- B. Installer: Complete installation shall be by manufacturer.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Protect materials in accordance with manufacturer's instructions and recommendations.

PART 2 - PRODUCTS

2.1 ELECTRONIC DETECTION SYSTEM

- A. Provide system including the following components:
 - 1. Set of two (2) pedestals consisting of one (1) primary pedestal with electronics and light and one (1) secondary pedestal with remote antenna.
 - 2. One (1) deactivator pad per POS register.
 - 3. One (1) deactivator chassis per POS register.

- B. Miscellaneous Materials: Provide as required and as standard with the manufacturer for the Owner for the units required.

PART 3 - EXECUTION

3.1 INSPECTION

- A. Inspect installation areas for a clean and level floor space; and materials for electronic connections. Areas shall be broom clean, free of construction debris.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Complete installation to be performed by the manufacturer.
- B. Coordinate installation with other components of the work.
 - 1. Repair abraded areas of factory applied finishes.

3.3 CLEANING

- A. Clean surfaces promptly after installation. Exercise care to avoid damage to the finish. Remove excess dirt and other substances.

3.4 PROTECTION

- A. Initiate and maintain protection and other precautions required through the remainder of the construction period to ensure that electronic detection system will be free of damage or deterioration at the time of substantial completion.

3.5 DEMONSTRATION

- A. Startup Services: Engage a factory-authorized service representative to perform startup services and to train Owner's maintenance personnel as specified below:
 - 1. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - 2. Train Owner's maintenance personnel on procedures and schedules related to startup and shutdown, troubleshooting, servicing, and preventive maintenance.
 - 3. Review data in maintenance manuals. Refer to Division 1 Section "Closeout Procedures".
 - 4. Schedule training with Owner, through Architect, with at least seven (7) day's advance notice.

SECTION 16710 – BURGLAR ALARM SYSTEM

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes a burglar alarm system.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with the manufacturers listed below for furnishing the burglar alarm system specified in this section. Complete installation shall be by the contractor. The General Contractor is responsible for contacting the manufacturer for pricing quotations, placing orders, and further information, please call the appropriate manufacturer for the area the store is located in.

1. Vector Security at (603) 329-7221
Area: Michigan Only.
2. AFA Protective System at (617) 312-5598
Areas: AL, CT, DC, DE, GA, MA, ME, MD, NC, NH, NY, PA, RI, SC, VA, VT, WV
3. BCI Technologies at (817) 649-0686
Areas: IN, IL, KS, KY, LA, MO, MS, MT, OH, OK, TN
4. MRJ Security at (978) 372-3489
Areas: MN
5. Integrated Security Solutions at (800) 505-0868
Area: New Jersey Only.

1.4 QUALITY ASSURANCE

- A. Standards: Comply with applicable industry standards.
- B. Installer Qualifications: Engage an experienced installer who is an authorized representative of the manufacturer for installation of the type of burglar alarm system required for this Project.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Protect materials in accordance with manufacturer's instructions and recommendations.

PART 2 - PRODUCTS

2.1 BURGLAR ALARM SYSTEM

- A. Provide components including, but not necessarily limited to, electronics, hard wire, alarms, alarm panels, key pads, batteries, contacts, detectors/sensors, recorders and miscellaneous accessories, as required and as standard with the manufacturer for the Owner.
- B. Verify Security System/Monitoring for NY and PA with CVS loss prevention department.

PART 3 - EXECUTION

3.1 INSPECTION

- A. Inspect installation areas for readiness of system including materials for electrical wiring and connections.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with manufacturer's specifications and recommendations for a complete installation.
- B. Provide proper support as standard with the manufacturer and anchor securely to surrounding construction with approved fasteners.
- C. Coordinate installation with other components of the work.
 - 1. Repair abraded areas of factory applied finishes.

3.3 CLEANING

- A. Clean surfaces promptly after installation. Exercise care to avoid damage to the finish. Remove excess dirt and other substances.

3.4 PROTECTION

- A. Initiate and maintain protection and other precautions required through the remainder of the construction period to ensure that, except for normal weathering, burglar alarm system will be free of damage or deterioration at the time of Substantial Completion.

3.5 TESTING

- A. Engage a factory-authorized service representative to perform testing and to train Owner's maintenance personnel as specified below:
 - 1. Test and adjust controls and equipment. Replace damaged and malfunctioning controls and equipment.
 - 2. Train Owner's maintenance personnel on procedures and schedules related to startup, troubleshooting, servicing, and preventive maintenance.

3. Review data in maintenance manuals. Refer to Division 1 Section "Closeout Procedures".
4. Schedule training with Owner, through Architect, with at least seven (7) day's advance notice.

END OF SECTION 16710

3. Review data in maintenance manuals. Refer to Division 1 Section "Closeout Procedures".
4. Schedule training with Owner, through Architect, with at least seven (7) day's advance notice.

END OF SECTION 16710

SECTION 16740 – COMMUNICATIONS EQUIPMENT

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes communications system.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with the manufacturers below. Complete installation shall be by the contractor. The general contractor shall call the appropriate manufacturer in the area the store is located in for all pricing quotations, placing orders and further information.
 - 1. CrossCom National at (847) 421-2764
Areas: DC, DE, MD, MS, NJ, NM, NY, TN, MO and WV.
 - 2. EGC Inc. at (888) 834-2462
Area: CT, MA, ME, NH, RI and VT.
 - 3. Intelex/Comm-Works at (317) 428-1266
Areas: GA, IA, IL, IN, KY, MI, NC, PR and WA.
 - 4. Net at (608) 827-7949 ext. 5300
Areas: AL, AR, CO, ID, KS, LA, MN, MT, ND, NE, OH, OK, OR, PA, SC, SD, UT, VA, WI and WY.

1.4 QUALITY ASSURANCE

- A. Standards: Comply with applicable industry standards.
- B. Installer Qualifications: Contractor shall enter onto a contract with the national account manufacturer listed above for complete installation of the communications system.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Protect materials in accordance with manufacturer's instructions and recommendations.

PART 2 - PRODUCTS

2.1 COMMUNICATIONS EQUIPMENT

- A. Provide components including, but not necessarily limited to, electronics, hardware/software, cabling, and miscellaneous accessories, as required and as standard with the manufacturer for the Owner.

PART 3 - EXECUTION

3.1 INSPECTION

- A. Inspect installation areas for readiness of system including materials for electrical wiring and connections.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with manufacturer's specifications and recommendations for a complete installation.
- B. Provide proper support as standard with the manufacturer and anchor securely to surrounding construction with approved fasteners.
- C. Coordinate installation with other components of the work.
 - 1. Repair abraded areas of factory applied finishes.

3.3 CLEANING

- A. Clean surfaces promptly after installation. Exercise care to avoid damage to the finish. Remove excess dirt and other substances.

3.4 PROTECTION

- A. Initiate and maintain protection and other precautions required through the remainder of the construction period to ensure that, except for normal weathering, communication system will be free of damage or deterioration at the time of Substantial Completion.

3.5 TESTING

- A. Engage a factory-authorized service representative to perform testing and to train Owner's maintenance personnel as specified below:
 - 1. Test and adjust controls and equipment. Replace damaged and malfunctioning controls and equipment.

2. Train Owner's maintenance personnel on procedures and schedules related to startup, troubleshooting, servicing, and preventive maintenance.
3. Review data in maintenance manuals. Refer to Division 1 Section "Closeout Procedures".
4. Schedule training with Owner, through Architect, with at least seven (7) day's advance notice.

END OF SECTION 16740



SECTION 16750 – ENERGY MANAGEMENT SYSTEM

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the Energy Management System.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with CPC for furnishing the Energy Management System specified in this section. For pricing quotations, placing orders, and further information, call CPC at (800) 829-2724.

1.4 QUALITY ASSURANCE

- A. Standards: Comply with applicable industry standards.
- B. Installer Qualifications: Contractor shall enter into a contract with CPC for complete installation of the Energy Management System.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Protect materials in accordance with manufacturer's instructions and recommendations.

PART 2 - PRODUCTS

2.1 ENERGY MANAGEMENT SYSTEM

- A. Provide components including, but not necessarily limited to, Controllers, Sensors, EMS Panel, control boards, and miscellaneous accessories, as required and as standard with the manufacturer for the Owner.

PART 3 - EXECUTION

3.1 INSPECTION

- A. Inspect installation areas for readiness of system including materials for electrical wiring and connections.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with manufacturer's specifications and recommendations for a complete installation.
- B. Provide proper support as standard with the manufacturer and anchor securely to surrounding construction with approved fasteners.
- C. Coordinate installation with other components of the work.
 - 1. Repair abraded areas of factory applied finishes.

3.3 CLEANING

- A. Clean surfaces promptly after installation. Exercise care to avoid damage to the finish. Remove excess dirt and other substances.

3.4 PROTECTION

- A. Initiate and maintain protection and other precautions required through the remainder of the construction period to ensure that, public address and music system will be free of damage or deterioration at the time of Substantial Completion.

3.5 TESTING

- A. Engage a factory-authorized service representative to perform testing and to train Owner's maintenance personnel as specified below:
 - 1. Test and adjust controls and equipment. Replace damaged and malfunctioning controls and equipment.
 - 2. Train Owner's maintenance personnel on procedures and schedules related to startup, troubleshooting, servicing, and preventive maintenance.
 - 3. Review data in maintenance manuals. Refer to Division 1 Section "Closeout Procedures".
 - 4. Schedule training with Owner, through Architect, with at least seven (7) day's advance notice.

END OF SECTION 16750

7

(

()

10

11

12

13

14