

CHURCH AVENUE
109B-F-4

CLIFF ISLAND

NOTATION

CITY
BUREAU



APPLICATION FOR PERMIT

Class of Building or Type of Structure Third Class

Permit No. 1220

Portland, Maine, October 20, 1942

To the INSPECTOR OF BUILDINGS, PORTLAND, ME.

The undersigned hereby applies for a permit to erect alter install the following building structure equipment in accordance with the Laws of the State of Maine, the Building Code of the City of Portland, plans and specifications, if any, submitted herewith and the following specifications:

Location Church Road, Cliff Island Within Fire Limits? no Dist. to

Owner's or Lessee's name and address Lulie L. Cushing, Cliff Island Telephone _____

Contractor's name and address Owner Telephone _____

Architect _____ Plans filed no No. of sheets _____

Proposed use of building Dwelling No. families 1

Other buildings on same lot fish house

Estimated cost \$ 70. Fee \$ 5.

Description of Present Building to be Altered

Memorandum from Department of Building Inspection, Portland, Maine
 Church Road, Cliff Island, Lulie L. Cushing-- Construction of enclosure on existing rear platform of dwelling-- 10/22/42

To Owner:

Our clerk who wrote application for permit for you says that you said the existing platform to be enclosed is now supported on solid ledge, although the application shows a foundations of flat rocks. If the platform is not supported on solid ledge then you are required by law and are bound by your application to provide cedar posts, concrete piers or stone laid in mortar piers under the sills of the platform which should be at least 4x6, posts or piers to extend at least 4 feet below the surface of the ground or to solid ledge if encountered at a less depth. It is also required by law that the outside walls of the enclosure consist of a frame of no less than 2x4 studs, set vertically no more than 16 inches from center to center and running one length from sill to underside of plate which is to be doubled 2x4, and the corner posts to be at least doubled 2x4.

Please be governed accordingly or return the permit and refrain from starting the work.

(Signed) Warren McDonald
 Inspector of Buildings

the heating contractor.

Details of New Work

Is any plumbing work involved in this work? no

Is any electrical work involved in this work? no Height average grade to top of plate _____

Size, front 7' depth 7' No. stories 1 Height average grade to highest point of roof 2'

To be erected on solid or filled land? solid earth or rock? rock

Material of foundation flat rocks Thickness, top _____ bottom _____ cellar _____

Material of underpinning _____ Height _____ Thickness _____

Kind of roof flat Rise per foot 3" Roof covering asphalt roofing Class C Under Laps

No. of chimneys _____ Material of chimneys _____ of lining _____

Kind of heat _____ Type of fuel _____ Is gas fitting involved? _____

Framing lumber--Kind spruce Dressed or full size? crossed

Corner posts 2x4 Sills 2x6 existing Girt or ledger board? _____ Size _____

Material columns under girders _____ Size _____ Max. on centers _____

Studs (outside walls and carrying partitions) 2x4-16" O. C. Girders 6x8 or larger. Bridging in every floor and flat roof span over 8 feet. Sills and corner posts all one piece in cross section.

Joists and rafters: 1st floor 2x6 2nd _____ 3rd _____ roof 2x6

On centers: 1st floor 16" 2nd _____ 3rd _____ roof 24"

Maximum span: 1st floor 7' 2nd _____ 3rd _____ roof 7'

If one story building with masonry walls, thickness of walls? _____ height? _____

If a Garage

No. cars now accommodated on same lot _____ to be accommodated _____

Total number commercial cars to be accommodated _____

Will automobile repairing be done other than minor repairs to cars habitually stored in proposed building? _____

Miscellaneous

Will above work require removal or disturbing of any shade tree on a public street? no

Will there be in charge of the above work a person competent to see that the State and City requirements pertaining thereto are observed? yes

Signature of owner Alfred E. Cushing

INSPECTION COPY

12/10/42

Permit No. 47/1220

Location Church Rd. Cliff Dr.

Owner Lulu L. Cusler

Date of permit 10/22/42

Notif closing-in

Aspn. closing-in 1094-F-1

Final Notif

Final Inspn.

Cert. of Occupancy is. used

NOTES

(The following section contains faint, illegible handwritten notes on a lined background.)