

07) 874-8703, FAX: 874-8716

Permit No.:

940756

Permit Issued:

Zone: CBL:

Zoning Approval:

Special Zone or Reviews:

- ☐ Shoreland
☐ Wetland
☐ Flood Zone
☐ Subdivision
☐ Site Plan: ☐ major ☐ minor ☐ minor ☐ minor

Zoning Appeal

- ☐ Variance
☐ Miscellaneous
☐ Conditional Use
☐ Interpretation
☐ Approved
☐ Denied

Historic Preservation

- ☒ Not in District or Landmark
☒ Does Not Require Review
☐ Requires Review

Action:

- ☐ Approved
☐ Approved with Conditions
☐ Denied

Date: 3/20/01

CEO DISTRICT

4

MR. CARROLL

COMMENTS

Done w/out Insp.

Inspection Record

Type

Date

Foundation: _____
Framing: _____
Plumbing: _____
Final: _____
Other: _____

BUILDING PERMIT REPORT

Address 1900 Congress St Date 21/July/90
Reason for Permit To Construct a 12'x12' Storage
shed Bldg. Owner: Christ Church Evangelical
Contractor: Owner
Permit Applicant: 1
Approval: */

CONDITION OF APPROVAL:

1. Before concrete for foundation is placed, approvals from ~~Public Works and~~ Inspection Services must be obtained. (A 24 hour notice is required prior to inspection).
2. Precaution must be taken to protect concrete from freezing.
3. It is strongly recommended that a registered land surveyor check all foundation forms before concrete is placed. This is done to verify that the proper setbacks are maintained.
4. All vertical openings shall be enclosed with construction having a fire rating of at least one (1) hr., including fire doors with selfclosers.
5. Each apartment shall have access to (2) separate, remote and approved means of egress. A single exit is acceptable when it exits directly from the apartment to the building exterior with no communications to other apartment units.
6. The boiler shall be protected by enclosing with one (1) hour fire rated construction including fire doors and ceiling, or by providing automatic extinguishment. Sprinkler piping serving not more than six sprinklers may be connected to a domestic water supply system having a capacity sufficient to provide 0.15 gallons per minute, per square foot of floor throughout the entire area. An INDICATING shut-off valve shall be installed in an accessible location between the sprinkler and the connection to the domestic water supply. Minimum pipe size shall be 3/4 inch copper or 1 inch steel. Maximum coverage area of a residential sprinkler is 144 square feet per sprinkler.
7. Every sleeping room below the fourth story in buildings of Use Groups R and I-1 shall have at least one operable window or exterior door approved for emergency egress or rescue. The units must be operable from the inside opening without the use of special knowledge or separate tools. Where windows are provided as a means of egress or rescue, they shall have a sill height not more than 44 inches (1118 mm) above the floor. All egress or rescue windows from sleeping room must have minimum net clear opening height dimension shall be 24 inches (610 mm). The minimum net clear opening width dimension shall be 20 inches (508 mm), and a minimum net clear opening of 5.7 sq.ft.

8. All single and multiple station smoke detectors shall be of an approved type and shall be installed in accordance with the provisions of the building code 919.3.2 (BOCA National Building Code 1993), and NFPA 101 Chapter 18 & 19. (smoke detectors shall be installed and maintained at the following locations):

1. In the immediate vicinity of bedrooms
2. In all bedrooms
3. In each story within a dwelling unit, including basements

9. Private garages located beneath habitable rooms in occupancies in Use Group R-1, R-2, R-3 or I-1 shall be separated from adjacent interior spaces by Fire Partitions and floor/ceiling assembly which are constructed with not less than 1-hour fire resisting rating. Private garages attached side-by-side to rooms in the above occupancies shall be completely separated from the interior spaces and the attic area by means of 1/2 inch gypsum board or the equivalent applied to the garage side. (Chapter 4 section 407.0 of the BOCA/1993).

10. Guardrails & Handrails - A guardrail system is a system of building components located near the open sides of elevated walking surfaces for the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Group 42", except Use Group R which is 36". In occupancies in Use Group A, B, H-4, I1, I-2 M and R and public garages and open parking structures, guards shall have balusters or be of solid material such that a sphere with a diameter of 4" cannot pass through any opening. Guards shall not have a decorative pattern that would provide a ladder effect.

11. All exit signs, lights and means of egress lighting shall be done in accordance with Chapter 10, section & subsections 1023.8 & 1024.0 of the City's building code (The BOCA National Building Code/1993).

12. Stair construction in Use Group R-3, R-4 is a minimum of 9" tread and 8-1/4" maximum rise.


13. Headroom in habitable space is a minimum of 7'6".

14. The minimum headroom in all parts of a stairway shall not be less than 80 inches.

15. All construction and demolition debris must be disposed at the City's authorized reclamation site. The fee rate is attached. Proof of such disposal must be furnished to the office of Inspection Services before final certificate or occupancy is issued or demolition permit is granted.

16. Section 25-135 of the Municipal Code for the City of Portland states: "No person or utility shall be granted a permit to excavate or open any street or sidewalk from the time of November 15 of each year to April 15 of the following year".

17. The builder of a facility to which Section 4594-C of the Maine State Human Rights Act, Title 5 MRSA refers, shall obtain a certification from a design professional that the plans of the facility meet the standards of construction required by this section. Prior to commencing construction of the facility, the builder shall submit certification to the Division of Inspection Services.


P. Samuel Hoffses
Chief of Inspections

/dmm 01/14/94(redo w/additions)

Snow Plowing

Snow Removal



DAVIS WOODWORKING, INC.

BUILDING AND REMODELING

235 ALLEN AVENUE

PORTLAND, MAINE 04103

SHOP

971 BRIGHTON AVENUE

PORTLAND, MAINE 04102

774-2045 • 797-3368 • 78.-7319

PRICE LIST

Regular Sheds

4' X 8'.....	\$ 450.00	10' X 10'.....	\$1325.00
6' X 6'.....	595.00	10' X 12'.....	1050.00
6' X 8'.....	745.00	10' X 14'.....	1365.00
6' X 10'.....	850.00	12' X 14'.....	1925.00
6' X 12'.....	910.00		

8' X 8'.....	\$ 850.00
8' X 10'.....	1025.00
8' X 12'.....	1325.00
8' X 14'.....	1650.00
8' X 16'.....	1795.00

Blocks for sheds
extra \$3.00 each

Vinyl Sheds

4' X 8'.....	\$ 700.00	10' X 10'.....	\$ 1725.00
6' X 6'.....	845.00	10' X 12'.....	1825.00
6' X 8'.....	995.00	12' X 12'.....	2250.00
6' X 10'.....	1025.00	12' X 14'.....	2450.00
6' X 12'.....	1160.00		

8' X 8'.....	\$ 1150.00
8' X 10'.....	1275.00
8' X 12'.....	1475.00
8' X 14'.....	1675.00
8' X 16'.....	1775.00

P.T. lumber extra
for floors

All sheds are 2 X 4 walls and 2 X 6 floors.

All sheds are pre-fab.

All sheds delivered and set-up to 25 miles free.

Roof is shingled on site. Your choice of color.

We also build garages on site.

Lawn and Patio

4' round table with 3 benches.....	\$ 95.00
5' round table with 4 benches.....	160.00
4' octagon with 4 benches.....	150.00
5' octagon with 4 benches.....	170.00
Double settee.....	60.00
Single bench 4'.....	25.00
Single chair.....	32.50
Lounge chairs.....Reg. \$65.00P.T.	95.00
Adirondack chair.....	60.00

Picnic Tables

Tot table - 48" L.....	\$ 45.00
4' table.....	60.00
6' table.....	75.00
6' table with separate benches.....	85.00
8' table.....	85.00
8' table with separate benches.....	105.00
10' table.....	107.50
12' table.....	125.00

P.T. + 1/2 cost of table.

Tables extra wide add \$25.00

Delivery \$10.00 under 10 miles for tables

Cedar swings \$325.00

Also - building and remodeling, roofing, snow plowing and snow removal
Prices are subject to change

Permit - Take out -
^{site}
~~shot~~ location sketch
Construction Plans -
Bill

Blocks
→

Chief -
Bldg inspector - Sam Hoffses
8704

874-8300
M.I. 1040
2nd Floor (10-50-76)
P. Cox 1
bldg

12 x 12 SHED

Floor Joists 2" x 6" 16" on C
Roof Joists 2" x 4" 16" on C
Floor S/S PVY BRX
Roof SHINGLES 3 TAB ASPHALT
WALL BR 2" x 4" 20" APART

1828.00

