

November 23, 1981

Mr. James G. LaRose
84 Abby Lane
Portland, Me.

Dear Mr. LaRose:

Your building permit to construct a two (2) story duplex, 24'x40' at lots 13 and 1/2 of 14 Berkshire Street is being issued with the following requirements.

1. A 4" cast iron sewer and house drain must run full size. After house drain raises 6" above cellar floor, the material may be changed to schedule 40 PVC but remain 4" through roof.
2. A rodding wye must be placed in line within 1 ft. after sewer enters building and also at base of stack.
3. 6" void space between units must be firestopped at each floor level or filled with a non combustible material.
4. Walls, partitions and floor ceiling construction separating tenant units from each other or from public or service areas shall have a sound transmission door (STC) of not less than forty-five (45) for airborne noise.

If you have any questions on this matter, please call.

Sincerely,

P.S. Hoffsen
Chief of Inspection Services

PSH:k